CONTRACT

PART C1: AGREEMENTS AND CONTRACT DATA PART C2: PRICING DATA PART C3: SCOPE OF WORK PART C4: SITE INFORMATION

CONTRACT

| TABLE OF CONTENTS | Page | Colour |
|---|------|--------|
| PART C1: AGREEMENTS AND CONTRACT DATA | | |
| C1.1: FORM OF OFFER AND ACCEPTANCE | C3 | Yellow |
| C1.1.1: OFFER | C3 | Yellow |
| C1.1.2: ACCEPTANCE | C4 | Yellow |
| C1.1.3: SCHEDULE OF DEVIATIONS | C5 | Yellow |
| C1.2: CONTRACT DATA | C7 | Yellow |
| C1.2.1: CONDITIONS OF CONTRACT | C7 | Yellow |
| C1.2.2: DATA PROVIDED BY THE EMPLOYER | C10 | Yellow |
| C1.2.3: DATA PROVIDED BY THE CONTRACTOR | C15 | Yellow |
| C1.3: PERFORMANCE GUARANTEE | C16 | White |
| C1.4: AGREEMENT IN TERMS OF SECTION 37(2) OF THE OCCUPATIONAL HEALTH AND SAFETY ACT NO. 85 OF 1993 | C19 | White |
| C1.5: RETENTION MONEY GUARANTEE | C21 | White |
| | 621 | white |
| C1.6: TRANSFER OF RIGHTS | C23 | White |
| PART C2: PRICING DATA | | |
| C2.1: PRICING ASSUMPTIONS | C24 | Yellow |
| C2.2: BILL OF QUANTITIES | C28 | Yellow |
| | | |
| PART C3: SCOPE OF WORK | | |
| TABLE OF CONTENTS | C64 | Blue |
| C3.1: STANDARD SPECIFICATIONS | C65 | Blue |
| C3.2: PROJECT SPECIFICATIONS | C65 | Blue |
| C3.3: PARTICULAR SPECIFICATIONS | C89 | Blue |
| PART C4: SITE INFORMATION | | |
| C4.1: LOCALITY PLAN | C225 | Green |
| C4.2: EXAMPLE OF CONTRACT SIGNBOARD DETAILS | C226 | Green |
| C4.3: EXISTING SERVICES REPORT | C227 | Green |
| C4.4: CONDITIONS ON SITE: MATERIALS INFORMATION | C228 | Green |
| C4.5: TRAFFIC INFORMATION | C233 | Green |
| | | |
| ANNEXURE A: GUIDELINES FOR CONSTRUCTION AND | | |
| MAINTENANCE PROJECTS DURING COVID-19 LOCKDOWN | C235 | White |

PART C1: AGREEMENTS AND CONTRACT DATA

C1.1: FORM OF OFFER AND ACCEPTANCE

C1.1.1: OFFER

The Employer, identified in the Acceptance signature block, has solicited offers to enter into a contract in respect of the following works:

CONTRACT NO. ZNB00124/00000/00/HOD/INF/20/T: UPGRADING OF MAIN ROAD P8/3 FROM GRAVEL TO BLACKTOP BETWEEN KM 17.560 AND KM 24.221 IN THE PIETERMARITZBURG REGION.

The Tenderer, identified in the Offer signature block below, has examined the documents listed in the Tender Data and addenda thereto as listed in the Tender Schedules, and by submitting this Offer has accepted the Conditions of Tender.

By the representative of the Tenderer, deemed to be duly authorised, signing this part of this Form of Offer and Acceptance, the Tenderer offers to perform all of the obligations and liabilities of the Contractor under the Contract including compliance with all its terms and conditions according to their true intent and meaning for an amount to be determined in accordance with the Conditions of Contract identified in the Contract Data.

The offered total of the prices inclusive of Value Added Tax is:

This Offer may be accepted by the Employer by signing the Acceptance part of this Form of Offer and Acceptance and returning one copy of this document to the Tenderer before the end of the period of validity stated in the Tender Data, whereupon the Tenderer becomes the party named as the Contractor in the Conditions of Contract identified in the Contract Data.

| Signa | ture: (of person authorised to sign the tender) |
|--------|---|
| Name | : (of signatory in capitals) |
| Capac | ity: (of signatory) |
| Name | of Tenderer: (organisation) |
| | Address: |
| | Telephone number: |
| Witnes | 88: |
| withe | |
| | Signature: |
| | |

[Failure of a Tenderer to sign this form will invalidate the tender]

This form is to be completed by the Employer only

C1.1.2: ACCEPTANCE

By signing this part of the Form of Offer and Acceptance, the Employer, identified below, accepts the Tenderer's Offer. In consideration thereof, the Employer shall pay the Contractor the amount due in accordance with the Conditions of Contract identified in the Contract Data. Acceptance of the Tenderer's Offer shall form an agreement between the Employer and the Tenderer upon the terms and conditions contained in this Agreement and in the Contract, that is the subject of this Agreement.

The terms of the contract are contained in

- Part C1 Agreements and Contract Data (which includes this Agreement)
- Part C2 Pricing Data
- Part C3 Scope of Work
- Part C4 Site Information

and the schedules, forms, drawings and documents or parts thereof, which may be incorporated by reference into Parts C1 to C4 above.

Deviations from and amendments to the documents listed in the Tender Data and any addenda thereto listed in the Tender Schedules as well as any changes to the terms of the Offer agreed by the Tenderer and the Employer during this process of offer and acceptance, are contained in the Schedule of Deviations attached to and forming part of this Agreement. No amendments to or deviations from said documents are valid unless contained in this Schedule, which must be duly signed by the authorised representatives of both parties.

The Tenderer shall within two weeks after receiving a completed copy of this Agreement, including the Schedule of Deviations (if any), contact the Employer's Agent (whose details are given in the Contract Data) to arrange the delivery of any bonds, guarantees, proof of insurance and any other documentation to be provided in terms of the Conditions of Contract identified in the Contract Data at, or just after, the date this Agreement comes into effect. Failure to fulfil any of these obligations in accordance with those terms shall constitute a repudiation of this Agreement.

Notwithstanding anything contained herein, this Agreement comes into effect on the date when the Tenderer receives one fully completed original copy of this document, including the Schedule of Deviations (if any). Unless the Tenderer (now Contractor) within five days of the date of such receipt notifies the Employer in writing of any reason why he cannot accept the contents of this Agreement, this Agreement shall constitute a binding contract between the parties.

| Signature: | |
|-------------|--------------------------------|
| Name: (in a | capitals) |
| | |
| Name of E | mployer: (organisation) |
| Ad | dress: |
| | |
| Witness: | Signature: Name: (in capitals) |
| Date: | |

This form is to be completed by the Employer and the successful tenderer only, upon acceptance of the successful tenderer's offer

C1.1.3: SCHEDULE OF DEVIATIONS

The extent of deviations from the tender documents issued by the Employer prior to the tender closing date is limited to those permitted in terms of the Tender Data and the Conditions of Tender.

A Tenderer's covering letter shall not be included in the final contract document. Should any matter in such letter, which constitutes a deviation as aforesaid, become the subject of agreement reached during the process of offer and acceptance, the outcome of such agreement shall be recorded here.

Any other matter arising from the process of offer and acceptance either as a confirmation, clarification or change to the tender documents and which it is agreed by the Parties becomes an obligation of the contract shall also be recorded here.

Any change or addition to the tender documents arising from the above agreement and recorded here shall also be incorporated into the final draft of the Contract.

| 1 | Subject: | |
|---|----------|--|
| | Details: | |
| | | |
| | | |
| 2 | Subject: | |
| | Details: | |
| | | |
| | | |
| 3 | Subject: | |
| | Details: | |
| | | |
| | | |
| 4 | Subject: | |
| | Details: | |
| | | |
| | | |
| 5 | Subject: | |
| | Details: | |
| | | |

By the duly authorised representatives signing this Schedule of Deviations, the Employer and the Tenderer agree to and accept the foregoing Schedule of Deviations as the only deviations from and amendments to

the documents listed in the Tender Data and addenda thereto as listed in the Tender Schedules, as well as any confirmation, clarification or change to the terms of the offer agreed by the Tenderer and the Employer during this process of offer and acceptance.

It is expressly agreed that no other matter whether in writing, oral communication or implied during the period between the issue of the tender documents and the receipt by the Tenderer of a completed signed copy of this Agreement shall have any meaning or effect in the contract between the parties arising from this Agreement.

FOR THE TENDERER:

| Signature: | |
|--------------|-----------------------------------|
| Name: | |
| Capacity: | |
| Tenderer: (/ | Name and address of organisation) |
| Witness: | |
| Signature: | |
| Name: | |
| Date: | |

FOR THE EMPLOYER:

| Signature: | |
|-------------|-----------------------------------|
| Name: | |
| Capacity: | |
| Employer: (| Name and address of organisation) |
| Witness: | |
| Signature: | |
| Name: | |
| Date: | |

C1.2: CONTRACT DATA

C1.2.1: CONDITIONS OF CONTRACT

C1.2.1.1 GENERAL CONDITIONS OF CONTRACT

This Contract will be based on the 'General Conditions of Contract for Construction Works, Third Edition (2015)', issued by the South African Institution of Civil Engineering (abbreviated title: 'GCC 2015').

It is agreed that the only variations from the GCC 2015 are those set out hereafter under "C1.2.1.2 SPECIAL CONDITIONS OF CONTRACT".

C1.2.1.2 SPECIAL CONDITIONS OF CONTRACT

C1.2.1.2.1 GENERAL

These Special Conditions of Contract (SCC) form an integral part of the Contract. The Special Conditions of Contract shall amplify, modify or supersede, as the case may be, the GCC 2015 to the extent specified below, and shall take precedence and shall govern.

The clauses of the Special Conditions of Contract hereafter are numbered "SCC" followed in each case by the number of the applicable clause or subclause in the GCC 2015, and the applicable heading, or (where a new special condition that has no relation to the existing clauses is introduced) by a number that follows after the last clause number in the GCC 2015, and an appropriate heading.

C1.2.1.2.2 AMENDMENTS TO THE GCC 2015

SCC 1.1 Definitions

SCC 1.1.1.14: *delete* "Commencement Date" *in the definition and substitute* "date of commencement of the Works".

Add the following to the end of Clause 1.1:

- "SCC 1.1.1.35 "Construction Manager" means the person approved of in writing by the Employer's Agent, as the Contractor's representative on Site.
- SCC 1.1.1.36 "Targeted Enterprise" means an enterprise as defined in Part F: Small Contractor Development of section C3.3 Particular Specifications in Part C3: Scope of Work.
- SCC 1.1.1.37 "Targeted Labour" means labour as defined in Part F: Small Contractor Development of section C3.3 Particular Specifications in Part C3: Scope of Work."

SCC 4.1.1 Extent of Contractor's obligations

Add the following new paragraphs to the end of Clause 4.1.1:

"If the Contractor fails to achieve the monetary value of the contract participation goal stated in the Contract Data for local labour content in terms of Part E: Expanded Public Works Programme of section C3.3 Particular Specifications in Part C3: Scope of Work, the Contractor shall be liable to the Employer for a sum calculated in accordance with the Contract Data and the aforementioned Scope of Work as a penalty for such underachievement.

If the Contractor fails to achieve the monetary value of the contract participation goal stated in the Contract Data for contract participation by Targeted Enterprises in terms of Part F: Small Contractor Development of section C3.3 Particular Specifications in Part C3: Scope of Work, the Contractor shall be liable to the Employer for a sum calculated in accordance with the Contract Data and the aforementioned Scope of Work as a penalty for such underachievement."

SCC 4.4.2 Subcontractor to be approved

Add the following to Clause 4.4.2:

"The Contractor shall comply with the subcontracting restrictions stated in the Contract Data."

SCC 4.10.1 Engagement of employees

Add the following to Clause 4.10.1:

"The contractor shall pay rates and wages, and observe conditions of labour, which are not lower than those established for the trade or industry where the work is carried out, as stated in the Contract Data."

SCC 5.3.1 Commencement of the Works

Delete the first sentence of Clause 5.3.1 and substitute the following:

"The Employer's Agent shall give the Contractor not less than 7 days' notice of the date of commencement of the Works on which date the Contractor is instructed to commence carrying out the Works, save as may be otherwise provided in the Contract, or be legally or physically impossible. The date of commencement of the Works shall be within the period after the Commencement Date stated in the Contract Data."

SCC 5.3.3 Time to instruct commencement of the Works

Delete Clause 5.3.3.

SCC 5.14.4 Certification of Completion

Insert the following in the first sentence after the words "has been duly completed,":

"and the Contractor has submitted the information stated in the Contract Data,".

SCC 5.14.6 Occupation by the Employer

Add the following to Clause 5.14.6:

"The use of any completed roadway or parts of the Works, whether for unhindered use by the public or for accommodation of traffic, while other parts are being constructed, shall not constitute occupation of the Works by the Employer."

SCC 6.2.1 Delivery of security

In the last two lines of Clause 6.2.1, delete the words "the type of security for the due performance of the Contract, as selected in the Contract Data" and replace them with the words "a fixed performance guarantee as security for the due performance of the Contract in accordance with the Contract Data Part A: Data Provided by the Employer".

Delete the entirety of Clause 6.2.2 and replace it with the following:

"SCC 6.2.2 Contractor failing to provide security

If the Contractor fails to provide the required fixed performance guarantee within the time period stated in the Contract Data, or if the performance guarantee shall differ substantially from the pro forma, it shall legally be deemed that the Contractor has selected a security of ten per cent retention of the value of the Works without limiting the Employer's right to terminate the Contract in terms of Clause 9.2."

SCC 6.2.3 Validity of performance guarantee

Delete the entirety of the first sentence of Clause 6.2.3 and replace it with the following:

"The Contractor shall ensure that the performance guarantee remains valid and enforceable until the Certificate of Completion is issued."

SCC 6.10.4 Delivery, dissatisfaction with and payment of payment certificate

Delete "within 28 days" in the third sentence and substitute "within 30 days".

SCC 6.10.8 Contractor's completion statement

Delete "within 28 days" in the third sentence and substitute "within 30 days".

SCC 6.10.9 Final Payment Certificate

Delete "within 28 days" in the second sentence and substitute "within 30 days".

SCC 10.1.5 Employer's Agent's ruling on Contractor's Claim

Delete "within 28 days" in the first sentence and in Clause 10.1.5.1, and substitute "within 56 days".

C1.2.2: DATA PROVIDED BY THE EMPLOYER

The following contract specific data are applicable to this contract.

| CLAUSE | CONTRACT SPECIFIC DATA PROVIDED BY THE EMPLOYER | | | | |
|--------------|---|---|--|--|--|
| 1. | GENERAL | | | | |
| 1.1.1.13 | The Defects Liability Period is 12 months. | | | | |
| SCC 1.1.1.14 | The time for achieving Practical Completion is 18 months from the date of commencement of the Works, including non-working days and special non-working days. | | | | |
| 1.1.1.26 | Pricing Strategy: The Contract is to be a Re-measurement Contract. | | | | |
| 1.1.1.15 | Name of Employer: Province of KwaZulu-Natal represented by Head of Department: Department of Transport | | | | |
| 1.2.1.2 | Address of Employer: | | | | |
| | Physical: | Postal: | | | |
| | 172 Burger Street Pietermaritzburg 3201 | Private Bag X9043 Pietermaritzburg 3200 | | | |
| | E-thulani.sambo@kzntransport.gov.za | | | | |
| | Telephone No: (033) 355 8600 | Fax No: (033) 342 4082 | | | |
| 1.1.1.16 | Name of Employer's Agent: Ilifa Af | rica Engineers (Pty) Ltd | | | |
| 1.2.1.2 | Address of Employer's Agent: | | | | |
| | Physical: | Postal: | | | |
| | 35A Piet Retief Street Harrismith 9880 | P.O. Box 802 Harrismith 9880 | | | |
| | E-mail: <u>harrismith@ilifa.biz</u> | | | | |
| | Telephone No: (058) 622 1297 | Fax No: (058) 623 0827 | | | |
| 3. | EMPLOYER'S AGENT | | | | |
| 3.2.3 | The Employer's Agent is required to obtain the specific approval of the Employer before executing any of his functions or duties according to the following Clauses: | | | | |
| | SCC 5.3.1: Give the Contractor notice of the commencement date of the Works. 6.3.1: Order any work as a Variation Order. 6.3.1: Order any work which requires the utilisation of the provision for contingencies in the Contract Sum. 6.3.1: Order any work which requires the Contract Price to exceed the Contract Sum. 10.1.5: Ruling on a Contractor's claim. | | | | |

| CLAUSE | CONTRACT SPECIFIC DATA PROVIDED BY THE EMPLOYER | | |
|---------------------|---|--|--|
| 4. | CONTRACTOR'S GENERAL OBLIGATIONS | | |
| | | | |
| SCC 4.1.1 | The contract participation goal for local labour content is 8.6%. | | |
| | The penalty for failing to achieve the monetary value of the above target set by the Employer for local labour content in terms of Part E: Expanded Public Works Programme of section C3.3 Particular Specifications in Part C3: Scope of Work, is 5% of the monetary value by which the achieved monetary value falls short of the target monetary value. | | |
| | The contract participation goal for Targeted Enterprises is 30.0%. | | |
| | The penalty for failing to achieve the monetary value of the above target set by the Employer for contract participation by Targeted Enterprises in terms of Part F: Small Contractor Development of section C3.3 Particular Specifications in Part C3: Scope of Work, is 5% of the monetary value by which the achieved monetary value falls short of the target monetary value. | | |
| SCC 4.4.2 | In accordance with regulation 12.(3) of the Preferential Procurement Regulations, 2017, the Contractor may not subcontract more than 25% of the value of the contract to any other enterprise that does not have an equal or higher B-BBEE status level of contributor than the Contractor, unless the contract is subcontracted to an EME that has the capability and ability to execute the subcontract. | | |
| SCC 4.10.1 | The Contractor and his subcontractors shall be registered with the Bargaining Council for the Civil Engineering Industry, and comply with the wage rates and conditions of labour agreed by the Bargaining Council for the Civil Engineering Industry, except where a specific industry publishes its own wage rates and conditions of labour. | | |
| | The wage rates and conditions of labour employed under the Expanded Public Works Programme, shall comply with the Ministerial Determination 4, issued in terms of the Basic Conditions of Employment Act of 1997 by the Minister of Labour in Government Notice No. R347 of 4 May 2012. | | |
| 5. | TIME AND RELATED MATTERS | | |
| SCC 5.3.1 and 5.3.2 | The date of commencement of the Works shall be within 28 days, or 56 days if a construction work permit is required, after the Commencement Date. | | |
| | The following documentation shall be submitted within <u>14 days</u> of the Commencement Date by the Contractor before commencing to carry out the Works: (i) Health and Safety Plan (refer to Clause 4.3); (ii) Form C1.4 'Agreement in terms of Section 37(2) of the Occupational Health and Safety Act No. 85 of 1993' to be signed by the Contractor and the Employer (refer to Clause 4.3); (iii) Proof of registration and good standing with the compensation fund or with a licensed compensation insurer as contemplated in the Compensation for Occupational Injuries and Diseases Act, 1993 (Act No. 130 of 1993) (refer to Clause 4.3); (iv) Initial Programme (refer to Clause 5.6); (v) Security (refer to Clause 6.2); and (vi) Insurance (refer to Clause 8.6); | | |
| | and if the Employer is required to apply for a construction work permit to perform construction work in terms of regulation 3(1) of the Construction Regulations 2014, the following documentation shall also be submitted: | | |

| CLAUSE | CONTRACT SPECIFIC DATA PROVIDED BY THE EMPLOYER | | |
|------------|--|--|--|
| | (vii) Temporary works designer's appointment duties in terms of Regulation 6(2) as have been agreed upon plus proof of registration with ECSA [CR 3(5)(b)(iii) read with CR 5(1)(e) and CR 6(2)]; (viii) Evidence that the Principal contractor has made adequate provision for the cost of Health and Safety, i.e., bill of quantities [CR 3(5)(b)(iii) read with CR 5(1)(g)]; and (ix) Evidence that the Principal contractor has the necessary competencies to carry out construction work safely, namely, schedule of activities, relevant appointments and proofs of competency [CR 5(1)(h)]. | | |
| 5.8.1 | The non-working days are Sundays. | | |
| | The special non-working days are: (i) the statutory public holidays in terms of the Public Holidays Act; (ii) the foreseeable election days declared as a statutory public holiday; and (iii) the annual year-end shutdown period as recommended by the Bargaining Council for the Civil Engineering Industry. | | |
| 5.13.1 | The penalty for failing to complete the Works is 0,05% of the Contract Sum per day, up to a maximum limit of twenty-five thousand rand per day (R25 000,00 per day). | | |
| 5.14.1 | The requirements for achieving Practical Completion are as stated in General Conditions of Contract 2015. | | |
| SCC 5.14.4 | The Contractor shall submit the following: | | |
| | (i) evidence that the local labour has been paid, and that the Targeted Enterprise subcontractors have received all amounts due in terms of their respective subcontract agreements; and (ii) the survey and materials information which the Employer's Agent requires to complete the as-built drawings and records. | | |
| 5.16.3 | The latent defects period is 10 years. | | |
| 6. | PAYMENT AND RELATED MATTERS | | |
| SCC 6.2.1 | The security to be provided by the Contractor shall be: | | |
| | Fixed Performance Guarantee of 8% of the first One Million Rand plus 3,5% of the balance of the Contract Sum. | | |
| 6.5.1.2.3 | The percentage allowance to cover overhead charges is 10%. | | |
| 6.8.2 | The value of payment certificates issued shall be adjusted in accordance with the Contract Price Adjustment Schedule with the following data. | | |
| | The values of the coefficients for calculating the Contract Price Adjustment Factor are: | | |
| | Road works – upgrade (Schedules A, D, F and G): | | |
| | a = 0,2 $b = 0,4$ $c = 0,25$ $d = 0,15$ | | |
| | Structures (Schedule B): | | |
| | a = 0,15 $b = 0,2$ $c = 0,55$ $d = 0,1$ | | |
| | "L", "P", "M" and "F" are defined as follows: | | |

| CLAUSE | CONTRACT SPECIFIC DATA PROVIDED BY THE EMPLOYER | | |
|-----------|--|--|--|
| CLAUSE | | | |
| | "L" is the "Labour Index" and shall be the Consumer Price Index for "Geographic Indices > CPI per province > KwaZulu-Natal" as published in Table A of the Statistical Release P0141 of Statistics South Africa. | | |
| | "P" is the "Construction Equipment Index" and shall be the Construction Materials Price Index for "Plant and equipment" as published in Table 4 of the Statistical Release P0151.1 of Statistics South Africa. | | |
| | "M" is the "Materials Index" and shall be the Construction Materials Price Index as published in Table 6 of the Statistical Release P0151.1 of Statistics South Africa for: | | |
| | Road works (Schedules A, E and F): "Civil engineering material – roads, general (excluding bitumen)" | | |
| | Structures (Schedule B): "Civil engineering material – structures (excluding bitumen)" | | |
| | "F" is the "Fuel Index" and shall be the Producer Price Index for "Coke, petroleum, chemical, rubber and plastic products > Coal and petroleum products > Diesel" as published in Table 1 of the Statistical Release P0142.1 of Statistics South Africa. | | |
| | The base month is the month preceding the month of tender closure. | | |
| | Any index calculated by means of a linking factor between an old and new index, shall be rounded to one decimal place. | | |
| | Price adjustments for variations in the cost of bitumen as a special material are allowed. | | |
| 6.8.3 | Only the net bitumen content of asphalt and bituminous products shall be subject to variations in cost, and no account shall be taken of transport, emulsifiers, diluents or modifiers that may be supplied ex refinery or added later. | | |
| | The percentage advance on Plant and materials not yet built into the Permanent Works is 80%. | | |
| 6.10.1.5 | The percentage retention on the amounts due to the Contractor is 10%. | | |
| 6.10.3 | The limit of retention money is 5% of the first One Million Rand plus 1,6% of the balance of the Contract Sum excluding contingencies, contract price adjustment, and VAT. | | |
| | A retention guarantee in lieu of a cash retention is permitted. | | |
| | | | |
| 8. | RISKS AND RELATED MATTERS | | |
| 8.6.1.1.2 | The value of Plant and materials supplied by the Employer to be included in the insurance sum is <u>nil</u> . | | |
| 8.6.1.1.3 | The amount to cover professional fees for repairing or reinstatement of damage to the Works to be included in the insurance sum is <u>nil</u> . | | |
| 8.6.1.2 | Special Risks Insurance issued by SASRIA is required. | | |
| 8.6.1.3 | The limit of indemnity for liability insurance is R10 000 000,00 (ten million Rand only) for | | |

| CLAUSE | CONTRACT SPECIFIC DATA PROVIDED BY THE EMPLOYER | | |
|--------|--|--|--|
| | any single liability claim. Liability insurance shall include spread of fire risk. | | |
| 10. | CLAIMS AND DISPUTES | | |
| 10.5.2 | Disputes shall be referred to ad-hoc adjudication. | | |
| 10.5.3 | The number of Adjudication Board members to be appointed shall be one. | | |
| 10.8.1 | Unresolved disputes shall be determined by court proceedings. | | |
| | DATA WITH REFERENCE TO C3.3 PARTICULAR SPECIFICATIONS | | |
| PART F | SMALL CONTRACTOR DEVELOPMENT | | |
| F2.9 | The target area for local labour is Dr Nkosazana Dlamini-Zuma Local Municipality | | |
| | The target area for Targeted Enterprises is Dr Nkosazana Dlamini-Zuma Local Municipality | | |

C1.2.3: DATA PROVIDED BY THE CONTRACTOR

The following contract specific data are applicable to this contract.

| CLAUSE | CONTRACT SPECIFIC DATA PROVIDED BY THE CONTRACTOR | | | |
|---------|--|------|-------------------------------------|--|
| 1. | GENERAL | | | |
| 1.1.1.9 | Name of Contractor: | | | |
| 1.2.1.2 | Address of Contractor: | | | |
| | Physical: | | Postal: | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 6. | PAYMENT AND RELATED MATTERS | | | |
| 6.8.3 | The tenderer shall complete the table below with respect to each of the special materials listed. This information shall be used to calculate the variation in cost of the special materials. | | | |
| | The rates and prices for the special materials for the base month which is the month preceding the month of tender closure, shall exclude VAT but shall include all other obligatory taxes and levies. | | | |
| | The tenderer shall append to this page a letter from the supplier confirming the supply price for the net bitumen content of asphalt and bituminous products. | | | |
| | A change of supplier due to circumstances beyond the control of the Contractor may be considered, subject to the submission of supporting documentation to the Employer's Agent for valuation to calculate the difference between the rate or price of the special material entered in the table below and the equivalent rate or price actually paid by the Contractor, and for approval. | | | |
| | SPECIAL MATERIALS | UNIT | RATE OR PRICE FOR THE BASE MONTH | |
| | 35/50 penetration grade bitumen | ton | | |
| | 50/70 penetration grade bitumen | ton | | |
| | 70/100 penetration grade bitumen | ton | | |
| | Signed on behalf of the Tenderer: | | | |

C1.3: PERFORMANCE GUARANTEE

PRO FORMA

PERFORMANCE GUARANTEE

For use with the General Conditions of Contract for Construction Works, Third Edition (2015).

1. GUARANTOR DETAILS AND DEFINITIONS

"Guarantor" means:
Physical address:
"Employer" means:
"Contractor" means:
"Employer's Agent" means:
"Works" means:

"Site" means:

"Contract" means: The Agreement made in terms of the Form of Offer and Acceptance and such amendments or additions to the Contract as may be agreed in writing between the parties.

"Contract Sum" means: The accepted amount inclusive of tax of R

Amount in words:

"Guaranteed Sum" means: The maximum aggregate amount of R

Amount in words:

"Expiry Date" means: or any other later date set by the Contractor and/or Employer provided such instruction is received prior to the Expiry Date as indicated here.

2. CONTRACT DETAILS

Employer's Agent issues: Interim Payment Certificates, Final Payment Certificate and the Certificate of Completion of the Works as defined in the Contract.

3. GUARANTOR'S LIABILITY

- 3.1 The Guarantor's liability shall be limited to the amount of the Guaranteed Sum.
- 3.2 The Guarantor's period of liability shall be from and including the date on which the Performance Guarantee is signed, up to and including the Expiry Date, or the date of issue by the Employer's Agent of the Certificate of Completion of the Works, or the date of payment in full of the Guaranteed Sum, whichever occurs first.
- 3.3 The Employer's Agent and/or the Employer shall advise the Guarantor in writing of the date on which the Certificate of Completion of the Works has been issued.

4. CONDITIONS APPLICABLE TO THIS PERFORMANCE GUARANTEE

- 4.1 The Guarantor hereby acknowledges that:
- 4.1.1 Any reference in this Performance Guarantee to the Contract is made for the purpose of convenience and shall not be construed as any intention whatsoever to create an accessory obligation or any intention whatsoever to create a suretyship.
- 4.1.2 Its obligation under this Performance Guarantee is restricted to the payment of money.
- 4.2 Subject to the Guarantor's maximum liability referred to in 3.1, the Guarantor hereby undertakes to pay the Employer the sum certified upon receipt of the documents identified in 4.2.1 to 4.2.3:
- 4.2.1 A copy of a first written demand issued by the Employer to the Contractor stating that payment of a sum certified by the Employer's Agent in an Interim or Final Payment Certificate has not been made in terms of the Contract and failing such payment within seven (7) calendar days, the Employer intends to call upon the Guarantor to make payment in terms of 4.2.2;
- 4.2.2 A first written demand issued by the Employer to the Guarantor at the Guarantor's physical address with a copy to the Contractor stating that a period of seven (7) days has elapsed since the first written demand in terms of 4.2.1 and the sum certified has still not been paid;
- 4.2.3 A copy of the aforesaid payment certificate which entitles the Employer to receive payment in terms of the Contract of the sum certified in 4.2.
- 4.3 Subject to the Guarantor's maximum liability referred to in 3.1, the Guarantor undertakes to pay to the Employer the Guaranteed Sum or the full outstanding balance upon receipt of a first written demand from the Employer to the Guarantor at the Guarantor's physical address calling up this Performance Guarantee, such demand stating that:
- 4.3.1 the Contract has been terminated due to the Contractor's default and that this Performance Guarantee is called up in terms of 4.3; or
- 4.3.2 a provisional or final sequestration or liquidation court order has been granted against the Contractor and that the Performance Guarantee is called up in terms of 4.3; and
- 4.3.3 the aforesaid written demand is accompanied by a copy of the notice of termination and/or the provisional/final sequestration and/or the provisional liquidation court order.
- 4.4 It is recorded that the aggregate amount of payments required to be made by the Guarantor in terms of 4.2 and 4.3 shall not exceed the Guarantor's maximum liability in terms of 3.1.
- 4.5 Where the Guarantor has made payment in terms of 4.3, the Employer shall upon the date of issue of the Final Payment Certificate submit an expense account to the Guarantor showing how all monies received in terms of this Performance Guarantee have been expended and shall refund to the Guarantor any resulting surplus. All monies refunded to the Guarantor in terms of this Performance Guarantee shall bear interest at the prime overdraft rate of the Employer's bank compounded monthly and calculated from the date payment was made by the Guarantor to the Employer until the date of refund.
- 4.6 Payment by the Guarantor in terms of 4.2 or 4.3 shall be made within seven (7) calendar days upon receipt of the first written demand to the Guarantor.
- 4.7 Payment by the Guarantor in terms of 4.3 will only be made against the return of the original Performance Guarantee by the Employer.
- 4.8 The Employer shall have the absolute right to arrange his affairs with the Contractor in any manner which the Employer may consider fit and the Guarantor shall not have the right to claim his release from this Performance Guarantee on account of any conduct alleged to be prejudicial to the Guarantor.

- 4.9 The Guarantor chooses the physical address as stated above for the service of all notices for all purposes in connection herewith.
- 4.10 This Performance Guarantee is neither negotiable nor transferable and shall expire in terms of 3.2, where after no claims will be considered by the Guarantor. The original of this Guarantee shall be returned to the Guarantor after it has expired.
- 4.11 This Performance Guarantee, with the required demand notices in terms of 4.2 or 4.3, shall be regarded as a liquid document for the purposes of obtaining a court order.
- 4.12 Where this Performance Guarantee is issued in the Republic of South Africa the Guarantor hereby consents in terms of Section 45 of the Magistrates' Courts Act No 32 of 1944, as amended, to the jurisdiction of the Magistrate's Court of any district having jurisdiction in terms of Section 28 of the said Act, notwithstanding that the amount of the claim may exceed the jurisdiction of the Magistrate's Court.

| Signed at |
|---------------------------|
| Date |
| Guarantor's signatory (1) |
| Capacity |
| Guarantor's signatory (2) |
| Capacity |
| Witness signatory (1) |
| Witness signatory (2) |

C1.4: AGREEMENT IN TERMS OF SECTION 37(2) OF THE OCCUPATIONAL HEALTH AND SAFETY ACT NO. 85 OF 1993

THIS AGREEMENT is made between The Province of KwaZulu-Natal represented by Head of Department: Department of Transport

(hereinafter called the EMPLOYER) of the one part, herein represented by:

| in his capacity as: |
|---|
| AND: |
| (hereinafter called the CONTRACTOR) of the other part, herein represented by: |
| in his capacity as: |

duly authorised to sign on behalf of the Contractor.

WHEREAS the CONTRACTOR is the Mandatary of the EMPLOYER in consequence of an agreement between the CONTRACTOR and the EMPLOYER in respect of:

CONTRACT NO. ZNB00124/00000/00/HOD/INF/20/T: UPGRADING OF MAIN ROAD P8/3 FROM GRAVEL TO BLACKTOP BETWEEN KM 17.560 AND KM 24.221 IN THE PIETERMARITZBURG REGION.

for the construction, completion and maintenance of the works;

AND WHEREAS the EMPLOYER and the CONTRACTOR have agreed to enter into an agreement in terms of the provisions of Section 37(2) of the Occupational Health and Safety Act No 85 of 1993, as amended by the Occupational Health and Safety Amendment Act No 181 of 1993 (hereinafter referred to as the ACT);

NOW THEREFORE the parties agree as follows:

- 1. The CONTRACTOR undertakes to acquaint the appropriate officials and employees of the CONTRACTOR with all relevant provisions of the ACT and the regulations promulgated in terms thereof.
- 2. The CONTRACTOR undertakes to fully comply with all relevant duties, obligations and prohibitions imposed in terms of the ACT and Regulations: Provided that should the EMPLOYER have prescribed certain arrangements and procedures that same shall be observed and adhered to by the CONTRACTOR, his officials and employees. The CONTRACTOR shall bear the onus of acquainting himself/herself/itself with such arrangements and procedures.
- 3. The CONTRACTOR hereby accepts sole liability for such due compliance with the relevant duties, obligations, prohibitions, arrangements and procedures, if any, imposed by the ACT and Regulations, and the CONTRACTOR expressly absolves the EMPLOYER and the EMPLOYER'S AGENT from being obliged to comply with any of the aforesaid duties, obligations, prohibitions, arrangements and procedures in respect of the work included in the contract.
- 4. The CONTRACTOR agrees that any duly authorised officials of the EMPLOYER shall be entitled, although not obliged, to take such steps as may be necessary to ensure that the CONTRACTOR has complied with his undertakings as more fully set out in paragraphs 1 and 2 above, which steps may include, but shall not be limited to, the right to inspect any appropriate site or premises occupied by the CONTRACTOR, or to take such steps the EMPLOYER may deem necessary to remedy the default of the CONTRACTOR at the cost of the CONTRACTOR.

5. The CONTRACTOR shall be obliged to report forthwith to the EMPLOYER any investigation, complaint or criminal charge which may arise as a consequence of the provisions of the ACT and Regulations, pursuant to work performed in terms of this agreement, and shall, on written demand, provide full details in writing of such investigation, complaint or criminal charge.

| Thus signed at | for and on behalf of the EMPLOYER |
|--------------------|-----------------------------------|
| on this the day of | . 20 |
| SIGNATURE: | |
| NAME AND SURNAME: | |
| CAPACITY: | |
| WITNESSES: 1 | |

2.

| Thus signed at | for and on behalf of the CONTRACTOR |
|-------------------|--|
| on this theday of | 20 |
| SIGNATURE: | |
| NAME AND SURNAME: | |
| CAPACITY: | |
| WITNESSES: 1 | |
| 2 | |

C1.5: RETENTION MONEY GUARANTEE

PRO FORMA

RETENTION MONEY GUARANTEE

THE HEAD: TRANSPORT PROVINCE OF KWAZULU-NATAL PRIVATE BAG X9043 PIETERMARITZBURG 3200

CONTRACT NO. _____ FOR _____

ISSUED TO: the **PROVINCE OF KWAZULU-NATAL**, represented by **HEAD: TRANSPORT** (hereinafter referred to as "the Employer")

ON BEHALF OF: (hereinafter referred to as "the Contractor")

In connection with

CONTRACT NO. ZNB (hereinafter referred to as "the Contract")

WHEREAS the Employer and the Contractor have agreed that the Contractor may provide a guarantee in lieu of the whole or portion of the retention monies provided for under the Contract;

NOW THEREFORE we, the undersigned, undertake, in accordance with the following provisions, to pay the Employer such amounts as the Employer may, from time to time, demand from us.

1. Each demand by the Employer shall be in writing signed by the Employer and delivered to us at

or such other address as we shall in writing notify to the Employer and shall be accompanied by a certificate complying with Clause 2, signed by the Employer's Agent as such in terms of the Contract.

- 2. The Employer's Agent's certificate referred to in Clause 1 shall certify
 - (a) that he is the Employer's Agent in terms of the Contract,
 - (b) that the Contractor is in breach of his obligations under the Contract, and
 - (c) that the amount demanded, which amount the certificate shall specify,
 - (i) does not exceed the amount of retention monies which, but for this guarantee, would have been retained by the Employer in terms of the Contract at the date of the certificate, less the aggregate of the amounts of retention money actually retained by the Employer and the amounts previously paid by us to the Employer in terms hereof, and
 - (ii) does not exceed a genuine estimate of the cost to the Employer of having the breach referred to in paragraph (b) remedied less the aggregate of any amounts withheld by the Employer from payments due the Contractor in terms of the Contract by reason of the breach referred to, and any amount in retention money actually held by the Employer save to the extent that the same had been deducted from any previous demand in terms hereof.
- 3. We shall within 28 days after our receipt of a demand complying with the provisions of Clauses 1 and 2 make payment to the Employer of the amount demanded at 172 Burger Street, Pietermaritzburg or at such other address as the Employer shall in writing notify us.
- 4. Subject to compliance with the provisions thereof, our liability to make the payments herein referred to shall be unconditional and shall not be affected nor diminished by any disputes, claims or counterclaims between the Employer and the Contractor.

- 5. Our aggregate liability under this guarantee is limited to R
- 6. This guarantee shall expire on the date on which the last of the retention monies, which but for this guarantee would have been retained by the Employer, becomes payable to the Contractor.
- 7. This guarantee is not transferable and must be produced for endorsement if any part payment is made and must be returned to us against final payment of our aggregate liability or on the date of the expiry of the guarantee in terms of Clause 6, whichever is the earlier.

Signed in the presence of the witnesses named hereunder:

| At | for and on behalf of |
|---------|-----------------------|
| on this | day of |
| Signatu | ıre: |
| Capaci | y: |
| Addres | S' |
| As Witr | iesses: |
| 1. | Name in Block Letters |
| 2. | Name in Block Letters |

C1.6: TRANSFER OF RIGHTS

TRANSFER OF RIGHTS AND INDEMNITY (To be completed during construction by successful Tenderer only)

| Claim for Plant and materials on site, Payment Certificate No Date: | | | | | |
|---|----------------------|--|--|--|--|
| | For (contract title) | | | | |
| | in my capacity as | | | | |

..... of (name of Contractor)

duly authorised hereto on behalf of the Contractor hereby transfer, cede and assign all the Contractor's rights, title and interest in and to the Plant and materials, for which evidence of bona fide ownership is attached hereto, unto and in favour of (name of Employer)

Insofar as the Contractor retains actual control of the materials and goods, the right of ownership thereof passes to the Employer by *constitutum possessorium*.

I herewith indemnify the Employer against any claim to and in respect of the said Plant and materials by reason of the Contractor's sequestration or liquidation or of any defect in the Contractor's title to the materials and agree that no payment for materials on site will be made by the Employer until such time as I have submitted documentary proof of bona fide ownership of the said Plant and materials.

This transfer shall become effective upon conclusion of the Contractor receiving payment from the Employer or from any other person on behalf of the Employer for the Plant and materials as Plant and materials on Site, payment of retention money thereon excluded.

I further confirm that I am fully responsible for all Plant and materials listed under this Transfer of Rights and that they have been insured adequately against all risks and will remain insured until they are built into or used in the permanent works and taken over by the Employer.

This certificate of Transfer of Rights applies only to the Plant and materials as listed in the following table.

| DESCRIPTION OF ITEM | UNIT | QUANTITY | RATE | AMOUNT | SUPPLIER |
|------------------------------------|------|----------|------|--------|----------|
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| TOTAL VALUE OF PLANT AND MATERIALS | | | | | |

Signed by:Date:Date:Date:Date:Date:Date:Date:

Witnessed by:

NOTE: This form, together with the documentary proof of ownership or proof of payment by the Contractor to the supplier, shall accompany the Contractor's claim for payment for Plant and materials on site in terms of Clause 6.10.1.5 of the General Conditions of Contract 2015.

PART C2: PRICING DATA

C2.1 PRICING ASSUMPTIONS

1. GENERAL

The Bill of Quantities forms part of the Contract Documents and must be read and priced in conjunction with all the other documents comprising the Contract Documents, which include the Conditions of Tender, Conditions of Contract, the Specifications (including the Project Specifications) and the Drawings.

2. DESCRIPTION OF ITEMS IN THE SCHEDULE

The Bill of Quantities has been drawn up generally in accordance with the relevant provisions of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020.

The short descriptions of the items in the Bill of Quantities are for identification purposes only and the measurement and payment clause of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020. and the Particular Specifications, read together with the relevant clauses of the amendments and additions contained in the Project Specifications and directives on the drawings, set out what ancillary or associated work and activities are included in the rates for the operations specified.

The item numbers appearing in the Bill of Quantities refer to the corresponding item numbers in the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020. Item numbers prefixed by the letter PS refer to items of payment described in Part B Amendments to the Standard Specifications.

For the purposes of this Bill of Quantities, the following words shall have the meanings hereby assigned to them:

- Unit: The unit of measurement for each item of work as defined in the specifications.
- Quantity: The number of units of work for each item.
- Rate: The payment per unit of measurement at which the Tenderer tenders to do the work.
- Amount: The product of the quantity and the rate tendered for an item.
- Lump Sum: An amount tendered for an item, the extent of which is described in the Bill of Quantities, the specifications or elsewhere, but the quantity of work of which is not measured in any units.

3. QUANTITIES REFLECTED IN THE BILL OF QUANTITIES

The quantities given in the Bill of Quantities are estimates only and are subject to re-measure during the execution of the work. The quantities finally accepted and certified for payment, and not the quantities given in the Bill of Quantities, shall be used to determine payments to the Contractor. The Contractor shall obtain the Employer's Agent's detailed instructions for all work before ordering any materials or executing work or making arrangements for it. The quantities of material or work stated in the Bill of Quantities shall not be regarded as authorisation for the Contractor to order material or to execute work.

The Works as finally completed in accordance with the Contract shall be measured and paid for as specified in the Bill of Quantities and in accordance with the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020, the Project Specifications and the Drawings. Unless otherwise stated, items are measured net in accordance with the Drawings, and no allowance has been made for waste. The validity of the

contract will in no way be affected by differences between the quantities in the Bill of Quantities and the quantities finally certified for payment.

4. PROVISIONAL SUMS

Where Provisional sums or Prime Cost sums are provided for items in the Bill of Quantities, payment for the work done under such items will be made in accordance with Clause 6.6 of the General Conditions of Contract 2015. The Employer reserves the right, during the execution of the works, to adjust the stated amounts upwards or downwards according to the work actually done under the item, or the item may be omitted altogether, without affecting the validity of the Contract.

The Tenderer shall not under any circumstances whatsoever delete or amend any of the sums inserted by the Employer in the "Amount" column of the Bill of Quantities and in the Summary of the Bill of Quantities unless so ordered or authorised in writing by the Employer before closure of tenders. Any unauthorised changes made by the Tenderer to provisional items in the Bill of Quantities, or to the provisional percentages and sums in the Summary of the Bill of Quantities, at the Employer's discretion, may invalidate the Tenderer's offer or may be treated as arithmetical errors and the provisional items and percentages corrected without change to the Contract Sum.

5. PRICING OF THE BILL OF QUANTITIES

The prices and rates to be inserted by the Tenderer in the Bill of Quantities shall be the full inclusive prices to be paid by the Employer for the work described under the several items, and shall include full compensation for all costs and expenses that may be required in and for the completion and maintenance during the defects liability period of all the work described and as shown on the drawings as well as all overheads, profits, incidentals and the cost of all general risks, liabilities and obligations set forth or implied in the documents on which the Tender is based. The rates and lump sums shall be comprehensive in accordance with Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020.

Each item shall be priced and extended to the "Amount" column by the Tenderer, with the exception of the items for which only rates are required, or items which already have Prime Cost or Provisional Sums affixed thereto. If the Tenderer omits to price any items in the Bill of Quantities, then these items will be considered to have a nil rate or price.

All items for which terminology such as "inclusive" or "not applicable" have been added by the Tenderer will be regarded as having a nil rate which shall be valid irrespective of any change in quantities during the execution of the Contract.

Should the Tenderer group a number of items together and tender one lump sum for such group of items, this single lump sum shall apply to that group of items and not to each individual item.

The tendered lump sums and rates shall be valid irrespective of any change in the quantities during the execution of the contract.

The Tenderer shall fill in rates for all items where the words "rate only" appear in the "Amount" column. The provisions of subclause C1.1.3.6 of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020 shall apply to rate only items. "Rate Only" items have been included where:

- (a) an alternative item or material is contemplated;
- (b) variations of specified components in the make-up of a pay item may be expected; and
- (c) no work under the item is foreseen at tender stage but the possibility that such work may be required is not excluded.

For "Rate Only" items, no quantities are given in the "Quantity" column, but the quoted rate shall apply in the event of work under this item being required. The Tenderer shall, however, note that in terms of the Tender Data the Tenderer may be asked to reconsider any such rates which the Employer may regard as imbalanced.

Reasonable compensation will be received where no pay item appears in respect of work required in terms of the Contract which is not covered in any other pay item.

All rates and amounts quoted in the Bill of Quantities shall be in Rands and cents and shall include all levies and taxes (other than VAT). VAT will be added in the summary of the Bill of Quantities. Note that fractions of a cent in all rates shall be omitted.

6. CORRECTION OF ENTRIES

Incorrect entries shall not be erased or obliterated with correction fluid but must be crossed out neatly. The correct figures must be entered above or adjacent to the deleted entry, and the alteration must be initialled by the Tenderer.

7. INTERIM PAYMENTS

Unless otherwise specified, progress payments in Interim Certificates, referred to in Clause 6.10 of the General Conditions of Contract 2015, in respect of "sum" items in the Bill of Quantities shall be by means of interim progress instalments assessed by the Employer's Agent and based on the measure in which the work actually carried out relates to the extent of the work to be executed by the Contractor.

Notwithstanding any custom to the contrary, the work as executed will be measured for payment in accordance with the methods described in the contract documents under the various items of payment.

Attention is directed to the provisions of Clause C1.1.2 of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020 regarding the measurement of quantities for payment. Except where specified otherwise, the nett measurements or mass of the finished work in place shall be taken for payment, but any quantity of work in excess of that prescribed shall be excluded.

8. ITEMS SCHEDULED FOR CONSTRUCTION USING LABOUR ENHANCED METHODS

Those parts of the Works to be constructed using labour enhanced methods are numbered with the specific COTO, Draft Standard (DS), October 2020 Specifications items in the Bill of Quantities.

9. UNITS OF MEASUREMENT

The units of measurement described in the Bill of Quantities are metric units. The following abbreviations are used in the Bill of Quantities:

| mm | = millimetre | m³.km | = cubic metre kilometre | Prov sur | n= provisional sum |
|----------------|---------------------------------------|--------|-------------------------|----------|--------------------|
| m | = metre | I | = litre | kPa | = kilopascal |
| km | = kilometre | kl | = kilolitre | MPa | = megapascal |
| km.pass | kilometre pass | kg | = kilogram | MN | = meganewton |
| m² | = square metre | t | = ton (1 000 kg) | t.km | = ton kilometre |
| m².pass | square metre pass | No | = number | h | = hour |
| ha | = hectare | % | = percent | dia | = diameter |
| m ³ | = cubic metre | PC sum | = prime cost sum | Sum | = lump sum |
| kW | = kilowatt | MN.m | = meganewton metre | | |

10. CONSISTENCY OF RATES

In order to ensure that payments certified by the Employer's Agent are reasonably consistent with the market value of the work done, and that variations in quantities do not distort the contract valuation, the rates, prices and amounts tendered in the Bill of Quantities are required to be in balance.

A tender will be considered out of balance if:

(i) the combined, extended total tendered for the item:

C1.3.1 The contractor's general obligations:

- C1.3.1.1 Fixed obligations
- C1.3.1.3 Time-related obligations

exceeds a maximum of 15% of the Contract Sum (excluding contingencies, contract price adjustment and VAT).

(ii) the rate, price or amount tendered <u>for any other item</u> differs by more than 20 (twenty) percent from the <u>average</u> of the rates, prices or amounts <u>for the same item</u> as tendered by those tenderers who submitted the lowest five responsive tender offers (or as tendered by all the responsive tenderers if there are less than five responsive tenderers).

Any such out of balance tender may be rejected if, after three (3) working days of having been given written notice by the Employer to adjust those rates or lump sums which are unreasonable or out of balance, the Tenderer fails to make the necessary satisfactory adjustments. These adjustments in rectification will be such that increases are balanced by decreases, leaving the tender offer unchanged.

C2.2 BILL OF QUANTITIES

| TABLE OF CONTENTS | Page |
|--------------------|------|
| BILL OF QUANTITIES | C29 |
| TENDER SUMMARY | C63 |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|----------|---|----------|----------|------|--------|
| C1.2 | GENERAL REQUIREMENTS AND PAYMENT | | | | |
| C1.2.1 | Environmental Management | | | | |
| C1.2.1.1 | Monitoring of compliance with and reporting on the EMP | month | 18 | | |
| C1.2.1.2 | Dedicated environmental officer (if specified in the Contract Documentation) | month | 18 | | |
| C1.2.2 | Programming and Reporting | | | | |
| C1.2.2.3 | Submission of a Scheme 2 Initial Programme | Lump Sum | 1 | | |
| C1.2.2.4 | Submission of a Scheme 2 Full Programme | Lump Sum | 1 | | |
| C1.2.2.5 | Reviewing and updating a Scheme 2 Programme every month | month | 18 | | |
| C1.2.2.6 | Preparation and submission of all information and reports specified in the Contract Documentation | month | 18 | | |
| C1.2.5 | Safety | | | | |
| C1.2.5.1 | Health and safety plan | Lump Sum | 1 | | |
| C1.2.5.2 | Implementation of health and safety plan | month | 18 | | |
| C1.2.8 | Dayworks | | | | |
| C1.2.8.1 | Personnel | | | | |
| (a) | Unskilled labourer | hour | 600 | | |
| (b) | Semi-skilled labourer | hour | 200 | | |
| (c) | Skilled labourer | hour | 200 | | |
| (d) | Gang leader | hour | 200 | | |
| (e) | Foreman | hour | 200 | | |
| (f) | Skilled Artisan | hour | 200 | | |
| | | | | | |
| C1.2 | TOTAL CARRIED FORWARD | | | | |

Province of KwaZulu-Natal Department of Transport

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|-------------|--|----------|--------------|------|--------------|
| | | UNIT | QUANTIT | RATE | AMOUNT |
| | TOTAL BROUGHT FORWARD | | | | |
| C1.2.8.2 | Construction Equipment | | | | |
| (a) | Motor grader (112kw) | hour | 50 | | |
| (b) | Vibratory roller (80kw) | hour | 50 | | |
| (c) | Pneumatic roller (60km, 20t) | hour | 50 | | |
| (d) | Front end loader backhoe (55kw) | hour | 50 | | |
| (e) | Excavator (92kw) | hour | 50 | | |
| (f) | Compressor (600cmf 17m ³ /min Complete with two tools and operators) | hour | 50 | | |
| (h) | Dozer (123kw) | hour | 50 | | |
| (i) | Pedestrian vibrating roller (1.4 ton) | hour | 50 | | |
| C1.2.8.3 | Vehicles (specify size) | | | | |
| (a) | Light delivery vehicle | km | 2000 | | |
| (b) | Flatbed truck | km | 1500 | | |
| (c) | Dump Truck 6m ³ | km | 1500 | | |
| (d) | Water spray truck (7000l) | km | 1500 | | |
| C1.2.8.4 | Materials | | | | |
| (a) | Procurement of materials | Prov Sum | 100000 | 1 | R 100 000.00 |
| (b) | Contractor's handling costs, profit and all other charges in respect of item C1.2.8.4(a) | % | R 100 000.00 | | |
| C1.2.9 | Disposal of non-usable assets | | | | |
| P.S.C1.2.10 | Community Participation | | | | |
| | (a) Cost for community Participation (PLC and CLO) | PC Sum | R 470 000.00 | 1 | R 470 000.00 |
| | (b) Handling costs and profit in respect of sub-item PSC1.2.10(a) above | % | R 470 000.00 | | |
| C1.2 | TOTAL CARRIED FORWARD TO SUMMARY (Page C56) | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|----------|---|----------|----------|------|--------|
| C1.3 | CONTRACTOR'S SITE ESTABLISHMENT AND GENERAL OBLIGATIONS | | | | |
| C1.3.1 | The Contractor's general obligations | | | | |
| C1.3.1.1 | Fixed obligations | Lump Sum | 1 | | |
| C1.3.1.3 | Time-related obligations | month | 18 | | |
| C1.3.2 | Contract sign boards | m² | 12 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| C1.3 | TOTAL CARRIED FORWARD TO SUMMARY (Page C56) | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE3 | AMOUNT |
|----------------------------|--|----------|----------|-------|-------------|
| C1.4 | FACILITIES FOR THE ENGINEER | | | | |
| C1.4.1 | Site accommodation | | | | |
| C1.4.1.1 | Offices and conference room | m² | 40 | | |
| C1.4.1.6 | Car ports | No | 4 | | |
| C1.4.1.7 | Ablution unit (Male and Female unit -Equipped with hand wash basin and Toilet) | No | 2 | | |
| C1.4.1.8 | Change room with a shower | No | 2 | | |
| C1.4.1.9 | Kitchen unit (Equipped with basin, Microwave and Refrigerator) | No | 1 | 1.00 | |
| C1.4.1.13 | Rented housing paid for by the Contractor | Prov Sum | 200 000 | | R200 000.00 |
| C1.4.1.14 | Contractor's handling costs, profit and all other charges in respect of item C1.4.1.13 | % | 200 000 | | |
| C1.4.2 | Items measured by area | | | | |
| C1.4.2.1 | Shelving as specified, complete with brackets | m² | 14 | | |
| C1.4.2.6 | Roller blinds, opaque type | m² | 10 | | |
| C1.4.2.7 | Venetian blinds | m² | 20 | | |
| C1.4.2.8 | Notice boards | m² | 10 | | |
| C1.4 TOTAL CARRIED FORWARD | | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|-----------|--|------|----------|------|--------|
| | TOTAL BROUGHT FORWARD | | | | |
| C1.4.3 | Items measured by number | | | | |
| C1.4.3.1 | Office swivel chair | No | 2 | | |
| C1.4.3.2 | Office chair | No | 8 | | |
| C1.4.3.3 | Draughtsman's stool | No | 2 | | |
| C1.4.3.5 | Office desk with 3 drawers (at least one lockable drawer) | No | 5 | | |
| C1.4.3.7 | Drawing table | No | 1 | | |
| C1.4.3.8 | Conference table | No | 1 | | |
| C1.4.3.9 | Bookcase | No | 3 | | |
| C1.4.3.10 | Filling cabinet | No | 2 | | |
| C1.4.3.11 | General purpose steel cabinet with shelves | No | 3 | | |
| C1.4.3.13 | 220/250 volt power outlet plug point | No | 22 | | |
| C1.4.3.14 | 400/231 volt 3-phase power outlet plug point | No | 2 | | |
| C1.4.3.15 | Single 1 500 mm, 58 watt fluorescent tube ceiling light | No | 10 | | |
| C1.4.3.16 | Single 1 500 mm, 22 watt LED tube ceiling light | No | 2 | | |
| C1.4.3.17 | 11 watt compact fluorescent bulb ceiling light | No | 2 | | |
| C1.4.3.19 | Wash-hand basin | No | 2 | | |
| C1.4.3.23 | Fire extinguisher 9,0 kg, dry powder type | No | 10 | | |
| C1.4.3.24 | Air-conditioning unit | No | 3 | | |
| C1.4 | TOTAL CARRIED FORWARD | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|-----------|--|--------|-------------|----------|-------------|
| | TOTAL BROUGHT FORWARD | | | | |
| C1.4.3.25 | Heater | No | 3 | | |
| C1.4.3.27 | Waste paper basket | No | 4 | | |
| C1.4.3.28 | UPS / Voltage stabiliser | No | 1 | | |
| C1.4.3.29 | A3 / A4 colour printer, copier, scanner | No | 1 | | |
| C1.4.3.30 | A4 colour printer, copier, scanner | No | 2 | | |
| C1.4.3.31 | Rain gauge | No | 1 | | |
| C1.4.3.32 | Minimum / maximum atmospheric temperature gauge | No | 1 | | |
| C1.4.3.33 | Digital thermometer | No | 2 | | |
| C1.4.3.34 | Mobile outdoor weather station | No | 1 | | |
| C1.4.3.35 | 3,0 m aluminium straight edge complete with two measuring wedges | No | 2 | | |
| C1.4.3.36 | Measuring wheel | No | 2 | | |
| C1.4.3.37 | First aid kit | No | 2 | | |
| C1.4.4 | Prime cost items | | | | |
| C1.4.4.1 | Cell phones costs, including pro- rate rentals, for calls made in connection with contract administration | PC Sum | 25000 | 1 | R 25 000.00 |
| C1.4.4.2 | Handling cost and profit in respect of item C1.4.4.1 | % | R 25 000.00 | | |
| C1.4.4.3 | The provision of a direct independent telephone line for the Engineer, including the monthly rental charges and the cost of business calls | PC Sum | 25000 | 1 | R 25 000.00 |
| C1.4.4.4 | Handling cost and profit in respect of item C1.4.4.3 | % | R 25 000.00 | | |
| C1.4.4.5 | The provision of internet connectivity and WIFI data for Engineer's site staff | PC Sum | 25000 | 1 | R 25 000.00 |
| C1.4 | TOTAL CARRIED FORWARD | | <u> </u> | <u> </u> | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|-----------|--|----------|-------------|------|-------------|
| | TOTAL BROUGHT FORWARD | | | | |
| C1.4.4.6 | Handling cost and profit in respect of item C1.4.4.5 | % | R 25 000.00 | | |
| C1.4.4.7 | The provision of paper and ink for a combination colour printer/copier/scanner | PC Sum | 30000 | 1 | R 30 000.00 |
| C1.4.4.8 | Handling cost and profit in respect of item C1.4.4.7 | % | R 30 000.00 | | |
| C1.4.4.9 | The provision of a complete 220/250 volt single phase electrical power installation, including all poles, insulators, wiring, switchboards, mains connection, meters, etc. | PC Sum | 30000 | 1 | R 30 000.00 |
| C1.4.4.10 | Handling cost and profit in respect of item C1.4.4.9 | % | R 30 000.00 | | |
| C1.4.4.15 | The provision of all gas installations required at the site offices, laboratories and at the Engineer's staff accommodation (if required), including gas storage cylinders, tubing, regulators, gas burners and shut-off cocks | PC Sum | 15000 | 1 | R 15 000.00 |
| C1.4.4.16 | Handling cost and profit in respect of item C1.4.4.15 | % | R 15 000.00 | | |
| C1.4.5 | Services at site offices, laboratories and site accommodation | | | | |
| C1.4.5.1 | Fixed costs | Lump Sum | 1 | | |
| C1.4.5.2 | Running costs | month | 18 | | |
| C1.4.6 | Office Staff | | | | |
| C1.4.6.2 | Technical assistant | month | 18 | | |
| C1.4 | TOTAL CARRIED FORWARD | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|----------|--|----------|----------|------|--------|
| | TOTAL BROUGHT FORWARD | | | | |
| C1.4.7 | Site inspection transport | | | | |
| C1.4.7.2 | Travel on site | km | 5000 | | |
| C1.4.8 | Site security measures for the Engineer's facilities | | | | |
| C1.4.8.1 | Supply and installation of all required security measures at the Engineer's site offices and laboratories | Lump Sum | 1 | | |
| C1.4.8.2 | Provision of security guards / watchmen and an armed response service at the Engineer's site offices and laboratories | month | 18 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| C1.4 | TOTAL CARRIED FORWARD TO SUMMARY (Page C56) | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|---------------------|---|-----------|----------|------|--------|
| C1.5 | ACCOMMODATION OF TRAFFIC | | | | |
| C1.5.2 | Accommodation of vehicular traffic | month | 18 | | |
| C1.5.4 | Construction of temporary deviations | | | | |
| C1.5.4/ C1.6.1.1 | Clearing with machines and some hand labour where necessary | ha | 2 | | |
| C1.5.7 | Temporary traffic control facilities | | | | |
| C1.5.7.1 | Delineators including mounting bases and ballast: | | | | |
| (a) | Single sided, reversible left or right (1000mm x 250mm) | No | 100 | | |
| (b) | Double sided, reversible left or right (1000 mm x 250mm) | No | 250 | | |
| C1.5.7.2 | Traffic cones, minimum height 750 mm | No | 50 | | |
| C1.5.7.3 | Flagmen | man-shift | 3960 | | |
| C1.5.7.4 | Traffic controllers | man-shift | 3960 | | |
| C1.5.7.5 | Provision of illuminated traffic signs | | | | |
| (a) | Sign mounted flashing amber lights (2 lights with the specified power supply) mounted on a backing board which is: | | | | |
| (a.i) | 900 mm wide x 150mm high | No | 5 | | |
| (a.ii) | 1200 mm wide x 200 mm high | No | 5 | | |
| (b) | Flashing LED illuminated arrow board | No | 2 | | |
| (c) | Illuminated road sign - R & TR series (1200mm dia.) | No | 10 | | |
| (d) | Illuminated road sign - TW series (1200mm sides) | No | 10 | | |
| <u></u> | | | | | |
| C1.5 | TOTAL CARRIED FORWARD | | | | |

| Department of Transport | | | | | | |
|-------------------------|---|-----------|-------------|------|-------------|--|
| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT | |
| | TOTAL BROUGHT FORWARD | | | | | |
| C1.5.7.6 | Maintenance of illuminated traffic signs: | | | | | |
| (a) | Sign mounted flashing amber lights (a pair of two lights mounted on a separate backing board) | month | 18 | | | |
| (b) | Flashing LED illuminated arrow board | month | 18 | | | |
| (c) | Illuminated road sign - R & TR series (1200mm dia.) | month | 18 | | | |
| (d) | Illuminated road sign - TW series (1200mm sides) | month | 18 | | | |
| C1.5.7.8 | Traffic control stations | month | 12 | | | |
| C1.5.7.9 | Cleaning of traffic control facilities | month | 12 | | | |
| C1.5.8 | Traffic safety officer | Man-month | 18 | | | |
| C1.5.9 | Traffic safety vehicle | month | 18 | | | |
| C1.5.11 | Provision of safety equipment for visitors | | | | | |
| C1.5.11.1 | Provision of reflective safety vests for visitors | No | 5 | | | |
| C1.5.11.2 | Provision of hard hats for visitors | No | 5 | | | |
| C1.5.12 | Additional traffic accommodation facilities ordered by the Engineer: | | | | | |
| C1.5.12.1 | Provision of additional traffic accommodation facilities | Prov Sum | 25000 | 1.00 | R 25 000.00 | |
| C1.5.12.2 | Handling cost, profit and all other charges in respect of item C1.5.12.1 | % | R 25 000.00 | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| C1.5 | TOTAL CARRIED FORWARD TO SUMMARY (Page C56) | | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|----------|--|---------------------|----------|------|--------|
| C1.7 | LOADING AND HAULING | | | | |
| C1.7.1 | Loading | | | | |
| C1.7.1.1 | Loading from stockpile using machines and some hand labour where necessary | m ³ | 5 000 | | |
| C1.7.1.2 | Loading from heaps or windrows using machines and/some hand labour where necessary | m ³ | 2 000 | | |
| C1.7.1.3 | Loading by hand only from stockpile or heaps when labour enhancement work is specified or is not possible to use machines | m ³ | 500 | | |
| C1.7.2 | Hauling | | | | |
| C1.7.2.1 | Hauling material for use in the Works and off-loading it on the site of the Works: | | | | |
| (a) | Soil, gravel, crushed stone and pavement layer material | m ³ - km | 150 721 | | |
| (b) | Boulders and hard material | m³ - km | 15 072 | | |
| C1.7.2.2 | Hauling material to spoil and off- loading it at a designated spoil or stockpile are: | | | | |
| (a) | Cleared and grubbed material (organic matter and all other unsuitable or waste material) | m ³ - km | 5 000 | | |
| (b) | Soil and gravel material | m ³ - km | 91 242 | | |
| (c) | Boulders, hard material and concrete | m³ - km | 5 000 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| C1.7 | TOTAL CARRIED FORWARD TO | | | | |
| | SUMMARY (Page C56) | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|-----------|---|----------|----------|------|-------------|
| C2.1 | GENERAL REQUIREMENTS AND TRENCHING FOR SERVICES | | | | |
| C2.1.1 | Location, Identification and relocation of existing services | | | | |
| C2.1.1.1 | Contractors' obligations | Lump Sum | 1 | | |
| C2.1.1.2 | Permanent services relocation or protection work by others | PC Sum | 20 000 | 1.00 | R 20 000.00 |
| C2.1.1.3 | Handling costs and profit in respect of item C2.1.1.2 above | % | 20 000 | | |
| C2.1.2.5 | Using hand excavation to locate, expose and verify services | m³ | 250 | | |
| C2.1.9 | Trench excavation using labour enhanced construction methods | | | | |
| C2.1.9.1 | Trenches up to 1.0m wide (in soft material) : | | | | |
| (a) | Up to 1.0m deep | m³ | 100 | | |
| (b) | Over 1.0m and up to 1.5m deep | m³ | 20 | | |
| C2.1.9.3 | Trenches over 1.0m up to 2.0m wide (in intermediate material) : | | | | |
| (a) | Up to 1.0m deep | m³ | 10 | | |
| (b) | Over 1.0m and up to 1.5m deep | m³ | 5 | | |
| C2.1.11 | Backfilling of trenches | | | | |
| C2.1.11.1 | Backfill compacted tp 93% (100% for sand) of MDD (areas subject to traffic loads) using material: | | | | |
| (a) | From the excavated trench material | m³ | 150 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| C2.1 | TOTAL CARRIED FORWARD TO | | | | |
| 02.1 | SUMMARY (Page C56) | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|----------|--|------|----------|------|--------|
| C2.2 | DRY SERVICES | | | | |
| C2.1.1 | Supply, lay and prove ducts | | | | |
| C2.2.1.1 | UPVC Ordinary pipes, spigot and socket joints | | | | |
| (a) | 110 mm diameter (OD) | m | 50 | | |
| (b) | 160 mm diameter (OD) | m | 50 | | |
| C2.2.4 | Bedding for ducts compacted to 90 % of MDD (100 % for sand) using material: | | | | |
| C2.2.4.1 | Selected from the excavated trench material | m³ | 10 | | |
| C2.2.5 | Concrete for bedding and encasement of ducts | | | | |
| C2.2.5.2 | Concrete encasement of ducts (Class 25/13 Concrete) | m³ | 10 | | |
| C2.2.6 | Duct accessories (markers, marking, draw wires and end caps etc.) | | | | |
| C2.2.6.1 | Duct markers (240mm x 50mm x 900mm Class 25/13 Concrete as per Drawing SD1002/C) | No | 20 | | |
| C2.2.6.3 | Draw wires (Galvanised Wire) | m | 100 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| C2.2 | TOTAL CARRIED FORWARD TO SUMMARY (Page C56) | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|-----------|---|----------------|----------|------|--------|
| C4.1 | BORROW MATERIALS | | | | |
| C4.1.4 | Removing of the overburden | | | | |
| C4.1.4.1 | In borrow pits | m ³ | 150 | | |
| C4.1.5 | Excavating of materials in the borrow pits and quarries, material obtained from | | | | |
| C4.1.5.1 | Soft excavation | m³ | 200 | | |
| C4.1.5.2 | Boulder excavation class A | m ³ | 6649 | | |
| C4.1.5.3 | Boulder excavation class B | m ³ | 100 | | |
| C4.1.15.1 | Shaping and finishing the borrow pit and quarry areas, and the stockpile sites: | | | | |
| (a) | Borrow pits | | | | |
| | (1) borrow pit 1 | ha | 1 | | |
| | (2) borrow pit 2 | ha | 1 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| C4.1 | TOTAL CARRIED FORWARD TO | | | | |
| 64.1 | SUMMARY (Page C56) | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|-----------|--|----------------|----------|------|--------|
| C4.2 | CUT MATERIALS | | | | |
| C4.2.1 | Compiling and implementing M&U plans for the cuttings | | | | |
| C4.2.1.1 | Cuttings exceeding 5 000 m ³ up to 10 000 m3 | No | 1 | | |
| C4.2.1.2 | Cuttings exceeding 10 000 m ³ up to 20 000 m3 | No | 1 | | |
| C4.2.3 | Excavating of materials in cuttings, material obtained from | | | | |
| C4.2.3.1 | Soft excavation | m ³ | 39 664 | | |
| C4.2.3.2 | Boulder excavation class A | m ³ | 9 916 | | |
| C4.2.3.3 | Boulder excavation class B | m ³ | 4 958 | | |
| C4.2.3.4 | Hard excavation (other than by blasting) | m ³ | 2 479 | | |
| C4.2.7 | Removal of unsuitable stable cut material to spoil | | | | |
| C4.2.7.1 | In layer thicknesses of 200 mm and less | m ³ | 100 | | |
| C4.2.9 | Excavate material to spoil in sites designated by the Contractor, material obtained from | | | | |
| C4.2.9.1 | Soft excavation, overburden and unsuitable material | m ³ | 45621 | | |
| C4.2.9.2 | Boulder excavation class A | m ³ | 1500 | | |
| C4.2.9.4 | Hard excavation (other than by blasting) | m ³ | 1000 | | |
| C4.2.12 | Finishing the side slopes | | | | |
| C4.2.12.1 | Cuttings: | | | | |
| (a) | In soft material | m² | 100 | | |
| (b) | In boulder material class A and B | m² | 400 | | |
| (d) | In soft material using labour enhanced methods of construction | m² | 3000 | | |
| C4.2 | TOTAL CARRIED FORWARD TO SUMMARY (Page C56) | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|-----------|---|----------------|----------|------|--------|
| C4.3 | EXISTING ROAD MATERIALS | | | | |
| C4.3.4 | Saw-cutting existing materials within the following average depth ranges | | | | |
| C4.3.4.1 | Asphalt material: | | | | |
| (a) | Up to 50 mm | m | 30 | | |
| (b) | Exceeding 50 mm and up to 100 mm | m | 30 | | |
| C4.3.18 | Excavate non-compliant or excess pavement layer material to spoil in sites designated by the Contractor, material consisting of: | | | | |
| C4.3.18.1 | Asphalt material | m ³ | 50 | | |
| C4.3.18.2 | Crushed stone, macadam, gravel and sand material | m ³ | 100 | | |
| C4.3.18.4 | Concrete material | m ³ | 50 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| C4.3 | TOTAL CARRIED FORWARD TO SUMMARY (Page C56) | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|----------|---|----------------|-------------|------|-------------|
| C4.4 | COMMERCIAL MATERIALS | | | | |
| C4.4.2 | Commercial materials identified by the Contractor from commercial, private or other non-commercial suppliers | | | | |
| C4.4.2.1 | Pavement layer material: | | | | |
| (b) | Type G2 material | m ³ | 10300 | | |
| (h) | Type G6 material | m ³ | 21981 | | |
| C4.4.4 | Cementitious stabilising agents | | | | |
| C4.4.4.1 | Cement | t | 959 | | |
| C4.4.7 | Sampling and material testing by a commercial laboratory for the stabilisation designs | | | | |
| C4.4.7.1 | Cost of sampling and material testing | Prov Sum | 15000 | 1.00 | R 15 000.00 |
| C4.4.7.2 | Handling cost and profit in respect of item C4.4.7.1 | % | R 15 000.00 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| C4.4 | TOTAL CARRIED FORWARD TO SUMMARY (Page C56) | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|----------|---|----------------|----------|------|--------|
| C5.1 | ROADBED | | | | |
| C5.1.1 | Roadbed construction and compaction | | | | |
| C5.1.1.1 | Compaction of in-situ material to 90% of MDD | m ³ | 3 137 | | |
| C5.1.3 | Excavate material to spoil sites designated by the Contractor | | | | |
| C5.1.3.1 | Excavate material to spoil from roadbed construction, material obtained from: | | | | |
| (a) | Soft excavation | m ³ | 100 | | |
| (b) | Boulder excavation Class A | m ³ | 100 | | |
| (d) | Hard excavation (other than by blasting) | m ³ | 100 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| C5.1 | TOTAL CARRIED FORWARD TO SUMMARY (Page C56) | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|-----------|---|----------------|----------|------|--------|
| C5.2 | FILL | | | | |
| C5.2.2 | Fill construction | | | | |
| C5.2.2.1 | Normal fill material in compacted layer thicknesses of 200 mm and less: | | | | |
| (b) | Compacted to 93% MDD | m ³ | 49 580 | | |
| C5.2.11 | Finishing off fill slopes, medians and interchange areas | | | | |
| C5.2.11.1 | Fill slopes | m² | 11 550 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| C5.2 | TOTAL CARRIED FORWARD TO SUMMARY (Page C56) | | | | |

| | | | | r | |
|----------|--|----------------|----------|------|--------|
| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
| C5.3 | ROAD PAVEMENT LAYERS | | | | |
| C5.3.1 | Compiling and implementing M&U plans for the construction of all the pavement layers | No | 2 | | |
| C5.3.2 | Construction of pavement layers | | | | |
| C5.3.2.1 | Construction of layers using conventional construction methods: | | | | |
| (c) | Upper selected subgrade layer (150mm) compacted to 95% of MDD | m ³ | 11 099 | | |
| (h) | Gravel shoulder layer (180mm) compacted to 95% of MDD | m ³ | 1 798 | | |
| (I) | Upper subbase gravel layer (chemically stabilised) (200mm) compacted to 98% of MDD | m³ | 15 633 | | |
| (x) | G2 crushed stone base layer (150mm) compacted to 85% of BD | m ³ | 10300 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | TOTAL CARRIED FORWARD TO | | | | |
| C5.3 | SUMMARY (Page C56) | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|----------|--|----------------|----------|------|--------|
| C5.4 | STABILISATION | | | | |
| C5.4.2 | Chemical stabilisation | | | | |
| C5.4.2.1 | Chemical stabilisation (layer thickness of 200mm) of pavement layers (Subbase layer to be stabilised to a C4) | m ³ | 14 212 | | |
| C5.4.5 | Cementitious stabilisation agents for pavement layers | | | | |
| C5.4.5.1 | Addition of cementitious stabilisation agents (specify agent separately) for pavement layers | | | | |
| (a) | Cement (for pavement layer) | t | 5 | | |
| C5.4.5.2 | Addition of cementitious stabilisation agents (specify agent separately) for pavement layers and spreading the agent using bags and labour enhancement methods. | | | | |
| (a) | Cement (for pavement layer) | t | 959 | | |
| C5.4.10 | Provision and application of water for curing | kł | 600 | | |
| C5.4.11 | Curing by covering with subsequent layer | m² | 9700 | | |
| C5.4.14 | Trial section for a chemically stabilised layer | m ³ | 1200 | | |
| C5.4.16 | Mechanical modification | m ³ | 11099 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| C5.4 | TOTAL CARRIED FORWARD TO SUMMARY (Page C56) | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|----------|---|------|----------|------|--------|
| C8.1 | PRIME COAT | | | | |
| C8.1.1 | Prime coat: | | | | |
| C8.1.1.5 | Certified product containing no solvents (E-Prime) | ł | 31 500 | | |
| C8.1.3 | Extra over item C8.1.1 for applying the prime coat accessible only to hand-held or light equipment | ł | 3 800 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| C8.1 | TOTAL CARRIED FORWARD TO SUMMARY (Page C56) | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|--------------|--|----------------|----------|------|--------|
| C10.1 | GENERAL REQUIREMENTS FOR SURFACE TREATMENTS | | | | |
| C10.1.3 | Multiple stone seals including a cover spray, if specified using: | | | | |
| C10.1.3.1 | 20 mm and 10 mm aggregate (Grade A aggregate and 70/100 Penetration grade bitumen binder) | m² | 69700 | | |
| C10.1.4 | Embargo period effects | | | | |
| C10.1.4.1 | Re-establishment of sealing team after embargo period | lump sum | 1 | | |
| C10.1.4.2 | Extra-over for sealing during the specified embargo period (Double seal -20mm+10mm Grade A Aggregate with 70/100 penetration grade bitumen cut back with 4% paraffin) | m² | 400 | | |
| C10.1.9 | Bituminous binder variations: | | | | |
| C10.1.9.1 | 70/100 Penetration grade bitumen | ł | 31 365 | | |
| C10.1.10 | Aggregate variation (Grade A): | | | | |
| C10.1.10.3 | 10 mm aggregate | m ³ | 1 745 | | |
| C10.1.10.5 | 20 mm aggregate | m ³ | 500 | | |
| C10.1.11 | Application of cover spray: | | | | |
| C10.1.11. 2 | 30 % Diluted Anionic stable-grade emulsion (50% and 50% emulsion) | ł | 24395 | | |
| C10.1.14 | Precoating of aggregate using a frontend loader | | | | |
| C10.1.14.1 | Product containing low flashpoint solvent (indicate precoating fluid) | ł | 15250 | | |
| C10/C8.4.1.2 | Correction material | | | | |
| (d) | Coarse slurry (Type 1 -Aggregate Grade A and Stable grade emulsion) | m ³ | 75 | | |
| C10.1 | TOTAL CARRIED FORWARD TO SUMMARY (Page C56) | | 1 | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|------------------|---|------|----------|------|--------|
| C11.6 | ROAD SIGNS | | | | |
| C11.6.1 | Road signboards with painted or coloured semi-matt background. Symbols, lettering and borders in semi- matt black or in Class I retro-reflective material, where the sign board is constructed from: | | | | |
| C11.6.1.3 | Prepainted galvanized steel plate: | | | | |
| (a) | Area 0 to 0,5 m ² | m² | 10 | | |
| (b) | Area exceeding 0,5 m2 but not 2,0 m ² | m² | 80 | | |
| (c) | Area exceeding 2,0 m2 but not 10 m ² | m² | 210 | | |
| C11.6.1.7 | Regulatory signs, permanent | | | | |
| (a) | 600 mm diameter (signboard material - Steel Plate 1.4mm thick, background - Class I and symbol retro-reflective class III) | No | 30 | | |
| C11.6.1.8 | Regulatory signs, temporary | | | | |
| (a) | 600 mm diameter (signboard material - Steel Plate 1.4mm thick, background - Class I and symbol retro-reflective class III) | No | 6 | | |
| C11.6.1.9 | Warning signs, permanent | | | | |
| (a) | 600 mm diameter (signboard material - Steel Plate 1.4mm thick, background - Class I and symbol retro-reflective class III) | No | 20 | | |
| C11.6.1.10 | Warning signs, temporary | | | | |
| (a) | 600 mm diameter (signboard material - Steel Plate 1.4mm thick, background - Class I and symbol retro-reflective class III) | No | 6 | | |
| C11.6.2 | Extra over on item C11.6.1 for using: | | | | |
| C11.6.2.1 (a) | Background of retro-reflective material: Class I | m² | 240 | | |
| C11.6 | TOTAL CARRIED FORWARD | | I | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|-----------|--|------|----------|------|--------|
| | TOTAL BROUGHT FORWARD | | | | |
| C11.6.2.2 | Lettering, symbols, numbers, arrows, emblems and borders of retro-reflective material: | | | | |
| (a) | Class III | m² | 60 | | |
| C11.6.3 | Road sign supports (overhead road sign structures excluded): | | | | |
| C11.6.3.2 | Timber | | | | |
| | (i) 125 mm diameter - CCA Treated | m | 828 | | |
| | (ii) 150 mm diameter - CCA Treated | m | 40 | | |
| C11.6.4 | Kilometre markers | | | | |
| C11.6.4.1 | Kilometre markers on posts (Concrete 450mm diameter pipes and as per SD1003/B) | No | 7 | | |
| C11.6.5 | Excavation and backfilling for road sign supports (not applicable to kilometre posts) | | | | |
| C11.6.5.1 | Excavating soft material and backfilling | m³ | 30 | | |
| C11.6.5.2 | Excavating soft or intermediate material and backfilling using labour enhanced construction methods | m³ | 35 | | |
| C11.6.5.3 | Extra over item C11.6.5.1 and 2 for cement-treated soil backfill | m³ | 14 | | |
| C11.6.5.4 | Extra over item C11.6.5.1 for hard material excavation | m³ | 4 | | |
| C11.6.6 | Dismantling, storing and re- erecting road signs with a surface area of: | | | | |
| C11.6.6.1 | Area 0 to 0,5 m² | m² | 2 | | |
| C11.6.6.2 | Area exceeding 0,5 m2 but not 2,0 m ² | m² | 4 | | |
| C11.6.6.3 | Exceeding 2,0 m2 but not 10 m ² | m² | 10 | | |
| C11.6 | TOTAL CARRIED FORWARD | | | | |

| <u>p</u> | | | | | | | |
|-----------|---|------|----------|------|--------------|--|--|
| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT | | |
| | TOTAL BROUGHT FORWARD | | | | R 597 100.00 | | |
| C11.6.7 | Dismantling and storing of road signs and overhead signs | | | | | | |
| C11.6.7.1 | Dismantling and storing of road signs with a surface area of: | | | | | | |
| (a) | Area 0 to 0,5 m ² | m² | 10 | | | | |
| (b) | Area exceeding 0,5 m2 but not 2,0 m ² | m² | 30 | | | | |
| (c) | Exceeding 2,0 m2 but not 10 m ² | m² | 15 | | | | |
| C11.6.8 | Danger plates at culverts/structures | | | | | | |
| C11.6.8.2 | Size 200 x 800 mm (state post type and reflective material) | No | 172 | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| C11.6 | TOTAL CARRIED FORWARD TO SUMMARY (Page C56) | | | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|-----------|--|------------|-------------|------|-------------|
| C20.1 | TESTING MATERIALS AND JUDGEMENT OF WORKMANSHIP | | | | |
| C20.1.2 | Special tests requested by the Engineer | | | | |
| C20.1.2.1 | Employer's contribution to concrete durability tests | | | | |
| C20.1.2.2 | Employer's contribution to other special tests | | | | |
| (a) | Test on Aggregates - SANS 3001- AG16 (Durability mill index) | Prime Cost | 25000 | 1 | R 25 000.00 |
| (b) | Test on Aggregates - SANS 3001- AG11 (Polished stone value of Aggregate) | Prime Cost | 25000 | 1 | R 25 000.00 |
| (c) | Test on cementitious stabilised materials - SANS 3001-GR56 (Wet and Dry Durability Test) | Prime Cost | 25000 | 1 | R 25 000.00 |
| (a.i) | Handling costs and profit in respect of item C20.1.2.2(a) | % | R50 000.00 | | |
| C20.1.3 | Providing testing equipment: | | | | |
| C20.1.3.1 | Core drill | No | 2 | | |
| C20.1.4 | Special tests using Automated Road condition assessment instruments operated by service providers as requested by the Engineer for acceptance control in terms of Clause A20.1.3.6b)(iii) | | | | |
| C20.1.4.1 | Using Highspeed Inertial Non- Contact laser profilers (Clause A20.1.5.5c)(ii)) | Prime Cost | 50000 | 1.00 | R 50 000.00 |
| (a) | Handling cost and profit in respect of item C20.1.4.1 | % | R 50 000.00 | | |
| C20.1.4.4 | Surface macro texture (Clause A20.1.5.5 b)) | Prime Cost | 50000 | 1.00 | R 50 000.00 |
| (a) | Handling cost and profit in respect of item C20.1.4.4 | % | R 50 000.00 | | |
| C20.1.5 | Financial contribution for an independent site/commercial laboratory | month | 18 | | |
| C20.1 | TOTAL CARRIED FORWARD TO SUMMARY (Page C56) | | | | |

SUMMARY OF SECTIONS

UPGRADING OF MAIN ROAD P8/3 FROM GRAVEL TO BLACKTOP BETWEEN KM 17.560 AND KM 24.221 IN THE PIETERMARITZBURG REGION

| CHAPTER | DESCRIPTION | FROM PAGE | AMOUNT |
|---------|--|--------------|--------|
| C1.2 | GENERAL REQUIREMENTS AND PAYMENT | C30 | |
| C1.3 | CONTRACTOR'S SITE ESTABLISHMENT AND GENERAL OBLIGATIONS | C31 | |
| C1.4 | FACILITIES FOR THE ENGINEER | C36 | |
| C1.5 | ACCOMMODATION OF TRAFFIC | C36 | |
| C1.7 | LOADING AND HAULING | C39 | |
| C2.1 | GENERAL REQUIREMENTS AND TRENCHING FOR SERVICES | C40 | |
| C2.2 | DRY SERVICES | C41 | |
| C4.1 | BORROW MATERIALS | C42 | |
| C4.2 | CUT MATERIALS | C43 | |
| C4.3 | EXISTING ROAD MATERIALS | C44 | |
| C4.4 | COMMERCIAL MATERIALS | C45 | |
| C5.1 | ROADBED | C46 | |
| C5.2 | FILL | C47 | |
| C5.3 | ROAD PAVEMENT LAYERS | C48 | |
| C5.4 | STABILISATION | C49 | |
| C8.1 | PRIME COAT | C50 | |
| C10.1 | GENERAL REQUIREMENTS FOR SURFACE TREATMENTS | C51 | |
| C11.6 | ROAD SIGNS | C54 | |
| C20.1 | TESTING MATERIALS AND JUDGEMENT OF WORKMANSHIP | C55 | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|---------|--|----------|----------|------|--------------|
| E | EXPANDED PUBLIC WORKS PROGRAMME (EPWP) | | | | |
| E6.01 | Provision of training venue facility, including the cost of transport the learners to and from this facility | Lump Sum | 1 | | |
| E6.02 | Training of learners employed by the contractor or by the Targeted Enterprise subcontractors: | | | | |
| (a) | Generic Skills: | | | | |
| (a.i) | Training costs | Prov Sum | 500 000 | 1.00 | R 500 000.00 |
| (a.ii) | Handling costs and profit in respect of subitem E6.02(a)(i) above. | % | 500 000 | | |
| (b) | Entrepreneurial skills: | | | | |
| (b.i) | Training costs | Prov Sum | 500 000 | 1.00 | R 500 000.00 |
| (b.ii) | Handling costs and profit in respect of subitem E6.02(b)(i) above. | % | 500 000 | | |
| (c) | Construction skills: | | | | |
| (c.i) | Training costs | Prov Sum | 500 000 | 1.00 | R 500 000.00 |
| (c.ii) | Handling costs and profit in respect of subitem E6.02(c)(i) above. | % | 500 000 | | |
| (d) | Transportation and accommodation costs of selected learners only, while receiving off- site training: | | | | |
| (d.i) | Transportation and accommodation costs | Prov Sum | 100 000 | 1.00 | R 100 000.00 |
| (d.ii) | Handling costs and profit in respect of subitem E6.02(d)(i) above. | % | 100 000 | | |
| E | TOTAL CARRIED FORWARD | | | | |
| | | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT | |
|---------|--|----------|----------|------|--------------|--|
| | TOTAL BROUGHT FORWARD | | | | | |
| E6.03 | Payments associated with the NYS programme: | | | | | |
| (a) | Employment of NYS workers | Prov Sum | 500 000 | 1.00 | R 500 000.00 | |
| (b) | Provision of tools and apparel for the NYS workers | Prov Sum | 50 000 | 1.00 | R 50 000.00 | |
| (c) | Handling cost and profit in respect of subitem E6.03(a) and (b) above | % | 550 000 | | | |
| (d) | Training of NYS workers: | | | | | |
| (d.i) | Provision of training for NYS workers | Prov Sum | 900 000 | 1.00 | R 900 000.00 | |
| (d.ii) | Handling costs and profit in respect of subitem E6.03(d)(i) above | % | 900 000 | | | |
| (e) | Liaison with the Employer's project manager and the training service provider: | | | | | |
| (e.i) | Liaison conducted by the construction manager | hr | 60 | | | |
| (e.ii) | Liaison conducted by senior site foreman | hr | 60 | | | |
| (f) | EPWP Branding (refer to spec) | | | | | |
| | (i) Prime cost sum for EPWP branding | PC Sum | 50 000 | 1.00 | R 50 000.00 | |
| | (ii) Handling costs and profit in respect of sub item F5.03(f)(i)above | % | 50 000 | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| E | TOTAL CARRIED FORWARD TO SUMMARY (Page C59) | | | | | |

SCHEDULE F: EXPANDED PUBLIC WORKS PROGRAMME

SUMMARY OF SECTIONS

UPGRADING OF MAIN ROAD P8/3 FROM GRAVEL TO BLACKTOP BETWEEN KM 17.560 AND KM 24.221 IN THE PIETERMARITZBURG REGION

| CHAPTER | DESCRIPTION | | AMOUNT | | |
|-----------|---|--|--------|--|--|
| E | E EXPANDED PUBLIC WORKS PROGRAMME (EPWP) | | | | |
| TOTAL CAR | TOTAL CARRIED FORWARD TO SUMMARY (Page C63) | | | | |

| • | | | | | |
|---------|---|------|----------|------|--------|
| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
| F | SMALL CONTRACTOR DEVELOPMENT | | | | |
| F10.1 | Procurement of Targeted Enterprises: | | | | |
| (a) | Management and execution of Targeted Enterprise procurement process: | | | | |
| (a.i) | Procurement process for the appointment of CIDB contractor grading designation 1 Targeted Enterprise subcontractor (100 copies of the tender document required for each individual tender) | No | 8 | | |
| (a.ii) | Procurement process for the appointment of CIDB contractor grading designation 2 Targeted Enterprise subcontractor (80 copies of the tender document required for each individual tender) | No | 10 | | |
| (a.iii) | Procurement process for the appointment of CIDB contractor grading designation 3 Targeted Enterprise subcontractor (60 copies of the tender document required for each individual tender) | No | 4 | | |
| (a.iv) | Procurement process for the appointment of CIDB contractor grading designation 4 Targeted Enterprise subcontractor (50 copies of the tender document required for each individual tender) | No | 1 | | |
| (a.v) | Procurement process for the appointment of CIDB contractor grading designation 5 Targeted Enterprise subcontractor (40 copies of the tender document required for each individual tender) | No | 1 | | |
| (a.vi) | Procurement process for the appointment of CIDB contractor grading designation 6 Targeted Enterprise subcontractor (40 copies of the tender document required for each individual tender) | No | 0 | | |
| | | | | | |
| F | TOTAL CARRIED FORWARD | | | | |
| - | | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|---------|--|----------|---------------|------|-----------------|
| | TOTAL BROUGHT FORWARD | | | | |
| F10.2 | Construction Works for Targeted Enterprise subcontractors: | | | | |
| (a) | Payments associated with the construction Works carried out by Targeted Enterprise subcontractors | Prov Sum | 27 696 357.95 | 1.00 | R 27 696 357.95 |
| (b) | Handling costs and profit in respect of subitem F10.02(a) | % | 27 696 357.95 | | |
| (c) | Supply of materials and small construction equipment to assist Targeted Enterprise subcontractors | Prov Sum | 1 457 703.05 | 1 | R 1 457 703.05 |
| (d) | Handling costs and profit in respect of subitem F10.02(c) | % | 1 457 703.05 | | |
| (e) | Management of the Targeted Enterprise subcontractors | Month | 18 | | |
| (a) | Generic Skills | | | | |
| (a.i) | Training costs | Prov Sum | 150 000 | 1.00 | R 150 000.00 |
| (a.ii) | Handling costs and profit in respect of subitem F10.03(a)(i) | % | 150 000 | | |
| (b) | Entrepreneurial skills: | | | | |
| (b.i) | Training costs | Prov Sum | 200 000 | 1.00 | R 200 000.00 |
| (b.ii) | Handling costs and profit in respect of subitem F10.03(b)(i) | % | 200 000 | | |
| (c) | Construction skills: | | | | |
| (c.i) | Training costs | Prov Sum | 300 000 | 1.00 | R 300 000.00 |
| (c.ii) | Handling costs and profit in respect of subitem F10.03(c)(i) | % | 300 000 | | |
| (d) | Transportation and accommodation costs of selected learners only, while receiving off- site training: | | | | |
| (d.i) | Transportation and accommodation costs | Prov Sum | 295 000.00 | 1.00 | R 295 000.00 |
| (d.ii) | Handling costs and profit in respect of subitem F10.03(d)(i) | % | 295 000.00 | | |
| F | TOTAL CARRIED FORWARD TO SUMMARY (Page C62) | | | | |

SCHEDULE F: CONTRACT PARTICIPATION GOALS

SUMMARY OF SECTIONS

UPGRADING OF MAIN ROAD P8/3 FROM GRAVEL TO BLACKTOP BETWEEN KM 17.560 AND KM 24.221 IN THE PIETERMARITZBURG REGION

| CHAPTER | DESCRIPTION | FROM PAGE | AMOUNT |
|---|------------------------------|--------------|--------|
| F | SMALL CONTRACTOR DEVELOPMENT | | |
| TOTAL CARRIED FORWARD TO SUMMARY (Page C63) | | | |

C2.3 SUMMARY OF BILL OF QUANTITIES

UPGRADING OF MAIN ROAD P8/3 FROM GRAVEL TO BLACKTOP BETWEEN KM 17.560 AND KM 24.221 IN THE PIETERMARITZBURG REGION

| DESCRIPTION | FROM PAGE | AMOUNT |
|--|--------------|--------|
| TOTAL SCHEDULE A : ROADWORKS CS | | |
| TOTAL SCHEDULE E: EXPANDED PUBLIC WORKS PROGRAMME | C59 | |
| TOTAL SCHEDULE F: CONTRACT PARTICIPATION GOALS | | |
| Subtotal 1 | | |
| CONTINGENCIES (10.0% of Subtotal 1) | | |
| Subtotal 2 | | |
| CONTRACT PRICE ADJUSTMENT AND RISE & FALL (10.0% of Subtot | tal 2) | |
| Subtotal 3 | | |
| VAT (15% of Subtotal 3) | | |
| TOTAL CARRIED FORWARD TO FORM OF OFFER (C1.1.1) | | |

| Signed on behalf of the Tenderer: | Signature) |
|-----------------------------------|------------|
|-----------------------------------|------------|

Date:

Tenderer's Name: (Company Name)

PART C3: SCOPE OF WORK

| TABL | <u>E OF CONTENTS</u> | | PAGE |
|------|---|--------------------|---------------------------------|
| C3.1 | STANDARD SPECIFICATIONS | | C65 |
| C3.2 | PROJECT SPECIFICATIONS | | C65 |
| | PART A: GENERAL | | |
| | DESCRIPTION OF THE WORKS DRAWINGS PROCUREMENT CONSTRUCTION MANAGEMENT | | C66 C75 C79 C79 C79 |
| | PART B: AMENDMENTS TO THE STANDA | ARD SPECIFICATIONS | |
| | PROJECT SPECIFICATIONS RELATING TO T SPECIFICATIONS AND OTHER ADDITIONAL | | C83 |
| C3.3 | PARTICULAR SPECIFICATIONS | | |
| | PART C: ENVIRONMENTAL MANAGEMENT | SPECIFICATION | C90 |
| | PART D: OHSA 1993 HEALTH AND SAFET | Y SPECIFICATION | C96 |
| | PART E: EXPANDED PUBLIC WORKS PRO | GRAMME | C126 |
| | PART F: SMALL CONTRACTOR DEVELOP | MENT | C161 |
| | | | |

C3.1: STANDARD SPECIFICATIONS

The Standard Specifications on which this contract is based are the 'Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020'.

C3.2: PROJECT SPECIFICATIONS

The Project Specifications, consisting of two parts, form an integral part of the Contract and supplement the Standard Specifications.

Part A contains a general description of the Works, the Site and the requirements to be met.

Part B contains variations, amendments and additions to the Standard Specifications and, if applicable, the Particular Specifications.

In the event of any discrepancy between a part or parts of the Standard or Particular Specifications and the Project Specifications, the Project Specifications shall take precedence. In the event of a discrepancy between the Specifications (including the Project Specifications) and the drawings and / or the Bill of Quantities, the discrepancy shall be resolved by the Employer's Agent before the execution of the work under the relevant item.

The Standard Specifications, which form part of this contract, have been written to cover all phases of work normally required for road contracts, and they may therefore cover items not applicable to this particular contract.

C3.2: PROJECT SPECIFICATIONS

PART A: GENERAL

1. DESCRIPTION OF THE WORKS

1.1 Employer's objectives

This Project forms part of the Province of KwaZulu-Natal Department of Transport's Upgrading Programme. This Contract is for the upgrading of P8/3 from gravel to blacktop from km 17.560 to km 24.221. The vertical and horizontal alignment will also be changed from the existing alignment to conform to the design specifications. The section of P8/3 that is to be upgraded is located west of Creighton.

The contract is located in a region of KwaZulu-Natal that has been historically impoverished by a lack of infrastructure access. It is therefore mandatory that the Contractor shall interact with the community via proactive project liaison with and project participation by its leaders and constituted organisations and forums, as well as through the employment of its people, and these activities shall constitute essential facets of the project.

The Employer's objectives in delivering public infrastructure and services for this project include the provision of temporary work opportunities to the local community through the application of labourenhanced methods to the maximum extent feasible, in accordance with the Expanded Public Works Programme (EPWP) Guidelines.

The Contractor shall be required to attend meetings of the local Project Liaison Committee (PLC) from time to time. The requirements of the Expanded Public Works Programme (EPWP) are contained in Part E of section C3.3 Particular Specifications. These EPWP requirements also include provisions for the National Youth Service programme where applicable.

1.2 Location of the Works

The Works are located about 5 km west of Creighton along the P8/3 in the Dr. Nkosazana Dlamini-Zuma Local Municipality KZ No. 436. See Locality plan under C4.1.

1.3 Overview of the Works

The project comprises of the construction of 6.66 kilometres of layer works and seal surfacing with a surfaced width of 8.5 m, including the associated road prism drainage, culverts, roadside furniture and intersection construction/upgrades.

1.4 Extent of the Works

The Works to be carried out include the following main activities:

- (a) Establishment on site and clearing and grubbing.
- (b) Provision of traffic accommodation facilities.
- (c) Survey requirements.
- (d) 150mm Rip and recompact the roadbed compacted to 90% Mod AASHTO.
- (e) 150mm G6 imported material compacted to 95% Mod AASHTO.
- (f) 200mm imported C4 material stabilized with 3% cement and compacted to 98% Mod AASHTO.
- (g) 150m imported G2 material compacted to 102% Mod AASHTO
- (h) 20/10mm 70/100 Penetration Bitumen Double Seal surfacing.
- (i) Road prism drainage.
- (j) Extension of existing culverts
- (k) Construction of new precast culvert
- (I) Construction of new cast in-situ reinforced concrete box culvert

- (m) Rehabilitation of parapet walls of existing bridge.
- (n) Construction of erosion protection measures (gabions, stone pitching, etc.)
- (o) Installation of guardrails, where required.
- (p) Installation of new road signs.
- (q) New road markings and road studs.
- (r) Finishing and cleaning up of the road and road reserve.
- (s) Continuous quality control over materials and workmanship, and compliance with the Particular Specifications with regards to environmental management and occupational health and safety, during all the above construction activities.
- (t) Removal of all site establishment facilities and constructional plant on completion of the Works.
- (u) Making good of any defects during the 12 months Defects Liability Period.

1.5 Detailed description of the Works

The following description is a broad outline of the works and does not limit the work to be executed by the Contractor in terms of the contract. The description of some of the major items indicated in this section are indicative, not absolute, and are provided to define in general terms the overall scope of the project.

Approximate quantities of each type of work to be carried out in accordance with the contract documents are to be listed in the Schedule of Quantities once the roads are identified.

The site shall not only comprise the proclaimed road reserve but shall be extended in the broader sense to take account of all areas occupied by the Contractor, be it deliberate or unintentional, in the execution of the contract. The site includes all the land within the proclaimed limits of the road reserve along the extent of the works, borrow pits and quarry sites, stockpile areas, locations set aside for construction and supervision accommodation and any other location required for the execution of the Works.

Incidental intrusion into private or tribal property outside the road reserve shall not be permitted without the owner's written authority. Any such agreement reached with a private or tribal landowner (occupier) shall include the proviso that any material or equipment on that site shall remain the exclusive property of the Employer in terms of the contract.

The Department requires the contractors to establish the necessary machines and personnel to carry out the extent of all the works. This includes upgrading the alignment, drainage and surfacing of P8/3 as indicated on the drawings.

The contractor is responsible for all traffic control and safety in the area of the works. One lane must be available to the travelling public at all times and the maximum length of roadway to be under construction at any one time is 2 kilometres. At night all obstructions must be removed and the necessary signs such as no lines, loose stones, speed limits, etc must be left on the site to ensure that the travelling public are safe. Some of these signs will need to be left on the road until such time that the road marking has been completed.

After surfacing with the necessary attention to the joints and edges, the roadway must be broomed to remove the excess aggregate.

The site camp and aggregate stock pile sites must be cleared and cleaned to the satisfaction of the Department or its representative. This must include excess stone in the drainage elements. Spilt bitumen and the cut off paper must be suitably disposed of at a registered waste disposal dump or as set out in the Environmental Management Plan.

1.5.1 Access to the Site

Access to the Site can be obtained from Road P8/3 from the west of Creighton.

Throughout the duration of the contract, Roads shall be shared with other contractors engaged by the KwaZulu-Natal Department of Transport on the identified projects whose construction activities may affect access from time to time. The Contractor shall therefore be required to liaise on an ongoing basis with these other contractors with respect to access related matters throughout the duration of the contract.

1.5.2 Demolition work

The Contractor is required to carry out demolition work to existing stormwater structures that require upgrading or replacement as shown in the drawings.

1.5.3 Spoiling of surplus material

Surplus material shall be spoiled in designated areas approved by the Employer's Agent. The spoil material shall be disposed of in accordance with subclause A4.1.7.2(I) of the COTO Standard Specifications.

1.5.4 Quantities

| Description | Source | Approximate quantity | |
|---|---|-----------------------|--|
| Selected layers – G9 and G7 | Stockpile/borrow – refer to materials report | 11 100 m ³ | |
| Selected material G7 – gravel shoulders | Stockpile/borrow – refer to materials report | 1 800 m³ | |
| Stabilised subbase layer – G6 | Commercial sources | 15 633 m³ | |
| Base layer – G2 | Commercial sources | 10 300 m ³ | |
| Concrete for lined drains | Commercial sources | 2 005 m ³ | |
| Guardrails | Commercial sources | 1 420 m | |

The approximate leading quantities for the permanent Works to be constructed are as follows:

1.5.5 Material investigations

Materials information is furnished in section C4.4 at the end of this document.

1.5.6 Material sources, spoil and stockpile areas

Where possible, the contractor shall source material from within 3 km of the site utilizing local labour. The material which may be sourced from site includes:

Rock for gabions and stone pitching

All layer works shall be obtained either from borrow pits or from commercial sources.

The material for the G2 base and all concrete materials shall be obtained from commercial sources.

Spoil areas and areas for the temporary stockpiling of construction materials shall be determined and agreed on site in conjunction with the Employer's Agent, the PLC (where applicable) and the local communities (where applicable). The Contractor shall be permitted to use only these agreed spoil and stockpile areas, which shall be landscaped and vegetated on completion of the work.

1.5.7 Accommodation of traffic

The Contractor shall be required to accommodate traffic on the existing roadway A traffic study was done in 2012, based on the values obtained from the traffic count it is expected that roughly 400 vehicles make use of P8/3 per day. 30% of these vehicles are heavy vehicles.

1.5.8 Accommodation of other contractors

No other construction contracts in the area are envisaged. However, if roads or borrow pits are shared with other contractors engaged by the KwaZulu-Natal Department of Transport the Contractor shall be required to liaise on an ongoing basis with these other contractors with respect to access related matters throughout the duration of the contract.

1.5.9 Existing services

All the known existing services are indicated on the layout drawings.

It is also expected that unknown domestic services crossings requiring relocation or protection may be encountered along the route as the work proceeds. The Contractor shall make every effort to establish the location of these services in any area prior to excavations commencing in that area. Such efforts shall include diligent enquiry and discussions with adjacent landowners, visual surface inspection and exploratory trenching investigation, as necessary.

1.5.10 Employer's Agent's site offices and laboratory

The Contractor shall be required to provide furnished site office facilities, laboratory facilities, ablution facilities, and carports for the Employer's Agent at a site located near the Contractor's office establishment and to the Works. A possible area for such site establishment shall be indicated at the Site Clarification Meeting.


1.5.11 Climate

A summary of the climatic statistics is given in **Table 1.1** below. Information obtained from www.timeanddate.com for Cedara, 71km from Ixopo between 2005 and 2015, was used for the calculations.

TABLE 1.1: CLIMATIC STATISTICS

| Property | Value |
|------------------------------------|---------|
| Average Annual Maximum Temperature | 22°C |
| Average Annual Minimum Temperature | 12ºC |
| Highest Maximum Temperature | 28.0° |
| Lowest Minimum Temperature | 3.0° |
| Average Annual Rainfall | 589.6mm |
| Maximum Monthly Rainfall | 103.9mm |

This is a high summer rainfall area with an average annual rainfall of 589.6mm. Most rain occurs from October to April. The maximum average daily summer temperature is 28°C and the minimum average daily winter temperature is 12°C.



The average temperatures and precipitation are shown in **Figure 3** below

FIGURE 3: FIGURE SHOWING EXPECTED TEMPERATURE FLUCTUATION IN IXOPO

1.5.12 Environment

The Contractor's attention is called to clause A1.2.3.3 of Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020 and to the requirements of Part C: Environmental Management Specification contained in section C3.3 Particular Specifications.

1.5.13 Labour

A Project Liaison Committee (PLC) has been established and is a vital means of communication between all parties involved with the project. The composition of the PLC comprises representatives of the Employer, the Employer's Agent and formal structures within the community.

The Contractor shall make use of these communication channels, and shall appoint from amongst his site personnel a responsible person to participate in the affairs of the PLC, and this representative will be also required to attend the monthly PLC meetings.

It is mandatory that the Contractor shall interact with the community via proactive project liaison and project participation by its leaders and constituted organisations and forums, as well as through the employment of its people, and these activities shall constitute essential facets of the project.

Local labour is to be used and the employment of such labour is to be done in conjunction with the PLC. The PLC has formed a Labour Committee who shall assist the Contractor with the recruitment of local labourers to ensure an equal distribution of people employed between the various Amakosi in the area.

1.5.14 Labour-enhanced construction methods

- Labour-enhanced construction shall mean the economically efficient employment of as great a portion
 of labour as is technically feasible to produce a standard of construction as demanded by the
 specifications with completion by the Due Completion Date, thus bringing about the effective
 substitution of labour for plant and equipment.
- •
- Appropriate portions of the Works included in the Contract shall be executed using labour-enhanced construction methods.
- •
- Except where the use of plant is essential in order, in the opinion of the Employer's Agent, to meet the specified requirements by the Due Completion Date, or where the use of plant is essential as a result of occupational health and safety considerations, the Contractor shall use only hand tools and equipment in the construction of those portions of the Works that are required in terms of these Project Specifications to be constructed using labour-enhanced construction methods.
- •
- These portions of the Works shall be constructed utilizing only locally employed labour and/or the labour of local subcontractors, supplemented by the Contractor's key personnel to the extent necessary and unavoidable, unless otherwise instructed by the Employer's Agent and in accordance with the further provisions of the relevant sections of Portion B of the Project Specifications.
- •
- Subject to considerations of occupational health and safety, the portions of the Works to be executed using labour-enhanced construction methods are:
- •
- Clearing and grubbing of the Site;
- Excavation for structures up to 1,5 m deep;
- Bedding, selected fill, backfilling and compaction of all pipe trenches irrespective of depth, but assisted by mechanical compaction equipment in order to achieve the specified densities;
- Transportation and spoiling of all trench materials, where the disposal site is located within 20 metres of the source;
- Dismantling and re-erection of fences;
- Mixing and placing of concrete;
- Construction of all brickwork required for structures; and
- Cleaning and tidying up of the Site.

1.6 Temporary Works

The Temporary Works required under this Contract shall include the traffic accommodation measures implemented, the provision of drainage control, falsework and formwork during the construction of the minor drainage structures, and the provision of any scaffolding or temporary propping used during the erection of the road signs.

All Temporary Works shall be removed from the Site on completion of the Contract.

1.7 Maintenance of the Works during the construction period

The Contractor shall take note of the various requirements of the General Conditions of Contract 2015 and the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020 with respect to the care and protection of the Works.

The handing-over of the road reserve for this contract is described in clause A1.2.3 of Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020. The Contractor shall be responsible for maintaining this portion of the road from the date of hand-over until the issue of the Certificate of Practical Completion.

1.8 Testing of materials

A prime cost sum has been allowed in chapter 20 of the Bill of Quantities for all acceptance control testing laboratory work to be carried out by the Employer's Agent using the laboratory facilities which may include and/or commercial laboratory facilities.

The Contractor shall carry out at his own cost the required process control testing as specified in terms of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020.

1.9 Power supply and other services

The Contractor shall make his own arrangements concerning the supply of electrical power and all other services. No direct payment shall be made for the provision of electrical and other services. The cost thereof shall be deemed to be included in the rates and amounts tendered for the various items of work for which these services are required.

1.10 Construction in confined areas

It may be necessary for the Contractor to work within confined areas. Except where provided for in the specifications, no additional payment shall be made for work done in restricted areas. In certain places the width of the fill material and pavement layers may decrease to zero and the working space may be confined. The method of construction in these confined areas largely depends on the Contractor's constructional plant. However, the Contractor shall note that, unless otherwise provided for in terms of the scheduled payment items in the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020 or these project specifications, measurement and payment shall be in accordance with the specified cross sections and dimensions only, irrespective of the method used for achieving these cross sections and dimensions, and that the tendered rates and amounts shall include full compensation for all special equipment and construction methods and for all difficulties encountered when working in confined areas and narrow widths, and at or around obstructions, and that no extra payment shall be made nor shall any claim for additional payment be considered in such cases.

1.11 Contractor's campsite (Project Specific)

Possible locations for a campsite shall be pointed out at the clarification meeting.

The Contractor shall make his own arrangements for the provision of his campsite and housing for construction personnel but the chosen site shall be subject to the approval of the Employer's Agent, the local authorities and, where applicable, the Project Liaison Committee (PLC) associated with the project.

The standard of the Contractor's camp, offices, accommodation, ablution, and other facilities must comply with the requirements of all local authority, environmental and industrial regulations concerned. In establishing and maintaining his campsite, due cognisance is to be taken of the requirements of clause A1.3.3 of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020.

The Contractor is to fully familiarise himself with all local by-laws and Government regulations for the employment, transport and accommodation of labour on site.

The Contractor shall particularly note that there is a high risk of theft, vandalism and damage to property in this area and strict security will be required for all plant, establishment, temporary works and partially completed works. The Contractor shall be responsible for providing security for all plant, establishment, temporary works and partially completed works. No separate payment shall be made for the provision of such security since full compensation for these costs shall be deemed to be included in the amount tendered for item C1.3.1.3 (The contractor's general obligations: Time-related obligations).

1.12 Additional requirements for construction activities

The travelling public shall have the right of way on public roads, and the Contractor shall make use of approved methods to control the movement of his equipment and vehicles so as not to constitute a hazard on the road.

The Contractor's tendered rates shall include full compensation for all costs which may arise from the construction and maintenance of deviations and construction under traffic. No claim for additional costs which may arise from these methods of traffic accommodation and no additional payment owing to inconvenience as a result of the Contractor's method of working shall be considered.

1.13 Construction programme

The Contractor shall submit a detailed time programme in accordance with clause 5.6.2 of the General Conditions of Contract 2015, clause A1.2.7 of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020.


In addition to any other restrictions accommodated by the Contractor in compiling the construction programme, the following constraints shall be taken into account in the preparation thereof:

- (a) The whole of the Works (and the portions of the Works if completion in portions is required) shall be completed within the time period(s) stated (refer to the Contract Data in section C1.2.2).
- (b) Working days lost due to abnormal rainfall shall be treated as set out in clause A1.2.3.4 (b)
- (c) Allowance shall be made for non-working days and special non-working days (refer to the Contract Data in section C1.2.2).
- (d) Construction activities must comply with all the specified environmental requirements including clause A1.2.3.3 of Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020 and the requirements of Part C: Environmental Management Specification contained in section C3.3 Particular Specifications.
- (e) Construction activities must comply with all the specified health and safety obligations including the requirements of Part D: OHSA 1993 Health and Safety Specification contained in section C3.3 Particular Specifications.
- (f) Strict control of access to and from local public roads shall be required when construction vehicles, plant or equipment leave or enter the site.
- (g) Throughout the contract period traffic must be accommodated through the site and all other contractors engaged on the construction of identified roads must be accommodated.
- (h) The Contractor's programme of work shall take due cognisance of risks by limiting the duration of the exposure of the various construction elements to natural phenomena.

For the guidance of Tenderers, a provisional preliminary construction programme is included below. This programme is given in good faith and no claims shall be entertained due to inaccuracies, discrepancies or omissions contained in the programme.

Department of Transport

PRELIMINARY CONSTRUCTION PROGRAMME



2. DRAWINGS

The drawings that form part of the Tender documents are issued on a CD and shall be used for Tender purposes only.

The Contractor will be supplied with three complete sets of A0 paper print drawings, and one set of drawings on a CD. These A0 paper prints and CD are issued free of charge and the Contractor shall make any additional copies he may require at his own cost.

Any information in the possession of the Contractor which the Employer's Agent requires to complete the as-built drawings shall be supplied to the Employer's Agent before a certificate of completion will be issued.

Only figured dimensions shall be used and drawings shall not be scaled unless so instructed by the Employer's Agent. The Employer's Agent will supply all figures / dimensions omitted from the drawings.

The levels given on the drawings are subject to confirmation on site, and the Contractor shall submit all levels to the Employer's Agent for confirmation before he commences any structural construction work. The Contractor shall also check all clearances given on the drawings and shall inform the Employer's Agent of any discrepancies.

| DESCRIPTION | DRAWING NO. |
|---|-------------|
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | C46184 |
| 560 - Km 24 + 170 -Index Plan | 646184 |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Design Plan/Expropriation/Service | C46185 |
| Plan- Sheet 1 of 7 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Design Plan/Expropriation/Service | C46186 |
| Plan- Sheet 2 of 7 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Design Plan/Expropriation/Service | C46187 |
| Plan- Sheet 3 of 7 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Design Plan/Expropriation/Service | C46188 |
| Plan- Sheet 4 of 7 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Design Plan/Expropriation/Service | C46189 |
| Plan- Sheet 5 of 7 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Design Plan/Expropriation/Service | C46190 |
| Plan- Sheet 6 of 7 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 | C46191 |
| -Design Plan/Expropriation/Service Plan- Sheet 7 of 7 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | C46192 |
| 560 - Km 24 + 170 -Long Section- Sheet 1 of 10 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | C46193 |
| 560 - Km 24 + 170 - Long Section - Sheet 2 of 10 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | C46194 |
| 560 - Km 24 + 170 - Long Section - Sheet 3 of 10 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | C46195 |
| 560 - Km 24 + 170 - Long Section - Sheet 4 of 10 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | C46196 |

| 580 - Km 24 + 170 - Long Section- Sheet 5 of 10 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + C46197 580 - Km 24 + 170 - Long Section- Sheet 6 of 10 C46198 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + C46198 S60 - Km 24 + 170 - Long Section- Sheet 8 of 10 C46200 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + C46200 S60 - Km 24 + 170 - Long Section- Sheet 9 of 10 C46200 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + C46201 S60 - Km 24 + 170 - Long Section- Sheet 1 of 10 C46202 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + C46203 S60 - Km 24 + 170 - Cross Section- Sheet 2 of 23 C46204 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + C46203 S60 - Km 24 + 170 - Cross Section- Sheet 3 of 23 C46204 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + C46205 S60 - Km 24 + 170 - Cross Section- Sheet 3 of 23 C46206 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + C46206 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + C46206 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + C46208 C460 - Km 24 + 170 - Cross Section- Sheet 7 of 23 C46208 Upgrade Of A Portion Of Ma | DESCRIPTION | DRAWING NO. |
|---|--|-------------|
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 · Km 24 + 170 - Long Section - Sheet 6 of 10C46197Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 · Km 24 + 170 - Long Section - Sheet 8 of 10C46199Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 · Km 24 + 170 - Long Section - Sheet 9 of 10C46200Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 · Km 24 + 170 - Long Section - Sheet 10 of 10C46201Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 · Km 24 + 170 - Long Section - Sheet 10 c13C46203Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 · Km 24 + 170 - Cross Section - Sheet 10 c23C46203Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 · Km 24 + 170 - Cross Section - Sheet 20 c23C46204Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 · Km 24 + 170 - Cross Section - Sheet 20 c23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 · Km 24 + 170 - Cross Section - Sheet 50 c23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 · Km 24 + 170 - Cross Section - Sheet 50 c23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 · Km 24 + 170 - Cross Section - Sheet 50 c23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 · Km 24 + 170 - Cross Section - Sheet 70 c23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 · Km 24 + 170 - Cross Section - Sheet 10 c123C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 · Km 24 + 170 - Cross Section - Sheet 10 c123C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 · Km 24 + 170 - Cross Section - Sheet 10 c123C46212 | 560 - Km 24 + 170 -Long Section- Sheet 5 of 10 | |
| 580 - Km 24 + 170 - Long Section - Sheet 6 of 10 C46197 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Long Section - Sheet 8 of 10 C46198 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Long Section - Sheet 8 of 10 C46200 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Long Section - Sheet 8 of 10 C46201 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Long Section - Sheet 1 of 10 C46202 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 1 of 23 C46203 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 2 of 23 C46204 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 3 of 23 C46205 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23 C46206 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 6 of 23 C46208 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 8 of 23 C46208 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 8 of 23 C46210 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 19 of 23 C46211 <t< td=""><td></td><td></td></t<> | | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Long Section - Sheet 7 of 10 C46198 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Long Section - Sheet 8 of 10 C46199 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Long Section - Sheet 9 of 10 C46200 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Long Section - Sheet 1 of 23 C46202 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 1 of 23 C46203 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 3 of 23 C46205 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 3 of 23 C46205 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23 C46206 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 7 of 23 C46208 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 7 of 23 C46209 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 8 of 23 C46210 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23 C46210 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 1 | 10 | C46197 |
| 560 - Km 24 + 170 - Long Section - Sheet 7 of 10C46198Upgrade Of A Portion Of Main Road & 3 From Km 17 + 560 - Km 24 + 170 - Long Section - Sheet 9 of 10C46199Upgrade Of A Portion Of Main Road & 3 From Km 17 + 560 - Km 24 + 170 - Long Section - Sheet 9 of 10C46200Upgrade Of A Portion Of Main Road & 3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 10C46201Upgrade Of A Portion Of Main Road & 3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 2 of 23C46203Upgrade Of A Portion Of Main Road & 3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 2 of 23C46204Upgrade Of A Portion Of Main Road & 3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 3 of 23C46205Upgrade Of A Portion Of Main Road & 3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23C46206Upgrade Of A Portion Of Main Road & 3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23C46206Upgrade Of A Portion Of Main Road & 3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 6 of 23C46208Upgrade Of A Portion Of Main Road & 3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 8 of 23C46209Upgrade Of A Portion Of Main Road & 3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 8 of 23C46210Upgrade Of A Portion Of Main Road & 3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23C46211Upgrade Of A Portion Of Main Road & 3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23C46213Upgrade Of A Portion Of Main Road & 3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 13 of 23C46213Upgrade Of A Portion Of Main | | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Long Section - Sheet 8 of 10 C46199 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Long Section - Sheet 9 of 10 C46200 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 1 of 10 C46201 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 1 of 23 C46203 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 2 of 23 C46204 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 3 of 23 C46205 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 3 of 23 C46206 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23 C46206 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 7 of 23 C46208 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 8 of 23 C46210 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23 C46211 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 11 of 23 C46213 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Shee | 10 | C46198 |
| 560Km 24 + 170 - Long Section - Sheet 8 of 10C46199Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Long Section - Sheet 9 of 10C46200Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Long Section - Sheet 1 of 12C46201Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 1 of 23C46203Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 2 of 23C46204Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 3 of 23C46205Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23C46207Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23C46207Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 7 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 7 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 11 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 13 of 23C46213Upgrade Of A Portion Of | | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Long Section - Sheet 9 of 10C46200Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 1 of 23C46201Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 2 of 23C46203Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 3 of 23C46204Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 3 of 23C46205Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 4 of 23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 8 of 23C46209Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 8 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 1 0 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 1 0 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 1 1 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 13 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 13 of 23< | 10 | C46199 |
| 560 - Km 24 + 170 - Long Section - Sheet 9 of 10C46200Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Orcoss Section - Sheet 1 of 10C46201Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Orcoss Section - Sheet 2 of 23C46203Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Orcoss Section - Sheet 3 of 23C46204Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Orcoss Section - Sheet 3 of 23C46205Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Orcoss Section - Sheet 3 of 23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Orcoss Section - Sheet 5 of 23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Orcoss Section - Sheet 6 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Orcoss Section - Sheet 8 of 23C46209Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Orcoss Section - Sheet 8 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Orcoss Section - Sheet 10 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Orcoss Section - Sheet 10 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Orcoss Section - Sheet 11 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Orcoss Section - Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Orcoss Section - Sheet 13 of 23C46216Upgrade Of A | | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Long Section- Sheet 1 of 10 C46201 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 2 of 23 C46203 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 3 of 23 C46204 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 4 of 23 C46205 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 5 of 23 C46206 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 5 of 23 C46207 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 6 of 23 C46209 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 7 of 23 C46209 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 9 of 23 C46210 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 10 of 23 C46211 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23 C46212 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23 C46214 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23< | | C46200 |
| 560Km 24 + 170 -Long Section- Sheet 10 of 10C46201Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 2 of 23C46203Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 3 of 23C46204Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 3 of 23C46205Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 5 of 23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 5 of 23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 5 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 5 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 9 of 23C46209Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 10 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 11 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 13 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 | | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 1 of 23C46203Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 2 of 23C46203Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 3 of 23C46204Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 4 of 23C46205Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 6 of 23C46207Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 7 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 9 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 13 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 14 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 15 of 23 </td <td></td> <td>C46201</td> | | C46201 |
| 560 - Km 24 + 170 - Cross Section - Sheet 1 of 23C46202Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 2 of 23C46204Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 4 of 23C46205Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 4 of 23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 6 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 8 of 23C46209Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 8 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 9 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 11 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 14 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 14 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 15 of 23C46216Upgrade Of A Portion Of | | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 2 of 23C46203Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 3 of 23C46204Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 4 of 23C46205Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23C46207Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 7 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 8 of 23C46209Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 11 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 14 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 16 of 23< | | C46202 |
| 560 - Km 24 + 170 - Cross Section - Sheet 2 of 23C46203Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 3 of 23C46204Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 4 of 23C46205Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23C46207Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 7 of 23C46209Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 9 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 13 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 14 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 15 of 23C46216Upgrade Of A Portion Of | | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 3 of 23C46204Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 4 of 23C46205Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 5 of 23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 6 of 23C46207Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 7 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 8 of 23C46209Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 8 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 10 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 11 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 11 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 14 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46217 | | C46203 |
| 560 - Km 24 + 170 - Cross Section - Sheet 3 of 23C46204Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 4 of 23C46205Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 6 of 23C46207Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 7 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 8 of 23C46209Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 11 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 12 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 13 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 14 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 15 of 23C46217Upgrade Of A Portion O | | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 4 of 23C46205Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 5 of 23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 6 of 23C46207Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 7 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 8 of 23C46209Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 9 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 10 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 11 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46217 | 15 | C46204 |
| 560 - Km 24 + 170 - Cross Section - Sheet 4 of 23C46205Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 6 of 23C46207Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 7 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 8 of 23C46209Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 11 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 12 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 13 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 16 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 16 of 23C46217Upgrade Of A Portion | | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 5 of 23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 6 of 23C46207Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 7 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 8 of 23C46209Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 9 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 10 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 11 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 14 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C4621 | | C46205 |
| 560 - Km 24 + 170 - Cross Section - Sheet 5 of 23C46206Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 6 of 23C46207Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 7 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 8 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 9 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 11 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 11 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 12 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 14 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 14 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 17 of 23C46218Upgrade Of A Portion | | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 6 of 23C46207Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 7 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 8 of 23C46209Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 10 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 10 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 11 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46 | | C46206 |
| 560 - Km 24 + 170 - Cross Section- Sheet 6 of 23C46207Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 7 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 8 of 23C46209Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 10 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 11 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 14 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road | | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 7 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 8 of 23C46209Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 9 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 11 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 12 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 14 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 15 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 15 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 15 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 18 of | 10 | C46207 |
| 560 - Km 24 + 170 - Cross Section - Sheet 7 of 23C46208Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 8 of 23C46209Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 10 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 12 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 13 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 14 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 15 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 16 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 17 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section - Sheet 18 of 23C46219Upgrade Of A Porti | | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 8 of 23C46209Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 10 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 11 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 14 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C | 10 | C46208 |
| 560 - Km 24 + 170 - Cross Section- Sheet 8 of 23C46209Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 10 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 11 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 14 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 14 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Roa | | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 10 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 11 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 14 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23 | | C46209 |
| 560 - Km 24 + 170 - Cross Section- Sheet 9 of 23C46210Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 10 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 11 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 14 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219 | | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 10 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 11 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 14 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23 <td< td=""><td>10</td><td>C46210</td></td<> | 10 | C46210 |
| 560 - Km 24 + 170 - Cross Section- Sheet 10 of 23C46211Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 11 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 14 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 14 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219 | | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 11 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 13 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 14 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 16 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 17 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219 | | C46211 |
| 560 - Km 24 + 170 -Cross Section- Sheet 11 of 23C46212Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 14 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 14 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 17 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219 | | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 14 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219 | | C46212 |
| 50Km 24 + 170 - Cross Section- Sheet 12 of 23C46213Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 14 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219 | | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 14 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219 | 10 | C46213 |
| 560 - Km 24 + 170 - Cross Section- Sheet 13 of 23C46214Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 14 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219 | | |
| 560 - Km 24 + 170 -Cross Section- Sheet 14 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219 | | C46214 |
| 560 - Km 24 + 170 -Cross Section- Sheet 14 of 23C46215Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219 | Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | 0.400.4.5 |
| 560 - Km 24 + 170 -Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219 | | C46215 |
| 560 - Km 24 + 170 -Cross Section- Sheet 15 of 23C46216Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219 | Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | • |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219 | | C46216 |
| 560 - Km 24 + 170 - Cross Section- Sheet 16 of 23C46217Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 - Cross Section- Sheet 18 of 23C46219 | Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | 0.400.47 |
| 560 - Km 24 + 170 -Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + C46220C46220 | | 646217 |
| 560 - Km 24 + 170 -Cross Section- Sheet 17 of 23C46218Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + C46220C46220 | Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | 040040 |
| 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23C46219Upgrade Of A Portion Of Main Road 8-3 From Km 17 + C46220C46220 | | C46218 |
| 560 - Km 24 + 170 -Cross Section- Sheet 18 of 23 Upgrade Of A Portion Of Main Road 8-3 From Km 17 + C46220 | Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | 040040 |
| (46/20) | 10 | G46219 |
| (26/20) | Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | C46220 |
| | 560 - Km 24 + 170 -Cross Section- Sheet 19 of 23 | G40ZZU |

| DESCRIPTION | DRAWING NO. |
|---|-------------|
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 - Cross Section- Sheet 20 of 23 | C46221 |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + 560 - Km 24 + 170 -Cross Section- Sheet 21 of 23 | C46222 |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 - Cross Section- Sheet 22 of 23 | C46223 |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | C46224 |
| 560 - Km 24 + 170 - Cross Section- Sheet 23 of 23 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | 0.40005 |
| 560 - Km 24 + 170 -Road Marking Drawings- Sheet 1 of 7 | C46225 |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Road Marking Drawings- Sheet 2 of 7 | C46226 |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Road Marking Drawings- Sheet 3 of 7 | C46227 |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Road Marking Drawings- Sheet 4 of | C46228 |
| 7 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Road Marking Drawings- Sheet 5 of 7 | C46229 |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Road Marking Drawings- Sheet 6 of | C46230 |
| 7 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Road Marking Drawings- Sheet 7 of 7 | C46231 |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Culvert Cross Section- Sheet 1 of | C46232 |
| 15 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Culvert Cross Section- Sheet 2 of 15 | C46233 |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Culvert Cross Section- Sheet 3 of | C46237 |
| 15 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Culvert Cross Section- Sheet 4 of | C46238 |
| 15 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | 0.40000 |
| 560 - Km 24 + 170 -Culvert Cross Section- Sheet 5 of 15 | C46239 |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Culvert Cross Section- Sheet 6 of | C46240 |
| 15 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | C46241 |
| 560 - Km 24 + 170 - Culvert Cross Section- Sheet 7 of | |

| DESCRIPTION | DRAWING NO. |
|---|-------------|
| 15 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Culvert Cross Section- Sheet 8 of | C46242 |
| 15 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Culvert Cross Section- Sheet 9 of | C46243 |
| 15 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Culvert Cross Section- Sheet 10 of | C46244 |
| 15 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Culvert Cross Section- Sheet 11 of | C46245 |
| 15 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Culvert Cross Section- Sheet 12 of | C46246 |
| 15 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Culvert Cross Section- Sheet 13 of | C46247 |
| 15 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Culvert Cross Section- Sheet 14 of | C46248 |
| 15 | |
| Upgrade Of A Portion Of Main Road 8-3 From Km 17 + | |
| 560 - Km 24 + 170 -Culvert Cross Section- Sheet 15 of | C46249 |
| 15 | |

3. PROCUREMENT

The contractor shall procure goods and services under provisional sums and prime cost sums according to the Employer's standards.

4. CONSTRUCTION

4.1 Applicable SANS 2001 standards for construction work

All construction work must conform with the relevant SABS or SANS specifications referred to in the 'Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020', or in Section C3.2 Project Specifications, Part B: Amendments to the Standard Specifications, of this document.

4.2 Applicable national and international standards

All construction work must be undertaken in accordance with the 'Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020 and as amended in Section C3.2 Project Specifications, Part B: Amendments to the Standard Specifications, of this document.

4.3 Particular / generic specifications

As well as the 'Amendments to the Standard Specifications' contained in Part B of Section C3.2 Project Specifications, of this document, the following Particular Specifications as contained in Section C3.3, are applicable to this Contract:

Part C: Environmental Management Specification

Part D: OHSA 1993 Health and Safety Specification

Part E: Expanded Public Works Programme

Part F: Small Contractor Development

The 'General Conditions of Contract for Construction Works, Third Edition (2015)', published by the South African Institution of Civil Engineering which is applicable to this Contract.

4.4 Certification by recognized bodies

No certification of items included in the Works is required.

4.5 Plant and materials provided by the Employer

No plant and materials are to be provided by the Employer.

4.6 Services and facilities provided by the Employer

The Employer's Agent's site office and laboratory facilities will be paid for in terms of the Contract. No other services or facilities are to be provided by the Employer.

5. MANAGEMENT

5.1 Applicable SANS 1921 standards

The following parts of SANS 1921 and associated specification data are applicable:

5.1.1 SANS 1921-1 Part 1: General engineering and construction works

| | Specification data associated with SANS 1921-1 | | |
|---------------|--|--|--|
| Clause No. | Essential data | | |
| 4.1.7 | There are no requirements for drawings, information and calculations for which the Contractor is responsible. | | |
| 4.2.1 | The responsibility strategy assigned to the Contractor for the works is 'A'. | | |
| 4.3.1 | The programme must conform to clause A1.2.7.1 (Scheme 2) 'Programme of Work' of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020 and clause 5.6 'Programme' of the 'General Conditions of Contract 2015'. | | |
| 4.3.3 | The Contractor must give 24 hours' notice for inspection of work that is to be covered up. | | |
| 4.7.3 | Where applicable, the Contractor is afforded the opportunity of pricing an item to cover costs of unavoidable over-break. | | |
| 4.12.2 | The samples of materials, workmanship and finishes that the Contractor is to provide and deliver to the Employer/Employer's Agent are to be as described in clause A1.2.8 'Workmanship and Quality Control' of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020 and clause 7 'Quality and Related Matters' of the 'General Conditions of Contract 2015'. | | |
| 4.12.2 | The fabrication drawings that the Contractor is to provide to the Employer are: none. | | |
| 4.14.5 | The Contractor is to provide latrine and ablution facilities as described in Part C 'Environmental Management Plan' in Section C3.3 Particular Specifications of these Project Specifications. | | |
| 4.14.6 | The requirements for the provision and erection of signboards are as described in clause A1.2.3.10 'Notices, Signs and Advertisements' of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020, and as detailed in the 'Example of Contract Signboard Details' in Section C4: Site Information of these Project Specifications. | | |
| 4.17.1 | The requirements for the termination, diversion or maintenance of existing services are described in clause A1.2.7.3 and Chapter 2 of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020. | | |
| 4.17.3 | Services that are known to exist on the site are described in clause A1.2.7.3 and Chapter 2 of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020. | | |
| 4.17.4 | The requirements for detection apparatus for locating underground services are: none. | | |
| 4.18 | The additional health and safety requirements are described in Part D 'OHSA 1993 Health and Safety Specification' in Section C3.3 Particular Specifications of these Project Specifications. | | |

5.1.1.1 Additional clauses:

(a) Site meetings and procedures

Site meetings shall be convened as described in clause A1.2.3.16 'Monthly Site Meetings' of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020. The Contractor shall keep on site a set of minutes of all site meetings, daily records of resources (people and equipment employed), a site memoranda book, a complete set of contract working drawings and a copy of the procurement document, and shall make these available at all reasonable times to all persons concerned with the contract.

(b) Water and electricity

The Contractor is to provide water and electricity as described in clauses A1.2.3.21 'Water' and A1.4.7.3 'Services' of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020.

| Specification data associated with SANS 1921-6 | | |
|--|--|--|
| Clause No. | o. Essential data | |
| 4.2.1(a) | A qualified service provider is one that is an accredited or provisionally accredited training service provider in the HIV/AIDS field. A list of accredited service providers can be obtained from the Construction SETA (CETA) (tel. 011 265 5900), Health and Welfare SETA (HWSETA) (011 622 6852) or on the Health and Welfare SETA website: www.hwseta.org.za. | |
| 4.2.1(a) | The HIV/AIDS awareness programme is to be repeated at four monthly intervals throughout the duration of the contract. | |

5.1.2 SANS 1921-6 Part 6: HIV/AIDS awareness

5.1.2.1 Additional clauses:

(a) Workshops

The duration of each workshop shall not be less than 2½ hours.

5.2 Recording of weather

The Contractor shall erect a rain gauge and record the rainfall as described in clause A1.2.3.4 of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020. This information together with other details of the prevailing weather conditions shall be recorded in the daily site diary.

5.3 Unauthorised persons

The Contractor shall keep unauthorised persons away from the Works at all times. Under no circumstances may the Contractor's personnel be accommodated on the site.

5.4 Management meetings

Management meetings are to be held weekly at a time convenient to all concerned, to discuss planning and health and safety amongst other things. Attendance by the Construction Manager and the Employer's Agent's Representatives on site is mandatory, and attendance by other interested parties will be by invitation.

5.5 Forms for contract administration

The Employer's Agent's Representative will provide standard forms for 'Site Diary', 'Site Memoranda', 'Requests for Inspection' and any others deemed to be necessary during the contract.

5.6 Electronic payments

Payments of approved payment claims will be made electronically upon submission of the Contractor's banking details.

5.7 Daily records

A site diary is to be compiled jointly by the Construction Manager and the Employer's Agent's Representatives on site and is to be agreed and signed by both parties. The original signed copy is to be retained by the Employer's Agent's Representative.

The Contractor is to keep daily records of people and equipment on site in a format to be agreed by the Employer's Agent's Representative, and is to provide copies to the Employer's Agent's Representative when requested.

5.8 Payment certificates

Details of measurements, proof of payment for items contained in provisional sums and prime cost sums,

proof of ownership of Plant and materials on site and documentation pertaining to contract price adjustment and special materials, are required as substantiation of claims for payment.

5.9 Permits

No security/entrance permits are required by the Contractor's personnel to enter the site.

5.10 Proof of compliance with the law

There are no requirements for the Contractor to verify compliance with any legislation.

5.11 Submission of reports

The contractor shall submit monthly reports in accordance with the specifications in Part E: Expanded Public Works Programme and Part F: Small Contractor Development.

C3.2: PROJECT SPECIFICATIONS

PART B: AMENDMENTS TO THE STANDARD SPECIFICATIONS

PROJECT SPECIFICATIONS RELATING TO THE STANDARD SPECIFICATIONS AND OTHER ADDITIONAL SPECIFICATIONS

In certain clauses in the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020, allowance is made for a choice to be specified in the Project Specifications between alternative materials or methods of construction, and for additional requirements to be specified to suit a particular contract. Details of such alternatives or additional requirements applicable to this Contract are contained in this part of the Project Specifications. It also contains the necessary additional specifications required for this Contract.

The clauses and payment items dealt with in this part of the Project Specifications are numbered 'PS' with a number corresponding to the relevant clause or item number in the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020.

New clauses and payment items not covered by clauses or items in the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020 have been included here and have also been designated with the prefix 'PS'. Such clauses and items have been given a new number following upon the last number used in the particular chapter referred to in the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020.

CHAPTER 1.2 GENERAL REQUIREMENTS AND PROVISIONS

PART A: SPECIFICATION

PSA1.2.3.4 EXTENSION OF TIME FOR DELAYS BY RAINFALL

Add the following to the end of A1.2.3.4(b) Method 2 (Critical path method with consequential delays):

The value of "n" working days expected delay caused by normal rainy weather as referred to in Method (ii) shall be as given in the table below for each respective calendar month of any year:

| Month | Expected delay of "n" working days due to normal rainy weather | Month | Expected delay of "n" working days due to normal rainy weather |
|------------|--|-------------|--|
| January*** | 5 | July | 1 |
| February | 4 | August | 1 |
| March | 4 | September | 2 |
| April | 3 | October | 3 |
| May | 2 | November | 4 |
| June | 1 | December*** | 5 |

*** Includes the whole month of December / January.

PSA1.2.3.11 ORDERING OF DAYWORKS

Replace Clause A1.2.3.11 with the following:

PSA1.2.3.11 DAYWORKS

a. Scope

Rates for daywork shall be entered in the under item C1.2.8.1 in accordance with the following specifications.

b. Daywork Rates

According to Clause 6.5 of the General Conditions of Contract 2015, certain work may be carried out using rates tendered in the daywork schedule. A schedule of personnel, construction equipment and vehicles which may be required to perform work on a daywork basis is included in the Bill of Quantities. The quantities used in the Bill of Quantities are for tender evaluation purposes only and the use or not of these items shall not constitute a variation in terms of Clause 6.3 of the General Conditions of Contract 2015.

No work will be paid for as daywork without the written instruction or approval of the Employer's Agent.

c. Type of Work

The Employer's Agent may order daywork in certain cases where it is necessary to vary or to extend the works due to new or unforeseen circumstances to such an extent that the tendered rates for specific items of work are no longer applicable, or where no suitable combination of tendered rates can be used to pay for such work.

As a general rule, applicable rates for additional work items will be agreed between the Contractor and the Employer's Agent. Daywork will only be used in exceptional circumstances.

d. Materials

Materials for use in works carried out under daywork shall be purchased by the Contractor who shall also arrange for delivery to site, and shall be responsible for any other requirements associated with specific materials. A Provisional Sum has been allowed in C1.2.8 of the Bill of Quantities for daywork materials. The Contractor shall enter a tendered percentage in the Bill of Quantities to cover his handling costs and profit, as per other provisional and prime cost sums in this Contract.

Materials shall be paid for using the method described in C2.1, 'Pricing Assumptions'. No contract price adjustment will be applicable to materials.

The Contractor shall submit proof of ownership for any materials used in daywork with his daywork claim to the Employer's Agent. Further, if specific materials are required for daywork, quotations will be called for as per Clause 6.5.2 of the General Conditions of Contract 2015.

e. Construction Equipment

Where daywork is ordered, the tendered rates for construction equipment in C1.2.8 of the Bill of Quantities shall be used in calculating the payment due for any construction equipment required to execute the daywork. If no rate is included in the Bill of Quantities for a particular item of construction equipment, and where no other rate or combination of rates would provide suitable compensation, then the daywork method of payment described in Clause 6.5.1.3 of the General Conditions of Contract 2015 will be used.

The tendered rates for each item of construction equipment shall include for all operating costs associated with the said item of construction equipment. Such costs are deemed to include fuel, refuelling costs, lubrication and routine servicing / maintenance, breakdowns and spares, all overhead costs, site management costs and administration costs. The tendered rates shall also include the construction equipment operator and the general supervision of the construction equipment while it is engaged in the daywork.

f. Salaries and Wages of Workmen

The salaries and wages of workmen executing daywork shall be paid for using the tendered rates in the Bill of Quantities. The tendered rates shall include for all costs associated with the employment of personnel, including salaries, wages, allowances, workmen's compensation, medical aid and pension contributions, government levies and taxes, training costs and any costs associated with living on the site. The tendered rates shall also include for the transportation of the workmen to the site of the daywork.

All overhead costs, administration costs, site management costs and the Contractor's profit are deemed to be covered by the daywork rates and no additions or mark ups will be made to the tendered rates.

The tendered rates shall also include any hand tools normally associated with the workmen's job description e.g. picks, shovels, hammers, saws and spirit levels. The tendered rate for labourers shall also include for the casual supervision by a gang leader or foreman. Only when specifically called for by the Employer's Agent, will payment be made for the use of a gang leader or foreman supervising on a continuous basis.

g. Measurement and Payment

The following principles shall also apply to the measurement and payment of daywork.

The unit of measurement for construction equipment shall be the number of Vibroclock hours worked and each item of construction equipment shall be fitted with a Vibroclock, the cost of which shall be included in the rates. Excessive non-productive time when the engine is idling will not be paid for. Where there is ambiguity between the flywheel horsepower and mass of the machine, the flywheel horsepower shall govern the measurement category. Where width and mass are specified, mass shall govern the measurement category.

The Contractor's attention is drawn to the requirements of Clauses 6.5.3 and 6.5.4 of the General Conditions of Contract 2015 with regard to the submission of lists and statements of personnel, materials and construction equipment used for daywork.

The payment items under C1.2.8 in the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020 will be applicable.

PSA1.2.3.18 Stakeholder liaison

Add the following to Clause A1.2.3.18:

a. Project Liaison Committee

The process of implementing infrastructure projects will be undertaken by means of structured engagement between those responsible for the delivery of the project and the community.

A Project Liaison Committee (PLC) is a vital means of communication between the parties involved with the project. A PLC may be formed if the project is such that a specific community can be identified.

The PLC comprises representatives of the employer, the engineer and formal structures within the community. The contractor shall make use of these communication channels, and shall appoint from amongst his site personnel a responsible person to participate in the affairs of the PLC, and this representative shall also attend the monthly PLC meetings when so requested.

The PLC shall meet at least once every month until such time as it is of the opinion that it could fulfil its tasks by meeting less frequently.

The PLC deals with local labour on the project, and is tasked with:

- assisting with community liaison and the resolution of community disputes;
- devising fair and transparent procedures that will assist the contractor in the engagement of labour;
- advising on and monitoring labour issues; and
- assisting in the resolution of labour disputes.

All labour recruitment, employment and associated risks shall remain the sole responsibility of the contractor.

A new pay item is included in Chapter 1.2 of the schedule of quantities relating to the payment of the PLC on a provisional sum basis. Payment under this item shall be made only for the period for which the duties of the PLC are required, and not necessarily for the full duration of the contract.

b. Community Liaison Officer (CLO)

The contractor, after consultation with the Project Liaison Committee (PLC), shall appoint a competent local person as a Community Liaison Officer (CLO). The contractor shall appoint the CLO as part of his site personnel, and shall direct all his liaison efforts with the local community through the appointed CLO.

The period of employment and the remuneration of the CLO shall be determined jointly by the contractor, the engineer and the employer.

The CLO shall:

- i. represent the community and assist the contractor, the engineer and the employer with communication between them and the community;
- ii. work an 8-hour day with a total of 40 hours worked per week, and shall be present on site each day except when performing off-site community liaison activities;

- iii. communicate daily with the contractor on labour related issues such as numbers and skill;
- iv. assist in the identification and screening of local labourers from the community in accordance with the contractor's requirements;
- v. inform local labour of their conditions of employment, including their period of employment;
- vi. attend disciplinary proceedings involving local labour, and ensure that hearings are fair and reasonable;
- vii. attend all meetings at which the community and/or local labour are present or are required to be represented;
- viii. attend monthly site meetings to report on community and local labour matters;
- ix. keep a daily written record of interviews and community liaison;
- x. submit monthly returns regarding community liaison; and
- xi. carry out all such other duties as agreed upon between all parties concerned.

A new pay item is included in Chapter 1.2 of the schedule of quantities relating to the payment of the CLO on a provisional sum basis. Payment under this item shall be made only for the period for which the duties of the CLO are required, and not necessarily for the full duration of the contract.

Add the following new Clause A1.2.3.24:

PSA1.2.3.24 Compliance with the Road Traffic Act

When a service necessitates vehicles or plant travelling or working on a public road, the following shall apply:

- The vehicles and plant shall be licensed in terms of the National Road Traffic Act 1996 (Act No. 93 of 1996) as amended.
- Every driver and operator of a vehicle or an item of plant shall be in possession of a valid permit in respect of the class of vehicle or item of plant he / she is driving or operating.

The Contractor shall provide, erect and maintain sufficient road signs, barricades, fencing and guarding as may be necessary or required by the Employer's Agent or by any act, regulation or statutory authority in order to minimise the danger and inconvenience caused to vehicle and pedestrian traffic. The Contractor by accepting this contract shall be deemed to have indemnified the Employer and the Employer's Agent against any claims, damages and / or costs that may arise in this regard.

Add the following new payment item.

PSC1.2 MEASUREMENT AND PAYMENT

ltem

Unit

PSC1.2.10 Community Participation

(a) Cost for community Participation (PLC and CLO)..... Prime Cost Sum

(b) Handling costs and profit in respect of sub-item PSC1.2.10(a) abovepercentage (%)

Expenditure under this item shall be made in accordance with clause 6.6 of the General Conditions of Contract 2015.

The tendered percentage is a percentage of the amount of expenditure approved by the Employer's Agent under sub-item PSC1.2.10(a), and shall include full compensation for the handling costs of the Contractor and the profit in connection with the provision of a Community Liaison Officer."

C3.3: PARTICULAR SPECIFICATIONS

In addition to the Standard Specifications and the Project Specifications, the following Particular Specifications shall apply to this contract and are bound in hereafter:

| PART C: | ENVIRONMENTAL MANAGEMENT SPECIFICATION | C90 |
|---------|---|------|
| PART D: | OHSA 1993 HEALTH AND SAFETY SPECIFICATION | C96 |
| PART E: | EXPANDED PUBLIC WORKS PROGRAMME | C126 |
| PART F: | SMALL CONTRACTOR DEVELOPMENT | C161 |

3.3 PARTICULAR SPECIFICATIONS

PART C: ENVIRONMENTAL MANAGEMENT SPECIFICATION

PART C: ENVIRONMENTAL MANAGEMENT SPECIFICATION

C1. SCOPE

The Employer recognises environmental management as a key component of road infrastructure development and as part of its environmental policy has developed this environmental management specification as a tool for continual improvement in environmental performance.

This environmental management specification prescribes the methods by which proper environmental controls are to be implemented by the Contractor. The duration over which the Contractor's controls shall be in place cover the construction period of the project as well as the limited time after contract completion defined by the General Conditions of Contract 2015 as the Defects Notification Period (maintenance period).

C2. ENVIRONMENTAL MANAGEMENT PLAN

In order to ensure that the construction work is carried out in an environmentally sensitive manner, strict compliance with the Environmental Management Plan (EMP) guidelines is required. The purpose of the EMP is to:

- Encourage good management practices through planning and commitment to environmental issues,
- Provide rational and practical environmental guidelines to:
 - (i) Minimise disturbance of the natural environment,
 - (ii) Prevent pollution of land, air and water,
 - (iii) Prevent soil erosion and facilitate re-vegetation.
- Adopt the best practicable means available to prevent or minimise adverse environmental impact,
- Develop waste management practices based on prevention, minimisation, recycling, treatment or disposal of wastes,
- Train employees and contractors with regard to environmental obligations.

C3. ADMINISTRATION OF ENVIRONMENTAL OBLIGATIONS

The Contractor is responsible for the implementation of this EMP to ensure sound environmental management during the construction phase of a project.

The Contractor shall receive and implement any instruction issued by the Employer's Agent relating to compliance with the EMP including the removal of personnel or equipment.

Compliance with the provisions contained herein or any condition imposed by the environmental approvals, shall become the responsibility of the Contractor through an approved Environmental Officer (EO). The Contractor shall nominate a person from among his site personnel to fulfil this function and submit to the Employer's Agent for his approval the curriculum vitae of the proposed EO. This request for approval shall be given, in writing, at least fourteen days before the commencement of any construction activity clearly setting out reasons for the nomination, and with sufficient detail to enable the Employer's Agent to make a decision.

Once a nominated representative of the Contractor has been approved as the EO, the EO shall be the responsible person for ensuring that the provisions of this EMP are complied with for the duration of the contract. The EO shall submit monthly written reports of compliance with the EMP to the Employer's Agent.

In addition to the compliance duties relating to this EMP, the EO shall also provide full cooperation whenever the Contractor is subjected to regular environmental audits.

C4. TRAINING AND INDUCTION OF EMPLOYEES

The Contractor has a responsibility to ensure that all those people involved in the project are aware of and familiar with the environmental requirements for the project (this includes subcontractors and local labour). The EMP shall be part of the terms of reference for all contractors, subcontractors and suppliers.

C5. COMPLAINTS REGISTER AND ENVIRONMENTAL INCIDENT BOOK

Any complaints received by the project team from the public will be recorded. The complaint should be brought to the attention of the Construction Manager, who will respond.

The following information must be recorded:

- Time, date and nature of the complaint,
- Type of communication (telephone, letter or email),
- Name, contact address and telephone number of the complainant,
- Response and investigation undertaken, and
- Actions taken and by whom.

All complaints received will be investigated and a response given to the complainant within 14 days.

All environmental incidents occurring on the site will be recorded. The following information will be provided:

- Time, date, location and nature of the incident, and
- Actions taken and by whom.

C6. SITE CLEANLINESS AND NEATNESS

- Location of a construction camp is to be approved by the Employer's Agent and is to be restored to its previous condition after completion of construction.
- The construction camp should preferably be fenced with a 1,8m Bonnox fence or similar approved.
- All materials, equipment, plant and vehicles must be stored within the construction camp.
- A dedicated area must be made available for construction staff to change and store their personal belongings.

C7. ACCESS

- Access to existing roads, schools, buildings, shops and residential properties must not be impeded during construction.
- Access roads utilised by the Contractor must be maintained in good condition.

C8. BORROW PITS

- Mining authorisations (permits) for borrow pits must be obtained from the Department of Mineral Resources (DMR) in consultation with the Department of Water and Sanitation (DWS).
- Spoil dumps resulting from borrow pits must not interfere with any natural surface drainage.
- Borrow pits must be rehabilitated after use in accordance with the requirements of DMR and DWS.

C9. DUST CONTROL / AIR QUALITY

- Dust suppression measures must be implemented during construction by ensuring that all surfaces prone to dust generation are kept damp (e.g. use of water tanker).
- Ensure that vehicles and equipment are in good working condition and that emissions are not excessive.
- Special care must be taken in areas where the route passes close to schools and residential areas.
- The speed of construction vehicles must be reduced.

C10. FAUNA

 Contractors' and subcontractors' staff and workers may not chase, catch or kill animals encountered during construction.

C11. FIRE PREVENTION AND CONTROL

- Smoking is prohibited in the vicinity of flammable substances.
- The Contractor must ensure that fire-fighting equipment is available on site, particularly where flammable substances are being stored or used, and that construction staff are aware of where it is kept and how it is operated.
- Fires started for comfort (warmth) are prohibited, due to the risk of veld fires and risk to adjacent property owners' lands.

C12. GRAVE SITES

• Grave sites in close proximity to the road must not be disturbed during construction.

C13. MATERIALS HANDLING AND SPILLS MANAGEMENT

- Any hazardous materials to be used during construction (e.g. lime, fuel and paint) are to be stored in a designated area at the campsite.
- The storage containers/facilities (including any diesel or petrol tanks) must be placed on an impermeable surface and surrounded by a bund wall, in order to ensure that accidental spillage does not pollute the environment.
- Workers must at all times be made aware of the health and safety risks associated with any hazardous substances used (e.g. smoking near fuel tanks), and must be provided with appropriate protective clothing/equipment in case of spillages or accidents.
- Ensure all staff and contractors undergo relevant training in the maintenance of equipment to prevent the accidental discharge or spill of fuel, oil, lubricants and other chemicals.
- Any spill of potentially hazardous materials must be cleaned up immediately (potentially hazardous materials on site include paint, oil, grease, fuel and turpentine).
- The area of contaminated soil or spill must be deposited into the hazardous waste container(s).
- The Contractor should keep Peat Sorb or a similar absorbent on site to clean up any spills. The absorbent must be stored in a designated area and be available for inspection.
- All spills are to be recorded in the environmental incident book.

C14. NOISE

- Noise generating activities must be restricted to between 07:00 and 17:00 Monday to Friday, unless otherwise approved by the appropriate competent person in consultation with adjacent landowners/affected persons.
- All equipment, vehicles and machinery must be in good working condition and be equipped with sound mufflers if necessary.
- Construction staff must be trained and made aware of not creating unnecessary noise such as hooting and shouting.

C15. POLLUTION CONTROL

- Soil and water pollution through usage of fuel, oil, paint, bitumen or other hazardous substances must be avoided.
- All construction vehicles are to be maintained in good working order so as to prevent soil or water pollution from oil, fuel or other leaks, and to reduce noise pollution.

C16. RIVERS AND STREAMS

- During construction of bridge structures, there must be no obstruction of the water flow of rivers and streams.
- Excavated material must not be stockpiled on or near riverbanks, in order to prevent sedimentation occurring.
- Erosion control measures must be employed both during and after construction.
- No impediments to natural surface water flow, other than approved erosion control measures, must occur.

C17. SAFETY

- Safety measures, such as detour signs, must be implemented during construction to ensure the safety of workers, pedestrians and drivers/passengers in vehicles in the vicinity of construction work.
- Special care must be taken in the vicinity of schools to ensure the safety of children wishing to cross the road under construction.
- The relevant signage (e.g. speed control signs) must be erected alongside the road during the operation phase in order to control traffic.
- Accommodation must be made for pedestrian pathways alongside the road during the construction and operation phases.

C18. SOIL MANAGEMENT

- Storm water drainage pipes must be installed alongside the road in all areas susceptible to soil erosion.
- Erosion should be minimised by the construction of meadow drains and the planting of indigenous vegetation on the side slopes and drains to reduce flow velocity of storm water.
- Spoil from cuts may be used in existing erosion gullies.
- Stone pitching and gabions should be constructed at pipe culvert outlets.
- Accidental spills of contaminants onto the ground e.g. oil, concrete, fuel and chemicals should be removed together with the contaminated soil.
- If necessary, an absorbent such as Peat Sorb should be used to aid in cleaning up the spill. The contaminated soil should be disposed of in an appropriate container, depending on its classification.
- Servicing and refuelling of vehicles must only be carried out at the construction camp.

C19. WORKER CONDUCT

Code of Conduct for Construction Personnel:

- Do not leave the construction site untidy and strewn with rubbish which will attract animal pests.
- Do not set fires.
- Do not cause any unnecessary, disturbing noise at the construction camp/site or at any designated worker collection/drop off points.
- Do not drive a construction-related vehicle under the influence of alcohol.
- Do not exceed the national speed limits on public roads or exceed the recommended speed limits on the site.
- Do not drive a vehicle which is generating excessive noise or gaseous pollution (noisy vehicles must be reported and repaired as soon as possible).
- Do not litter along the roadsides, including both the public and private roads.
- Do not pollute any water bodies (whether flowing or not).
- No member of the construction team is allowed to enter the areas outside the construction site.

C20. TRAFFIC DISTURBANCES AND DIVERSIONS

- Any traffic diversions must be undertaken with the approval of all relevant authorities and in accordance with all relevant legislation.
- Wherever possible, traffic diversion must only take place on existing disturbed areas and remain within the existing road reserve.
- Traffic diversion routes must be rehabilitated after use.

C21. VEGETATION

- Only vegetation falling directly on the route must be removed where necessary.
- Alien vegetation within the road reserve must be eradicated, and management measures must be implemented for future control of these species.
- Vegetation that has been removed from large areas (e.g. on traffic diversion routes) during construction must be replaced with indigenous vegetation after construction has been completed.

C22. WASTE MANAGEMENT

- All general, non-hazardous waste must be placed in a skip container and disposed of at a registered waste disposal site.
- The Contractor is to ensure that the portable toilet facilities at the campsite are properly maintained and in working order.
- No disposal, or leakage, of sewage must occur on or near the site.
- All hazardous waste (e.g. oil, paint, empty lime bags, and contaminated wash water) must be stored in leakproof containers and disposed of at a registered hazardous waste disposal site.
- The contents of waste storage containers must, under no circumstances, be emptied to the surrounding area. In general, littering, discarding or burying of any materials is not allowed on site or along the route.
- Adequate waste receptacles must be available at strategic points around the construction camp and site for all domestic refuse and to minimise the occurrence of littering.
- Concrete rubble must be collected and disposed of as directed by the Employer's Agent.
- Each working area must be cleared of litter and building waste (e.g. rubble, wood and concrete packets) on completion of the day's work.
- Any spill around the container(s) should be treated as per clause C13 and C18.

C23. MEASUREMENT AND PAYMENT

The contractor shall make provision in the various rates and prices for all costs related to the environmental management specification and measures required in terms of legislation. Provision is made in item B13.02 of the Bill of Quantities for the contractor's general obligations, risks and liabilities in accordance with the environmental management specification.

C3.3 PARTICULAR SPECIFICATIONS

PART D: OHSA 1993 HEALTH AND SAFETY SPECIFICATION

PART D: OHSA 1993 HEALTH AND SAFETY SPECIFICATION

D1. SCOPE

This part covers the health and safety requirements to be met by the Contractor to ensure a continued safe and healthy working environment for all employees, subcontractors, the Employer, the Employer's Agent, inspectors and all other persons entering the site of works.

This specification shall be read in conjunction with the Occupational Health and Safety Act, 1993 (Act No 85 of 1993 and amendment Act No 181 of 1993) and the corresponding Construction Regulations 2014, and all other safety codes and specifications referred to in the said Act and Construction Regulations.

In terms of the OHSA Agreement in Section C1.4 of the Contract document, the status of the Contractor as mandatary to the Employer (client) is that of an employer in his own right, responsible for compliance with all provisions of OHSA 1993 and the Construction Regulations 2014.

This specification and the Contractor's own Health and Safety Plan as well as the Construction Regulations 2014, shall be displayed on site or made available for inspection by inspectors, the Employer, the Employer's Agent, the Construction Health and Safety Agent, subcontractors, employees, representatives of trade unions and any other persons entering the site of works.

D2. DEFINITIONS

For the purpose of this contract the following shall apply:

D2.1 "**Construction Health and Safety Agent**" (CHSA) means any competent person who acts as a representative for the Employer in managing health and safety on a construction project for the Employer and who has satisfied the registration criteria of the SACPCMP to perform the required functions.

D2.2 **"Contractor**" where used in the contract documents and in this specification, means the Contractor as defined in the General Conditions of Contract 2015, and it shall have the exact same meaning as **"principal contractor**" as defined in the Construction Regulations 2014. **"Contractor**" and **"principal contractor**" are therefore interchangeable and shall be read in the context of the relevant document.

In this specification the terms "principal contractor" and "contractor" are replaced with "Contractor" and "subcontractor" respectively.

For the purpose of this contract the Contractor will, in terms of OHSA 1993, be the mandatary, without derogating from his status as an employer in his own right.

D2.3 "**Employer**" where used in the contract documents and in this specification, means the Employer as defined in the General Conditions of Contract 2015 and it shall have the exact same meaning as "**client**" as defined in the Construction Regulations 2014. "**Employer**" and "**client**" are therefore interchangeable and shall be read in the context of the relevant document.

D2.4 **"Employer's Agent**" where used in this specification, means the Employer's Agent as defined in the General Conditions of Contract 2015.

D3. EMPLOYER'S BASELINE RISK ASSESSMENT

D3.1 Risk information

The information presented in this clause is based on the Employer's baseline risk assessment prepared specifically for this contract.

This information describes the type of work required in terms of this contract that will be accompanied by dangers, hazards and risks which the Contractor shall be required to identify, analyse, manage, monitor and review in terms of the Health and Safety Plan and risk assessments.

This information is neither prescriptive nor exhaustive, and is provided as a guideline to Tenderers in

preparing their tender submissions, and to the successful Contractor as a basis for the preparation of the site-specific risk assessments to be performed by the Contractor in terms of Construction Regulation 9.

Tenderers shall make their own assessment of the dangers, hazards and risks that can be expected during the course of this contract, which may include dangers, hazards and risks not identified in the baseline risk assessment, including those that may arise from specific methods of construction employed by the Contractor, and shall make due allowance in their tendered rates and prices for all costs related to complying with the provisions of the Act and Construction Regulations.

This information is given in good faith for the guidance of Tenderers, and no additional payment shall be made as a result of any inaccuracies, discrepancies or omissions contained therein.

D3.2 Baseline risk assessment

The following is a list of risks identified which forms the Baseline Risk Assessment for the project prepared by the Employer in terms of Construction Regulation 5(1)(a).

| | Date: | 11/2020 |
|--|---------------------------|------------|
| S | Revision Number: | CSS/ 001 |
| Construction Safety Services Reg. No. 2004/094601/23 | Baseline Risk / | Assessment |
| | Compiled by: N Gilroy, C | HSM |
| Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 | Approved by: W. Gilroy, P | r. CHSA |
| E.mail : gilroy@internext.co.za | (willing | 1 |

Section 8: Baseline Risk Assessments

1. Project Description

| Project: | Upgrading of Main Road P8/3, From Gravel to Blacktop between KM 17.560 and KM 24.221 ZNT ZNB00124/00000/00/HOD/INF/20/T |
|---|--|
| Client: | Province of Kwazulu-Natal Department of Transport |
| Principal Agent/Engineers: Construction Health and Safety Agent: | Ilifa Africa Engineers (PTY) Ltd Construction Safety Services |

2. Introduction

This site specific baseline risk assessments have been compiled in accordance to the Construction Regulations 5(1)(a). It is in no means exhaustive and can be revised as the project progress.

The Risk Assessments and Requirements listed must be used by the Principal Contractor to compile site specific Risk Assessments and to identify Hazards that will be prevalent on the Construction Site.

Compliance with the requirements of legislation remains the responsibility and accountability of the Principal Contractor.

| | Date: | 11/2020 |
|--|---------------------------|------------|
| S | Revision Number: | CSS/ 001 |
| Construction Safety Services Reg. No. 2004/094601/23 | Baseline Risk A | Assessment |
| Construction Health and Safety Consultants | Compiled by: N Gilroy, C | |
| PO Box 402, Harrismith, 9880 | Approved by: W. Gilroy, P | r. CHSA |
| E.mail : gilroy@internext.co.za | willing | r |

3. Index

| Reference | Construction Health and Safety | Description |
|-----------|---|--|
| No. | Risk Rating Formula | Formula for rating risks and hazards |
| 1 | Procurement Management | The non-compliance of establishing, implementing and managing procurement strategies and procedures, including the preparation of necessary documentation for effective and timeous construction health and safety management of the project |
| 2 | Cost Management | The non-compliance of not making adequate and sufficient provision for health and safety measures regarding incident/injury prevention. |
| 3 | Hazard Identification Management | The non-compliance to identify, evaluate and eliminate, mitigate and/or control Hazard identified for construction work. |
| 4 | Risk Management | The non-compliance to identify, evaluate and eliminate, mitigate and/or control Risks identified for construction work. |
| 5 | Accident and Incident Investigation Management | The non-compliance of implementing a system to investigate and establish the root cause of incidents and/or accidents |
| 6 | Legislation and Regulations Management | The non-compliance of legislative and regulative requirements for construction work. |
| 7 | Health, Hygiene and Environmental Management | The non-compliance of Health, safety, hygiene and environmental legislative requirements for construction work. |
| 8 | Communication Management | The non-compliance of implementing a communication system between the Principal Contractor and his/her employees, site visitors, appointed contractors, the client, the client's representative or an inspector. |
| 9 | Emergency Preparedness Management | The non-compliance of emergency preparedness on the construction site |

•

| | Date: | 11/2020 | | | |
|--|--|----------|--|--|--|
| S | Revision Number: | CSS/ 001 | | | |
| Construction Safety Services Reg. No. 2004/094601/23 Construction Health and Safety Consultants | Baseline Risk Assessment Compiled by: N Gilroy, CHSM Approved by: W. Gilroy,-,Pr. CHSA | | | | |
| PO Box 402, Harrismith, 9880 E.mail : <u>gilroy@internext.co.za</u> | Cwiln | S | | | |

4. Risk Rating Process

All hazards have been identified prior to commencement of work activities and the associated risks have been assessed by considering the severity, probability and exposure of a potential incident. Categorising the risk into: a very low, low, medium, high or very high risk.

Purpose

Low

When the level of risk is exposed, the appropriate mitigation measures can be implemented and safe working procedures can be developed. Employees involved can then be informed of the associated risks and be instructed on their roles and responsibilities to be able to execute the task in a safe manner.

| 1 | Severity | Proba | bility/Frequency | | Exposure | | |
|------------------|--|----------------|--|-----------------|--|--|--|
| (5) Catastrophic | Multiple fatalities Total Damage to tools, equipment, plant and/or surrounding structures | (5) Frequent | Incident can occur daily | (5) Extensive | 80% - 100% of work force Total Damage to tools, equipment, plant and/or surrounding structures | | |
| (4) Critical | Fatality or number of disabling injuries Major Damage to tools, equipment, plan and/or surrounding structures | (4) Regular | Incident can occur weekly | (4) Widespread | 60% - 80% of work force Serious Damage to tools, equipment, plant and/or surrounding structures. | | |
| (3) Serious | Permanent disability or loss of a limb Substantial Damage to tools, equipment, plant and/or surrounding structures | (3) Occasional | Incident can occur monthly | (3) Significant | 40% - 60% of work force Damage to tools, equipment, plant and/or surrounding structures | | |
| (2) Marginal | Hospitalised for less than 14 days with no disability Medium Damage tools, equipment and/or plant | (2) Uncommon | Incident can occur within six months | (2) Restricted | 20% - 40% of work force Damage to tools, equipment and/or plant | | |
| (1) Negligible | First aid on site is sufficient Minor Damage to tools and/or equipment | (1) Rare | Incident occur very rarely | (1) Negligible | 1% - 20% of work force No Damage to tools and/or equipment | | |
| | (S X P) E = Risk Rating | | Medium | | 16 - 30 | | |
| Very Low | 1- | 6 | High | | 31-60 | | |
| Low | | | | | | | |

Very High

8 - 15

61 - 125

| | | Date: | 11/2020 | | | |
|---------------------|--|--|------------|--|--|--|
| | S | Revision Number: | CSS/001 | | | |
| | Construction Safety Services Reg. No. 2004/094601/23 | Baseline Risk | Assessment | | | |
| | Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 E.mail : <u>gilroy@internext.co.za</u> | Compiled by: N Gilroy, CHSM Approved by: W. Gilroy,- Pr. CHSA | | | | |
| 5. Risk Assessments | | Gel | | | | |

5. Risk Assessments

| Ref. no. | Hazard | Risk | | Calc | ulatio | 'n | | Risk Rating | Compliance Reference | |
|-------------|--|----------|--|------|--------|----|-----------|---------------------|--|--|
| 1 | Construction Health and Safety | 1. Healt | th and Safety Legal Framework: | S | IP | E | T | | | |
| | Procurement Management: | a) | Compile a Site Specific Health and Safety Plan | 5 | 4 | 5 | T 100 | Manutilah | 00 7/41/ 1 | |
| | The non-compliance of establishing, implementing and | b) | Registration of the Project with the Department of Labour | 2 | 3 | 4 | 100 24 | Very High Medium | CR 7(1)(a) CR 4(1) | |
| | managing procurement strategies and procedures, including the | c) | Letter of Good Standing with the Compensation Fund or a licensed compensation insurer | 3 | 5 | 5 | 75 | Very High | CR 5(1)(j) | |
| | preparation of necessary | d) | Open and keep on site a Health and Safety File | 4 | 5 | 5 | 100 | Very High | CR 7(1)(b) | |
| | documentation for effective and timeous construction health and | e) | On appointing any other contractor ensure complies with the provision of the Act | 5 | 5 | 5 | 125 | Very High | CR 7 (1)(c) | |
| | safety management of the | 2. Perso | onnel – Principal Contractor | S | P | E | T | Risk Rating | Compliance Reference | |
| | project | a) | Ensure appointed personnel have the necessary competency | 5 | 5 | 5 | 125 | Very High | CR 5(1)(h) | |
| | | b) | Proof available in the Health and Safety File for verification | 4 | 4 | 4 | 64 | Very High | CR7(1)(b) | |
| | | c) | All employees in possession of a valid medical fitness certificate | 4 | 3 | 5 | 60 | High | CR 7(1)(g); CR 17(12)(a); CF 23(1)(d)(ii) | |
| | | d) | Make available first aid and emergency equipment on the construction site | 5 | 5 | 5 | 125 | Very High | GSR 3 (1), (2), (3) | |
| | | e) | Appoint a competent first aider as per GSR | 4 | 4 | 5 | 80 | Very High | GSR 3 (4) | |
| | | f) | Implement emergency evacuation procedures | 4 | 3 | 5 | 60 | High | GSR 3 (6), (7), (8), (9) | |
| | | g) | Provide at or within reasonable access of every construction site the following clean, hygienic and maintained facilities: • Sanitary facilities for each sex; • Changing facilities for each sex; | 1 | 4 | 5 | 20 | Medium | CR 30 | |
| | | | Sheltered eating areas; | | | | | | | |

1

| | | | Da | ate: | | 11/2020 | |
|--|--|---|----|---------|-------------|--|--|
| S | | | Re | evision | Number: | CSS/ 001 | |
| Construction Safety Services Reg. No. 2004/094 Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 E.mail : <u>gilroy@internext.co.za</u> | Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 | | | | | Risk Assessment , CHSM DY:-Pr. CHSA When | |
| Safe Drinking Water. | | - | | 1 | | 1 | |
| h) Provide adequate and sufficient Personal Protection Equipment, free of charge, as identified in the Passessments | ctive 3 Risk | 5 | 5 | 75 | Very High | GSR 2(3), Sec 8 (2)(b) of th Act, Sec 23 of the Act, CR 17(6)(c) | |
| 3. Construction Health and Safety Training | S | P | E | Т | Risk Rating | Compliance Reference | |
| a) The Employer must provide such information, instructions and training as may be necessary to ensure the health and safety of his employees a work place | 4 out the | 4 | 5 | 80 | Very High | Sec 8(2)(e) of the Act CR 17(12)(c) | |
| b) The contractor must ensure that all employees under his/her control are informed, instructed a trained regarding any hazard and the related we procedures and/or control measures before any work commences | ork | 4 | 5 | 80 | Very High | CR 9(3) | |
| Fall Protection: Provide a programme for the training of employees working from a fall risk position | 5 | 5 | 5 | 125 | Very High | CR 10 (2)(c) | |
| 4. Emergency Preparedness | S | P | E | T | Risk Rating | Compliance Reference | |
| a) Implement appropriate measures to avoid the r of fire | isk 4 | 3 | 4 | 48 | High | CR 29 | |
| b) Implement first aid procedures | 4 | 5 | 5 | 100 | Very High | GSR 3 | |
| 5. Construction Health and Safety Signage | S | Р | E | T | Risk Rating | Compliance Reference | |
| a) Supply, install and maintain health and Safety Signage to inform and communicate hazards and risks prevalent on the construction site to employees and persons other than employees, t ensure a reasonable safe and healthy environme at the work place | :0 | 4 | 5 | 60 | High | Sec 8(2)(e) GAR 4 | |
| b) Identify the location of excavations which is accessible to the public or where persons are | 3 | 4 | 4 | 48 | High | CR 13(2)(i) CR13(2)(l) | |

E

| | | | | | | Da | te: | | 11/202 | 20 | |
|-------------|---|------------|---|-----|-------------|----------|------------------|--|--|-------------------|-----|
| | | | S | | | Re | vision | Number: | CSS/ 0 | 01 | |
| | Cor | nstruction | Safety Services Reg. No. 2004/094601, Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 E.mail : <u>gilroy@internext.co.za</u> | /23 | | Co Ap | mpilec provec | Baseline Risk Assessment by: N Gilroy, CHSM by: W. Gilroy, -Rr. CHSA | | | |
| | | | working/carrying out tests. | | | T | 1 | | 1 | | |
| | | c) | Identify the location of first aid equipment | 3 | 3 | 12 | 10 | | / | | |
| | | d) | Prohibit smoking/open flames in flammable storag areas | 8 5 | 5 | 2 | 18 125 | Medium Very High | GSR 3(6) CR 29(1)(c) | | |
| Ref. no. | Hazard | Risk | | Cal | Calculation | | Calculation | | Risk Rating | Compliance Refere | nce |
| 2 | Construction Health and Safety | 1. Dire | ct Cost | S | P | E | T | | | | |
| | Cost Management: The non-compliance of not | a) | Ensure adequate provisions have been made for th cost of health and safety measures | e 5 | 5 | 5 | 125 | Very High | CR 5(1)(g) | | |
| | making adequate and sufficient | b) | Health and safety administration requirements | 3 | 3 | 3 | 27 | Medium | CR 7(1)(a); CR7(1)(b | 1 | |
| | provision for health and safety measures. | c) | Health and safety measures for a safe and healthy working environment | 5 | 5 | 5 | 125 | Very High | Sec 8(1) & (2) of the 85/93 | | |
| | | d) | Health and safety training requirements | 4 | 4 | 4 | 64 | Very High | Sec 8(2)(e) of the C 85/93; CR 5(1)(h); CR 9(3); (2)(c); CR 17(12)(c) | | |
| | | e) | Provide adequate and sufficient Personal Protective Equipment, free of charge, as identified in the Risk Assessments | 5 | 5 | 5 | 125 | Very High | GSR 2(3), Sec 8 (2)(t OHS Act 85/93, Sec the OHS Act 85/93; 17(6)(c) | 23 of | |
| | | f) | Medical fitness for employees and /or operators | 4 | 4 | 5 | 80 | Very High | CR 7(1)(g); CR 17(12 23(1)(d)(ii) | !)(a); CR | |
| | | <u>g)</u> | Health and safety emergency preparedness | 5 | 5 | 5 | 125 | Very High | GSR 3 | | |
| | | h) | Site establishment: storage, facilities and waste management | 3 | 3 | 3 | 27 | Medium | CR 14, 25, 27, 28, 29 GSR 4 | 9, 30; | |
| | | i) | Signage: information, location, instructions etc. | 4 | 4 | 4 | 64 | Very High | Sec 8(2)(e) of the OI 85/93; CR 13(2); GS CR 29(1)(c); GAR 4 | | |
| | | 2. Indire | | S | P | E | T | Risk Rating | Compliance Referen | ice | |
| | | a) | Implementation, maintenance and review process | 5 | 5 | 5 | 125 | Very High | Sec 24 of the OHS A | | |

| | | | | | | Da | te: | | 11/2020 | |
|-------------|---|------------|--|------|--------|----|--------|---|--|--|
| | | | S | | | Re | vision | Number: | CSS/ 001 | |
| | Const | truction ! | Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 E.mail : <u>gilroy@internext.co.za</u> | 3 | | | | Baseline Ri by: N Gilroy by: W. Gilro | | |
| | | | to manage injuries and incidents on the construction site | - | 1 | | | | GAR 8 and 9 COID Act 130/93 | |
| | | b) | Registration and in good standing with the compensation fund or a licensed compensation insurer. | 4 | 3 | 5 | 60 | High | CR 5(1)(j) COID Act 130/93 | |
| D.f | | c) | Public Liability Insurance | 3 | 5 | 5 | 75 | Very High | Contract Requirement | |
| Ref. no. | Hazard | Risk | Section 24 Provide Advertised | Calc | ulatio | n | | Risk Rating | Compliance Reference | |
| 3 | Construction Health and Safety | 1. Elimi | nate, Mitigate and/or Control | S | P | ET | | 125 12 19 10 19 10 10 | | |
| | Hazard Identification Management: The non-compliance to identify, | a) | Ensure the provision and maintenance of systems of work, plant and machinery that are safe and without risk to health | 5 | 5 | 5 | 125 | Very High | Sec 8(2)(a) of the OHS Act 85/93; CR 20(5) | |
| | evaluate and eliminate, mitigate and/or control Hazards identified | b) | Before resorting to personal protective equipment eliminate or mitigate the hazard identified | 5 | 5 | 5 | 125 | Very High | Sec 8(2)(b) of the OHS Act 85/93 | |
| | | c) | Provide adequate and sufficient PPE, free of charge | 5 | 5 | 5 | 125 | Very High | GSR 2(3), Sec 8 (2)(b) of the OHS Act 85/93, Sec 23 of the OHS Act 85/93 | |
| | | d) | Establish what precautionary measures to be taken attached to any work which is performed, any article or substance which is produced, processed, used, handled stored or transported and/or any plant or machinery which is used. | 5 | 5 | 5 | 125 | Very High | Sec 8(2)(c) of the OHS Act 85/93 | |
| | | | Provide adequate and sufficient information signage for the hazards and risk prevalent on the construction site | 4 | 4 | 4 | 64 | Very High | Sec 8(2)(e) of the OHS Act 85/93; CR 13(2); GSR 3(6); CR 29(1)(c); GAR 4 | |
| | | | Ensure that work is performed and machinery or plant is used under the supervision of a person who is trained to understand the hazards associated with the work, plant or machinery | 5 | 5 | 5 | 125 | Very High | Sec 8(2)(i) of the OHS Act 85/93 | |
| | | g) | Make available first aid and emergency equipment | 4 | 4 | 5 | 100 | Very High | GSR 3 (1), (2), (3) | |

T

| | | | | | Da | te: | | 11/2020 | | |
|-------------|---|--|---|---------|-------------|-----|---|--|-----------------------------------|--|
| | | | S | | | Re | vision | Number: | CSS/ 001 | |
| | Cons | truction Safety Services Reg. No. 2004/094601/23 E Compiled b | | | | | | Baseline Risk Assessment ed by: N Gilroy, CHSM ed by: W. Gilroy,- Pr. CHSA W. Gilroy,- Pr. CHSA | | |
| | | | on the construction site | | | - | | - 7 | r, | |
| | | h) | | | - | - | | | CR 29 | |
| | | | Provide adequate and sufficient storage facilities | 3 | 4 | 5 | 60 | High | CR 27, 28, 29 GSR 4 | |
| | | i) | Before commencement of working activities cause hazard identification and risk assessment to be do by a competent person who has been appointed in writing | ne n | 5 | 5 | 125 | Very High | CR 9(1) | |
| | | j) | The hazard identification and risk assessments mu include a monitoring and a review plan | | 3 | 5 | 60 | High | CR 9(1)(d) and (e) | |
| | | k) | Develop and implement safe working procedures mitigate, reduce or control the hazards and risks identified | to 5 | 5 | 5 | 125 | Very High | CR 9(1)(c) | |
| Ref. no. | Hazard | Risk | | Cale | ulatio | n | | Risk Rating | Note/Ref. | |
| 4 | Construction Health and Safety | 1. Appo | intment of Site Personnel (key appointments) | S | P | E | Т | | | |
| | Risk Management: The non-compliance to identify, | a) | Delegation of Duties (CEO) | 5 | 5 | 5 | 125 | Very High | Sec 16(2) of the OHS Act 85/93 | |
| | evaluate and eliminate, mitigate | b) | Health and Safety Representative | 2 | 3 | 5 | 30 | Medium | Sec 17(1) | |
| | and/or control Risks identified | c) | Health and Safety Committee Member | 1 | 2 | 3 | 6 | Low | Sec 19(1) | |
| | | d) | First Aider | 5 | 5 | 5 | 125 | Very High | GSR 3(4) | |
| | | e) | Construction Manager | 5 | 5 | 5 | 125 | Very High | CR 8(1) | |
| | | f) | Assistant Construction Manager | 3 | 3 | 3 | 27 | Medium | CR 8(2) | |
| | | g) | Construction Health and Safety Officer | 5 | 4 | 5 | 100 | Very High | CR 8(5) | |
| | | h) | Construction Supervisor | 4 | 3 | 2 | 24 | Medium | CR 8(7) | |
| | | i) | Assistant Construction Manager | 1 | 2 | 1 | 2 | Very Low | CR 8(8) | |
| | | | Risk Assessor | 4 | 5 | 5 | 100 | Very High | CR 9(1) | |
| | | j) | | | | | Sector Alternation | Bu | | |
| | | j) k) | Fall Protection Planner | 5 | 5 | 5 | 125 | Very High | | |
| | | | Fall Protection Planner Excavation Supervisor | | - | 5 | 125 1 | Very High Very Low | CR 10(1)(a) | |
| | | k) | Fall Protection Planner | 5 | 5 1 4 | | 1 C 1 C 1 C 1 C 1 C 1 C 1 C 1 C 1 C 1 C | Very High Very Low Very High | | |

| | | | | | Da | te: | | 11/2020 |
|--------------|---------------|---|---|---|----|---------|--------------------------|---|
| | | | | | | | | CSS/ 00: |
| | | | | | | | | Baseline Risk Assessment Compiled by: N Gilroy, CHSM Approved by: W. Gilroy, Pr. CHSA |
| | o) St | o) Stacking and Storage Supervisor 3 2 | | | | | Medium | (CD 20(2)() |
| | | e Extinguisher Inspector | 4 | 2 | 3 | 18 8 | | CR 28(1)(a) |
| | | affic Control Officer | 5 | 5 | 5 | 125 | Low | CR 29(1)(h) |
| Section 1200 | 2. General | Requirements and Provisions | S | P | E | T | Very High Risk Rating | SADCRTSM |
| | a) Pr | otection, removal, realignment and replacement services: Traffic Monitoring Stations | 3 | 3 | 3 | 27 | Medium | Note/Ref. |
| | b) Pro | otection, removal, realignment and replacement services: Communication and Municipal services ater, sewage, etc.) | 3 | 3 | 3 | 27 | Medium | |
| | of | otection, removal, realignment and replacement services: Electrical | 5 | 5 | 5 | 125 | Very High | |
| | | nning for underground services | 1 | 1 | 1 | 1 | Very Low | |
| Section 1300 | | ors Site Establishment and General Obligations | S | P | E | Т | Risk Rating | Note/Ref. |
| | | alth and Safety obligations | 4 | 3 | 5 | 60 | High | |
| | | vironmental obligations | 2 | 5 | 5 | 50 | High | |
| S | | cure and maintain 10 seater mini-bus | 2 | 2 | 2 | 8 | Low | |
| Section 1400 | | Offices and Laboratory | S | P | E | Т | Risk Rating | Note/Ref. |
| | | ices, kitchen and laboratory | 5 | 2 | 2 | 20 | Medium | Troxler storage |
| | | oratory: Concrete floor | 2 | 1 | 2 | 4 | Very Low | |
| | wit | ings, installations and equipment: Floodlights h poles | 4 | 3 | 2 | 24 | Medium | |
| | d) Ins | tallation of internet facilities | 2 | 1 | 1 | 2 | Very Low | |
| | e) Ca | ports as specified | 3 | 1 | 2 | 6 | Very Low | |
| | f) Ser | vices: Electricity | 5 | 5 | 3 | 75 | Very High | C.o.C |
| | | vices: Water | 2 | 5 | 3 | 30 | Medium | |
| | h) Ser | vices: Sewage | 2 | 1 | 2 | 4 | Very Low | |
| | | ting other specified by engineer (accommodate sonnel) | 3 | 2 | 2 | 12 | Low | |
| Section 1500 | 5. Traffic Ac | commodation | S | P | E | T | Risk Rating | Note/Ref. |
| | a) Div | ersions: Secondary Road/Farm road | 5 | 4 | 4 | 80 | Very High | noternen |

| | | | | | Da | te: | | 11/2020 | | | |
|--------------|--------------|--|----|--------|---|----------|--------------------|-----------------------------|--|--|--|
| | | 2 | | | Re | visior | Number: | CSS/001 | | | |
| | Construction | Construction Safety Services Reg. No. 2004/094601/23 Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 E.mail : <u>gilroy@internext.co.za</u> | | | Baseline Risk Assessment Compiled by: N Gilroy, CHSM Approved by: W. Gilroy, Pr. CHSA | | | | | | |
| | b) | Diversions: Intersections | 1. | 1.0 | 1. | | | 7 | | | |
| | c) | Temporary: Flag persons | 4 | 3 | 3 | 36 | High | 1 | | | |
| | | Temporary: Portable stop-and-go | 5 | 3 | 3 | 45 | High | | | | |
| | e) | | 5 | 3 | 3 | 45 | High | | | | |
| | f) | Temporary: Moveable barricading : procure and placement | 3 | 5 3 | 2 | 30 18 | Medium Medium | | | | |
| | g) | Temporary: Moveable barricading: dismantling and re-erecting | 3 | 4 | 2 | 24 | Medium | | | | |
| | h) | Temporary: Moveable barricading: dismantling and removal | 3 | 3 | 2 | 18 | Medium | | | | |
| | 0 | Temporary: Implementation and maintenance of two-way communication system | 4 | 4 | 4 | 64 | Very High | | | | |
| | j) | Temporary: Other traffic control measures ordered by the site Engineer | 3 | 2 | 2 | 12 | Low | | | | |
| | k) | Half-width: Signal facilities | 2 | 5 | 2 | 20 | Medium | Establish | | | |
| | I) | Half-width: Operation of signal facilities | 2 | 3 | 2 | 12 | Low | Maintain | | | |
| | | Traffic control vehicle | 4 | 3 | 5 | 60 | High | | | | |
| | | Signage: Variable message signs mounted on trailers and flashing illuminated arrow boards | 2 | 3 | 2 | 12 | Low | Implement maintain and move | | | |
| | | Traffic accommodation for Engineer | 5 | 2 | 2 | 20 | Medium | Inspection | | | |
| ection 1700 | | ing and Grubbing | S | P | E | T | Risk Rating | Note/Ref. | | | |
| | | Clearing and grubbing: Inlets and outlets of hydraulic structures | 3 | 3 | 3 | 27 | Medium | Machine/Hand combination | | | |
| | b) | Cleaning Hydraulic Structures: Pipes | 3 | 3 | 2 | 18 | Medium | | | | |
| | c) | Cleaning Hydraulic Structures: Box culverts | 3 | 3 | 2 | 18 | Medium | | | | |
| | | Removal and temporary stockpile of topsoil | 2 | 2 | 2 | 8 | Low | Environmental | | | |
| Section 1800 | 7. Day V | | S | P | E | Т | Risk Rating | Note/Ref. | | | |
| | | Unskilled labour | 5 | 5 | 5 | 125 | Very High | | | | |
| | | Semi-skilled labour | 4 | 4 | 3 | 48 | High | | | | |
| | c) | Skilled labour | 3 | 3 | 2 | 18 | Medium | | | | |

| | | | | | - | nte: | | 11/2020 |
|--------------|--------------|---|----|---|----|----------|--|---------------------|
| | | S | | | Re | evision | Number: | CSS/ 001 |
| | Construction | Safety Services Reg. No. 2004/094601/ Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 E.mail : <u>gilroy@internext.co.za</u> | 23 | | | | Baseline R d by: N Gilroy d by: W. Gilro | Risk Assessment |
| | (b | Supervisor | 12 | | 1. | | | 1 |
| | e) | Foreman | 3 | 3 | 3 | 27 | Medium | |
| | f) | Equipment: Compressor | 5 | 3 | 3 | 45 | Very High | |
| | g) | Equipment: Water spray truck | 4 | 3 | 3 | 36 | High | |
| | h) | Equipment: Tipper truck, 6.0m ³ | 3 | 2 | 2 | 12 | Low | |
| | 1) | Equipment: Pedestrian roller | 3 | 3 | 3 | 36 | High | |
| | i) | Equipment: Pheumatic-tyred roller | | 3 | 2 | 18 | Medium | |
| | k) | | 3 | 2 | 2 | 12 | Low | |
| | . 1) | Equipment: Self-propelled grader | 4 | 2 | 2 | 12 | Low | |
| | (m) | | 4 | 4 | 3 | 48 | High | |
| | n) | Equipment: Tractor-loader-backhoe, | 4 | 4 | 4 | 64 | Very High | |
| | 0) | Equipment: Bulldozer with ripper | 3 | 2 | 1 | 64 | Very High | - |
| | | Equipment: Excavator | 3 | 3 | - | 6 | Very Low | |
| | | | 3 | 2 | 2 | 18 12 | Medium | |
| | r) | Equipment: Other | 4 | 4 | 4 | - | Low | MSDS |
| | s) | Materials: Procure, stack and store | 3 | 3 | 3 | 64 | Very High | To be specified/fin |
| | t) | Transport vehicle: LDV | 5 | 5 | 5 | 27 | Medium | |
| | u) | Transport vehicle: Flatbed truck | 4 | 5 | 5 | 125 | Very High | |
| Section 2100 | 8. Drain | | S | P | E | 100 T | Very High | a) |
| | a) | Excavation: Open drains, soft material 0.0m up to 1.5m | 1 | 4 | 2 | 8 | Risk Rating | Note/Ref. |
| | b) | Excavation: Open drains, hard material | 2 | 5 | 2 | 20 | Medium | |
| | | Existing open drains: clearing and shaping | 1 | 5 | 2 | 10 | Low | |
| | d) | Existing open drains: Spoil material, including haul | 2 | 4 | 2 | 16 | Medium | |
| | e) | Excavation: Subsoil drainage system, soft material 0.0m up to 3m | 4 | 5 | 2 | 40 | Very High | |
| 1 | | Excavation: Subsoil, hard material | 5 | 3 | 2 | 30 | High | |
| | | Overhaul material | 5 | 2 | 2 | 20 | Medium | |
| | h) | Procure: crushed stone/natural aggregate | 2 | 2 | 2 | 8 | Low | Commental |
| | i) | Clearing and shaping existing open drains | 3 | 2 | 2 | 12 | Low | Commercial source |

| | | | | Da | ite: | | 11/2020 | |
|-------------|--|--|---|----|-------|-------------|-----------------------------|--|
| | S | | | Re | visio | n Number: | CSS/001 | |
| | Construction Safety Services Reg. No. 2004/09460 Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 E.mail : <u>gilroy@internext.co.za</u> | Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 | | | | | | |
| | j) Install subsoil pipes | 2 | 2 | 2 | 8 | Low | 7 | |
| | k) Cleaning outlet structures | 3 | 2 | 2 | 12 | Low | | |
| | Compact backfill, 93% AASHTO | 3 | 2 | 2 | 12 | Low | | |
| | m) Testing | 1 | 1 | 1 | 1 | Very Low | | |
| ection 2200 | 9. Prefabricated Kerbs | S | P | E | T | Risk Rating | Note/Ref. | |
| | a) Excavation up to 3 meters | 3 | 4 | 3 | 36 | High | Note/Kei. | |
| | b) Excavation in soft material | 2 | 2 | 3 | 12 | Low | By hand included | |
| | c) Excavation in hard material | 3 | 3 | 3 | 27 | Medium | by hand included | |
| | d) Backfilling | 2 | 1 | 3 | 6 | Very Low | | |
| | e) Import selected material | 2 | 2 | 1 | 4 | Very Low | | |
| | f) Concrete pipe culverts | 2 | 3 | 1 | 6 | Very Low | Procure, stack and store | |
| | g) Install: Concrete pipe culverts | 3 | 2 | 3 | 18 | Medium | Thocare, stack and store | |
| | h) Remove existing concrete | 3 | 2 | 2 | 12 | Low | Include prefabricated | |
| | i) Spoil/stack removed culverts | 3 | 2 | 1 | 6 | Very Low | | |
| | j) Manholes, catchpit inlet and outlet | 2 | 1 | 2 | 4 | Very Low | Procure, stack and store | |
| | k) Install: Manholes, catchpits, inlets and outlets | 2 | 2 | 2 | 8 | Low | Thoedre, stack and store | |
| | Construct: Headwalls | 2 | 2 | 2 | 8 | Low | | |
| ection 2300 | 10. Concrete Works: Kerbs, Channelling, Chutes, Downpip and Lining | es S | P | E | T | Risk Rating | Note/Ref. | |
| A | a) Procure, stack and store: Concrete Kerbing | 2 | 4 | 2 | 16 | Medium | SABS 927 | |
| | b) Concrete kerbing-channelling combination | 3 | 4 | 2 | 24 | Medium | Cast in-situ | |
| | c) Trimming of Excavation: Soft material | 1 | 2 | 2 | 4 | Very Low | Cust in situ | |
| | d) Trimming of Excavation: Hard material | 2 | 2 | 2 | 8 | Low | | |
| | e) Concrete lining of open drains: In situ | 2 | 2 | 2 | 8 | Low | | |
| | f) Concrete lining of open drains: V-drains | 2 | 3 | 2 | 12 | Low | | |
| | g) Surface finishing | 1 | 2 | 2 | 4 | Very Low | | |
| | Formwork for in cast situ concrete lining open dra | ns 2 | 2 | 2 | 8 | Low | | |
| | i) Sealant | 1 | 2 | 1 | 2 | Very Low | MSDS | |
| | j) Cutting bitumen surfacing & pavement layers: 50mm depth | 3 | 4 | 2 | 24 | Medium | Small plant: concrete cutte | |

| | | | | Da | te: | | 11/2020 | | |
|--------------|---|---------|---|----|-----|-------------|--|--|--|
| | S | S | | | | | | | |
| | Construction Safety Services Reg. No. 2004/094601/23 Baseline Risk Ass Construction Health and Safety Consultants Compiled by: N Gilroy, CHS PO Box 402, Harrismith, 9880 Approved by: W. Gilroy, - Pr. C E.mail : gilroy@internext.co.za Image: Construction Health and Safety Consultants | | | | | | | | |
| | k) Demolition of existing structures: Reinforced concrete. 3.0m width | 3 | 4 | 2 | 24 | Medium | Å | | |
| | Demolition of existing structures: Kerb-chann combination | el 2 | 4 | 2 | 16 | Medium | | | |
| Section 3300 | 11. Mass Earthworks | S | P | E | T | Risk Rating | Note/Ref. | | |
| | a) Cut to spoil, including haul | 3 | 3 | 3 | 27 | Medium | | | |
| | b) Excavation in soft material | 2 | 2 | 3 | 12 | Low | By hand included | | |
| | c) Excavation in hard material | 3 | 3 | 3 | 27 | Medium | | | |
| | d) Compact material: Specified AASHTO density | 3 | 4 | 3 | 36 | High | Commercial sources | | |
| | e) Rock fill and compacting | 2 | 5 | 2 | 20 | Medium | | | |
| | f) Finishing-off cut and fill slopes | 2 | 3 | 2 | 12 | Low | | | |
| | g) Overhaul | 2 | 3 | 3 | 18 | Medium | | | |
| Section 3400 | 12. Pavement Layers of Gravel Material | S | P | E | T | Risk Rating | Note/Ref. | | |
| | a) Gravel material: Haul | 3 | 3 | 2 | 18 | Medium | Commercial sources | | |
| | b) Gravel subbase stabilized: Compacted to spec AASHTO density | ified 4 | 4 | 3 | 48 | High | Chemically stabilized, MSDS | | |
| | c) Gravel base unstabilized: Compacted to speci AASHTO density | ied 3 | 3 | 2 | 18 | Medium | | | |
| | d) Gravel pavement: Compacted to specified AA density | SHTO 3 | 3 | 2 | 18 | Medium | Using cement | | |
| | e) Construction Vehicles and Mobile Plant | 4 | 5 | 5 | 100 | Very High | Establishment, maintenance and removal. | | |
| Section 3500 | 13. Stabilization | S | P | E | T | Risk Rating | Note/Ref. | | |
| | a) Stabilization: Lime | 4 | 5 | 3 | 60 | High | MSDS | | |
| | b) Stabilization: Cement | 3 | 3 | 3 | 27 | Medium | MSDS | | |
| 0 | c) Stabilization: Water curing | 1 | 3 | 1 | 3 | Very Low | | | |
| | d) Temporary diversion | 2 | 3 | 2 | 12 | Low | | | |
| Section 3600 | 14. Crushed Stone Base | S | P | E | Т | Risk Rating | Note/Ref. | | |
| | a) Construction of G2 Base | | | | | | Commercial source | | |

| | | | | Da | ite: | | 11/2020 | | | |
|--------------|---|--|---|----|------|--------------------|---|--|--|--|
| | S | Construction Safety Services Seg. No. 2004/094601/23 Revision Construction Health and Safety Consultants Compiled PO Box 402, Harrismith, 9880 Approved E.mail : gilroy@internext.co.za Compiled | | | | | | | | |
| | Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 | | | | | | | | | |
| Section 4300 | 15. Seals | S | р | E | Т | Dick Detter | A la la | | | |
| | a) Prime Coat: E-prime | 1 | 2 | 2 | 4 | Risk Rating | Note/Ref. MSDS | | | |
| | b) Asphalt surfacing | 4 | 5 | 3 | 60 | Very Low High | | | | |
| | c) Trial section | 2 | 4 | 3 | 24 | Medium | Hot mix | | | |
| | d) Test cores | 3 | 3 | 3 | 27 | Medium | | | | |
| | e) Procure, stack and store: tack/prime coat | 1 | 3 | 2 | 6 | Very Low | Environmental | | | |
| | f) Variation in active filler content: Lime/cement | 4 | 3 | 3 | 48 | High | MSDS | | | |
| | g) Backfill: Asphalt base and surface | 2 | 3 | 3 | 18 | Medium | 111505 | | | |
| | h) Application of prime/tack | 3 | 3 | 2 | 18 | Medium | MSDS | | | |
| | Procure, stack and store: Bituminous binder | 1 | 3 | 2 | 6 | Very Low | Environmental | | | |
| Section 5100 | j) Application fog spray | 2 | 3 | 3 | 18 | Medium | Traffic accommodation | | | |
| Section STOD | 16. Pitching, Stonework and Protection Against Erosion | S | P | E | T | Risk Rating | Note/Ref. | | | |
| ÷ . | a) Materials: Stone pitching | 2 | 2 | 1 | 4 | Very Low | Procure, stack, store and deliver to working areas | | | |
| Section 5400 | b) Stone pitching | 2 | 2 | 3 | 12 | Low | | | | |
| Section 3400 | 17. Guardrails | S | P | E | Т | Risk Rating | Note/Ref. | | | |
| | a) Excavation | 2 | 2 | 2 | 8 | Low | | | | |
| | b) Installation (timber or steel) | 2 | 4 | 2 | 16 | Medium | | | | |
| | c) Removal of existing guardrails | 3 | 4 | 2 | 24 | Medium | | | | |
| Section 5500 | d) Nailing of gang plates on timer posts 18. Fencing | 2 | 4 | 1 | 8 | Low | | | | |
| | | S | P | E | Т | Risk Rating | Note/Ref. | | | |
| | a) Clearing fence line | 2 | 1 | 1 | 2 | Very Low | | | | |
| | b) Procure, erect, repair existing fence c) Excavation and installation: Standards, droppers | 3 | 4 | 2 | 24 | Medium | | | | |
| | straining posts, stays and anchors | 3 | 4 | 2 | 24 | Medium | | | | |
| Section 5600 | d) Procure and install new gates | 3 | 3 | 2 | 18 | Medium | | | | |
| | 19. Road Signs | S | P | E | T | Risk Rating | Note/Ref. | | | |
| | a) Procure, stack and store | 2 | 3 | 1 | 6 | Very Low | | | | |
| | b) Excavate, install and backfill sign support c) Real-filling constant is a support | 2 | 2 | 2 | 8 | Low | | | | |
| | c) Backfilling cement treated | 2 | 3 | 2 | 12 | Medium | MSDS | | | |

| | and the second se | | | Da | te: | | 11/2020 |
|--------------|---|--|---|----|--------|----------------|-----------------------------------|
| | S | | | Re | visior | Number: | CSS/001 |
| | Construction Safety Services Reg. No. 2004/094601/ Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 E.mail : <u>gilroy@internext.co.za</u> | Baseline Risk Assessment Compiled by: N Gilroy, CHSM Approved by: W. Gilroy,- Pr. CHSA | | | | | |
| | d) Concrete backfill for footing | 2 | 3 | 2 | 12 | Medium | 12 |
| | e) Gravel drainage layers below road sign footings | 2 | 3 | 2 | 12 | Medium | |
| | f) Temporary covering of permanent road signs | 1 | 1 | 2 | 2 | Very Low | |
| | g) Dismantling and disposal of redundant signs | 2 | 1 | 3 | 6 | Very Low | |
| Section 5700 | 20. Road Marking | 5 | P | E | T | Risk Rating | Note/Ref. |
| | a) Setting out and pre-marking | 4 | 4 | 4 | 64 | Very High | Note/net. |
| | Removal of existing, temporary or permanent road marking: Sandblasting | 4 | 3 | 2 | 24 | Medium | |
| | c) Retro-reflective paint | 3 | 3 | 4 | 36 | Very High | MSDS |
| | d) Install/Remove road studs | | | | | i ci j i i git | 111000 |
| Section 5900 | 21. Finishing the Road and Road Reserves | S | P | E | T | Risk Rating | Note/Ref. |
| | a) Trimming: Machine | 3 | 4 | 1 | 12 | Low | (Bulldozer and/or moto grader) |
| | b) Trimming: Hand | 2 | 1 | 1 | 2 | Very Low | 0. eeel |
| | Preparing for grassing: Scarifying for loosing material | 1 | 1 | 1 | 1 | Very Low | |
| | Applying chemical fertilisers and/or soil- improvement material | 3 | 2 | 2 | 12 | Low | |
| | e) Stockpiling topsoil | 2 | 2 | 1 | 4 | Very Low | |
| | f) Grassing | 1 | 1 | 1 | 1 | Very Low | |
| | g) Watering | 1 | 1 | 1 | 1 | Very Low | |
| | h) Removal of undesirable vegetation | 2 | 1 | 3 | 6 | Very Low | |
| Section 6600 | 22. No-fines Concrete, Joint, Bearing, Bolt Groups for Electrification, Parapets and Drainage for Structures | S | Р | E | T | Risk Rating | Note/Ref. |
| | a) Repair bridge joints | 3 | 3 | 3 | 27 | Medium | Traffic accommodation |
| | b) Structural steelwork | 2 | 2 | 4 | 16 | Medium | |
| Section 7300 | 23. Concrete Block Paving | S | P | E | T | Risk Rating | Note/Ref. |
| | Block paving: 60mm thickness | 2 | 4 | 2 | 16 | Medium | |
| | b) Concrete edge beams: Interlocking, 60mm thickness | 1 | 2 | 2 | 4 | Very Low | |
| | c) Apply herbicide | 2 | 2 | 2 | 8 | Low | Certification |

| | | | | | | Da | te: | | 11/2020 |
|-------------|--|--|--|------|--------|--------|---------|--------------|--------------------------------------|
| | | | S | | Re | vision | Number: | CSS/ 001 | |
| | Const | struction Safety Services Reg. No. 2004/094601/23 Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 E.mail : gilroy@internext.co.za Reg. No. 2004/094601/23 Reg. No. 2004/094601/23 Baseline Risk Ass Compiled by: N Gilroy, CHSM Approved by: W. Gilroy, - Pr. Cl | | | | | | | |
| Section | 8100 & 8200 | 24. Test | ing Materials, Workmanship and Quality Control | S | P | E | T | Risk Rating | Note/Ref. |
| | | a) | | 2 | 2 | 2 | 8 | Low | ingrey ker. |
| | | b) | Testing material and workmanship: Laboratory facilities | 3 | 3 | 2 | 18 | Medium | |
| | | c) | Testing material and workmanship: Transport, stack and store | 3 | 3 | 1 | 9 | Low | |
| | | d) | Testing material and workmanship: Hazardous devices | 3 | 4 | 5 | 60 | High | Troxler etc. |
| Section | Section D1010 | | Il Contractors Development, Training and nunity Participation | S | Р | E | T | Risk Rating | Note/Ref. |
| | | a) | Community participation | 4 | 5 | 5 | 100 | Very High | |
| | | b) | Training: Generic and/or accredited (accommodation thereof) | 1 | 2 | 5 | 10 | Low | |
| | | c) | Community Works: Pedestrian sidewalks | 2 | 4 | 3 | 24 | Medium | Social responsibility |
| | | | Site establishment of nominated sub-contractors | 2 | 1 | 5 | 10 | Low | |
| Ref. no. | Hazard | Risk | | Calc | ulatio | n | 3 | Risk Rating | Compliance Reference |
| 5 | Construction Health and Safety | 1. Accid | ent and Incidents | S | P | E | Т | Dest all set | |
| | Accident and Incident | a) | Near miss | 1 | 5 | 5 | 25 | Medium | Sec 24(1)(c); GMR 7 |
| | Investigation Management: The non-compliance of | b) | First aid treatment | 1 | 5 | 1 | 5 | Very Low | GSR 3(3) and (4); COIDA Sec 71(1) |
| | implementing a system to investigate and establish the root | c) | Medical treatment- Hospitalised less than 14 days | 2 | 3 | 2 | 12 | Low | GSR 3(3) and (4); COIDA Sec 71(1) |
| | cause of incidents and/or accidents | | Person dies, becomes unconscious, suffers the loss of a limb, illness that can cause permanent disability or death | 5 | 5 | 5 | 125 | Very High | Sec 24 1 (a); GAR 8 and 9 |
| | | | Dangerous substance spilled | 3 | 5 | 3 | 45 | High | Sec 24 1 (c)(i) |
| | | | Uncontrolled release of substance under pressure | 4 | 3 | 5 | 60 | High | Sec 24 1 (c)(ii); GMR 7 |
| | | g) | Machinery failure - flying or falling objects | 3 | 2 | 5 | 30 | Medium | Sec 24 1 (c)(iii); GMR 7 |

| Contract No. 2 | ZNB 00124/00000/00/HC |)D/INF/20/T |
|----------------|-----------------------|-------------|
|----------------|-----------------------|-------------|

F

| | 2 | | | | Date: | | 11/2020 | | |
|------|-----------------------------------|------------------------|---|--|----------------------------------|--|---|--|--|
| | | | S | | Revision | n Number: | CSS/ 001 | | |
| | Cons | truction | Safety Services Reg. No. 2004/094601/2 Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 E.mail : gilroy@internext.co.za | 23 | Compile Approve | Baseline R d by: N Gilroy d by: W. Gilro | isk Assessment , CHSM py,- Pr. CHSA | | |
| | | 2. Inve | stigating, Reporting and Recording Procedures | | | | A | | |
| | | a) | | S | P E T | Risk Rating | Compliance Reference | | |
| | | b) | | N/A | | Medium | Sec 24(2); GMR 7; GAR 9 (2 | | |
| | | c) | Near miss | Epilure | to comply to | Very Low | CR 9(7)(b) | | |
| | | d) | First aid treatment | legisla | | Very Low | Sec 24(1)(c); GMR 7 | | |
| | | e) | | requir | ements can | Low | Sec 14(e) of the Act; COIDA Sec 38(1); | | |
| | 5 | | Medical treatment- Hospitalised less than 14 days | | o civil and/or al prosecution | Medium | Sec 14(e) of the Act; COIDA Sec 38(1) and 39; GAR 8 (1) and (2) | | |
| | | f) | Person dies, becomes unconscious, suffers the loss of a limb, illness that can cause permanent disability or death | | | Very High | Sec 14(e) of the Act; COIDA Sec 38(1) and 39; GAR 8 and 9(1) | | |
| | - (9a.) | g) | Dangerous substance spilled | | | High | Sec 24 1 (c)(i) | | |
| | | h) | Uncont. release of substance under pressure | | | Very High | Sec 24 1 (c)(iii); GMR 7 | | |
| Ref. | Hazard | i) | Machinery failure - flying or falling objects | | | High | Sec 24 1 (c)(ii); GMR 7 | | |
| no. | | Risk | | | | | | | |
| 6 | Construction Health and Safety | 1. Act | | Notes/ | Reference | | - | | |
| | Legislation and Regulations | a) | The Occupational Health and Safety Act, Act 85 of | And the local division of the local division | ed February 20 | 14 | | | |
| | Management: | | 1993 | | l Administrative | | | | |
| | The non-compliance of legislative | | | | Safety Regulat | | | | |
| | and regulative requirements. | | | | uction Regulatio | | | | |
| | | Environr Facility R | | | aces | | | | |
| | | | | Environmental Regulations for Workplaces Facility Regulations | | | | | |
| | | | | | Driven Machinery Regulations | | | | |
| | | | | | I Machinery Reg | | | | |
| | | | | | al Installations I | | | | |
| | | | | | al Machinery Re | | | | |
| | | b) | The Compensation for Injuries and Disease Act, Act 130 of 1993 | | of Good Standin | | | | |

| | | | and the second se | | | Da | te: | | 11/2020 | |
|-------------|---|-----------|---|-------|--------|--------|----------|--------------------|--|--|
| | | | S | | | Re | vision | Number: | CSS/ 001 | |
| | Con | struction | Safety Services Reg. No. 2004/094601, Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 E.mail : <u>gilroy@internext.co.za</u> | 23 | | | | by: N Gilroy | eline Risk Assessment N Gilroy , CHSM W. Gilroy,- Pr. CHSA | |
| | | c) | The National Environmental Management Act, Act 107 of 1998 | | | | | / | 4 | |
| | | d) | The Basic Conditions of Employment Act, Act 75 of 1997 | | | | | | | |
| | | e) | The Committee of Land Transport Officials; Department of Transport | COLTO | | | | | | |
| | | f) | The South African Development Community Road Traffic Signs Manual | 10000 | CRTSI | | | | | |
| | | g) | The Unemployment Insurance Act, Act 30 of 1966 | UIF | 5 | | | | | |
| | | h) | The South African National Standards | SAM | IS/SAE | IS | | | | |
| | | i) | ISO | Inte | rnatio | nal St | andard | s Organisation | | |
| - | | j) | AASHTO | | | | | | y and Transport Officials | |
| lef. no. | Hazard | Risk | | Cal | ulatio | n | 1 | Risk Rating | Compliance Reference | |
| 7 | Construction Health and Safety | 1. Healt | h and Safety | S | S P E | | | - | | |
| | Health, Hygiene and Environmental Management: The non-compliance of Health, | a) | Provide and maintain a working environment that is safe and without risk to the health of his/her employees | 5 | 5 | 5 | T 125 | Very High | Sec 8(1) of the Act | |
| | safety, hygiene and | b) | General duties of employers to their employees | 5 | 5 | 5 | 125 | Very High | Sec 8(2) of the Act | |
| | environmental legislative | c) | General duties of employees at the work place | 5 | 5 | 5 | 125 | Very High | Sec 14 of the Act | |
| | requirements | d) | Provide first aid and emergency equipment | 5 | 5 | 5 | 125 | Very High | GSR 3 and 4; ER 9 | |
| | | e) | Develop, implement and maintain a health and safety plan on the construction site | 5 | 5 | 5 | 125 | Very High | CR 7(1)(a) | |
| | | f) | Manage construction work by competent people | 5 | 3 | 5 | 75 | Very High | CR 8 | |
| | | | Cause risk assessments to be performed before and during construction work | 5 | 5 | 5 | 125 | Very High | CR 9(1) | |
| | | | Provide information and training | 5 | 3 | 5 | 75 | Very High | Sec 8(1)(e) of the Act; GAF 4; CR 9(3) | |
| | | 2. Hygie | | S | Ρ | E | Т | Risk Rating | Compliance Reference | |
| | | a) | Provide and maintain clean toilet facilities | 3 | 1 | 5 | 15 | Low | CR 30(1)(b) | |

| | | | | | | Da | te: | | 11/2020 | | |
|-------------|--|---|---|---------|--------|--|-----------|---------------------|---|--|--|
| | | | S | | | Re | vision | Number: | CSS/001 | | |
| | Const | nstruction Safety Services Reg. No. 2004/094601/23 Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 E.mail : gilroy@internext.co.za | | | | Baseline Risk Assessment Compiled by: N Gilroy, CHSM Approved by: W. Gilroy,- Pr. CHSA | | | | | |
| | | b) | Provide sheltered eating facilities | 2 | | 1. | 1.00 | | A | | |
| | | c) | Provide toilet paper and cleansing agent | 3 | 2 | 5 | 30 | Medium | CR/30(1)(c) | | |
| | | d) | | 3 | 2 | 5 | 30 | Medium | FR 2(3)(a) and (d) | | |
| | | | onmental | 5 | 5 | 5 | 125 | Very High | FR 7 | | |
| | | a) | Practice good housekeeping | \$ 5 | P | E | T | Risk Rating | Compliance Reference | | |
| | | b) | Implement a waste management system | 3 | 3 | 5 | 75 | Very High | CR 27; ER 6 | | |
| | | c) | Provide adequate and sufficient ventilation and lighting | 5 | 5 | 3 | 27 125 | Medium Very High | CR 27 (1)(b),(e) and (f) ER 3, 4 and 5 | | |
| | | d) | Dangerous chemical/substance spillage | 5 | 5 | 5 | 125 | Very High | Environmental Legislation | | |
| Ref. no. | Hazard | Risk | | - | ulatio | - | 125 | Risk Rating | Compliance Reference | | |
| 8 | Construction Health and Safety | 1. Employees | | S | P | E | T | | TEST MORE ALLOS | | |
| | Communication Management: The non-compliance of implementing a communication system between the Principal | d) | instructions and training as may be necessary to ensure the health and safety of his employees at the work place | 4 | 4 | 5 | 80 | Very High | Sec 8(2)(e) of the Act CR 17(12)(c) | | |
| | Contractor and his/her employees, site visitors, appointed contractors, the client, the client's representative or an inspector. | e) | The contractor must ensure that all employees under his/her control are informed, instructed and trained regarding any hazard and the related work procedures and/or control measures before any work commences | 4 | 4 | 5 | 80 | Very High | CR 9(3) | | |
| | | 2. Signa | | S | P | E | T | Risk Rating | Compliance Reference | | |
| | | e) | Supply, install and maintain health and Safety Signage to inform and communicate hazards and risks prevalent on the construction site to employees and persons other than employees, to ensure a reasonable safe and healthy environment at the work place | 3 | 4 | 5 | 60 | High | Sec 8(2)(e) GAR 4 | | |
| | 2 | f) | Identify the location of excavations which is accessible to the public or where persons are | 3 | 4 | 4 | 48 | High | CR 13(2)(i) CR13(2)(l) | | |

| | Construction | Safety Services Reg. No. 2004/094601/2 Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 | 3 | | Re | visior | Number: | 11/2020 CSS/ 001 |
|-------------|--------------|--|--|-------|----|---------|--------------------------|--|
| | Construction | Construction Health and Safety Consultants | 3 | | | | | |
| | | E.mail : gilroy@internext.co.za | Baseline Risk Assessment Compiled by: N Gilroy, CHSM Approved by: W. Gilroy,- Pr. CRSA | | | | | |
| | | working/carrying out tests. | - | | | | (9) | X |
| | g) | Identify the location of first aid equipment | - | _ | - | | / | $\overline{1}$ |
| | h) | Prohibit smoking (ones flames of | 3 | 3 | 2 | 18 | Medium | GSR 3(6) |
| | | Prohibit smoking/open flames in flammable storage areas | 5 | 5 | 5 | 125 | Very High | CR 29(1)(c) |
| | 3. Princ | ipal Contractor and Contractor | S | P | E | T | Dick Dotton | |
| | i) | Provide the potential contractors with the Health and Safety Specifications | 5 | 5 | 5 | 125 | Risk Rating Very High | Compliance Reference CR 7(1)(c)(i) |
| | | Audit contractors at least once every thirty days, provide the finding within 7 days | 3 | 3 | 5 | 45 | High | CR 7(1)(c)(vii); CR 5(1)(p) |
| | k) | When change are brought about to the design and construction, make available sufficient health and safety information | 3 | 4 | 5 | 60 | High | CR 7(c)(ix) |
| | 1) | Discuss the content of the Health and Safety Plan | 5 | 3 | 5 | 75 | | |
| | m) | Ensure co-operation between all contractors | 3 | 5 | 5 | | Very High | CR 7(1)(x) |
| | 4. Princi | pal Contractor and Client | S | P | E | 75 T | Very High | CR 7(4) and 2(d) |
| | | Develop and implement the Health and Safety Plan as discussed | 5 | 5 | 5 | 125 | Risk Rating Very High | Compliance Reference CR 5(1)(I) |
| | b) | Open and keep on site a Health and Safety File | 3 | 5 | 5 | 75 | Manada | |
| | c) | Develop a comprehensive list of all contractors | 3 | 3 | 5 | 45 | Very High | CR 7(1)(b) |
| | | under the Principal Contractor, including their responsibilities and duties | 5 | | 5 | 45 | High | CR 7(1)(f) |
| | d) | Site Diary | 1 | 5 | 5 | 25 | Madi | |
| | e) | Incident and Accident Records | 5 | 2 | 5 | 25 | Medium | Contractual requirement |
| | 5. Site Vi | sitors | | 4 | 3 | 50 | High | Sec 14(e) and 24 of the OHS Act; GAR 8; CIOD Act; GMR |
| | | | S | Р | E | Т | Risk Rating | Compliance Reference |
| | | Ensure that all visitors to a construction site undergo health and safety induction training pertaining to the hazards prevalent on the site | 5 | 5 | 5 | 125 | | CR 7(6) |
| tef. Hazard | Risk | | Calcu | ation | | | Risk Rating | Compliance Reference |

Г

| | | | | | | | | Date: | | | |
|---|---|--------|---|---|------------|----------|---------|-----------|---------------------------|-------------------|--|
| | | S | | | | | vision | | CSS/001 | | |
| | Construction Safety Services Reg. No. 2004/094602 Construction Health and Safety Consultants PO Box 402, Harrismith, 9880 E.mail : <u>gilroy@internext.co.za</u> | | | | | D | | | | | |
| 9 | Construction Health and Safety | 1. Eme | rgency Preparedness | | | | - | | X | | |
| | Emergency Preparedness Management: The non-compliance of emergency preparedness on the construction site | | Letter of Good Standing with the Compensation Fund or a licensed compensation insurer | 3 | Р 5 | E | T 75 | Very High | CR 5(1)(j) | | |
| | | b) | All employees in possession of a valid medical fitness certificate | 4 | 3 | 5 | 60 | High | CR 7(1)(g) 23(1)(d)(ii | ; CR 17(12)(a); C | |
| | | | c) Make available first aid and emergency equipment 5 5 5 125 Very High GSR on the construction site | | GSR 3 (1), | | | | | | |
| | | (b | Appoint a competent first aider as per GSR | 4 | 4 | 5 | 80 | Very High | GSR 3 (4) | | |
| | | e) | Implement emergency evacuation procedures | 4 | 3 | 5 | 60 | High | | (7), (8), (9) | |
| | | f) | The Employer must provide such information, instructions and training as may be necessary to ensure the health and safety of his employees at the work place | 4 | 4 | 5 | 80 | Very High | | of the Act | |
| | | g) | The contractor must ensure that all employees under his/her control are informed, instructed and trained regarding any hazard and the related work procedures and/or control measures before any work commences | 4 | 4 | 5 | 80 | Very High | CR 9(3) | 8 | |
| | | h) | Implement appropriate measures to avoid the risk of fire | 4 | 3 | 4 | 48 | High | CR 29 | | |
| | | i) | Fire Precaution Escape | 5 | 5 | 5 | 125 | Very High | ER 9 | | |
| | | j) | Supply, install and maintain health and Safety Signage to inform and communicate hazards and risks prevalent on the construction site | 3 | 4 | 5 | 60 | High | Sec 8(2)(e) GAR 4 | | |
| | | k) | Identify the location of first aid equipment | 3 | 3 | 2 | 18 | Medium | GSR 3(6) | | |
| | | ŋ | | | | 5 | 125 | Very High | CR 5(1)(g) | | |

D3.3 Guidelines for construction and maintenance projects under Covid-19 Lockdown

The Employer has prepared guidelines which set out the key principles and minimum requirements that define responsible, healthy and safe operations for road construction operations under COVID-19 Lockdown conditions, for the Contractor to comply with. In addition, the Contractor shall comply with any new COVID-19 Regulations issued by Government.

The guidelines have been included as Annexure A at the end of this Project Document.

D4. APPLICATION FOR CONSTRUCTION WORK PERMIT

Where the contract meets the requirements of Construction Regulation 3, the Employer must at least 30 days before commencement of the work and in accordance with the requirements of Construction Regulation 3, apply to the Provincial Director of the Department of Labour in writing for a construction work permit to perform construction work. The Employer's application must be done in a form similar to Annexure 1 of the Construction Regulations, and submitted with the required documentation, some of which the Contractor shall provide as stated in the Contract Data.

A copy of the construction work permit must be kept on site in the occupational health and safety file, available for inspection by inspectors, the Employer, the Employer's Agent, the Construction Health and Safety Agent, subcontractors, employees, representative trade unions and any other persons on the site. The Provincial Director will assign a site-specific number for each construction site, which must be conspicuously displayed at the main entrance to the site.

D5. NOTIFICATION OF CONSTRUCTION WORK

Where the contract meets the requirements of Construction Regulation 4, the Contractor shall, before commencement of the work and in accordance with the requirements of Construction Regulation 4, notify the Provincial Director of the Department of Labour of the intention to carry out the construction work, using the pro forma form included as Annexure 2 to this Health and Safety Specification.

A copy of the notification form must be kept on site, available for inspection by inspectors, the Employer, the Employer's Agent, the Construction Health and Safety Agent, subcontractors, employees, representative trade unions and any other persons on the site. A copy of the notification form shall also be kept on the health and safety file, and a further copy shall be forwarded to the Employer for his records.

D6. HEALTH AND SAFETY PLAN

Before commencement of any construction work, the Contractor shall prepare a project specific Health and Safety Plan complying with the requirements of Construction Regulation 7(1)(a) and this Health and Safety Specification.

The Health and Safety Plan must include a risk assessment performed and recorded in writing by a competent person as required in terms of Construction Regulation 9. The risk assessment shall identify and evaluate the risks and hazards that may be expected during the execution of the work under the contract, and it shall include a documented plan and applicable safe work procedures to mitigate, reduce or control the risks and hazards identified.

The Health and Safety Plan shall be available on site for inspection by inspectors, the Employer, the Employer's Agent, subcontractors, employees, representative trade unions, and health and safety representatives and committee members, and must be monitored and reviewed periodically by the Contractor.

D7. APPOINTMENT OF EMPLOYEES AND SUBCONTRACTORS

D7.1 Appointments

The Contractor shall appoint in writing all employees.

The Contractor shall appoint in writing all subcontractors, and such appointments shall be in compliance with the requirements of Construction Regulation 7.

D7.2 Health and safety induction training

No person shall be allowed or permitted to enter the site of the works unless such person has undergone health and safety induction training pertaining to the hazards prevalent on the site.

The Contractor shall ensure that all employees under his control, including subcontractors and their employees, undergo health and safety induction training by a competent person before commencement of construction work in compliance with Construction Regulations 7(5) and 9(3) and (4).

The Contractor shall ensure that all visitors to the construction site undergo health and safety induction and are provided with the necessary personal protective equipment in compliance with Construction Regulation 7(6).

D7.3 Medical certificate of fitness

The Contractor shall ensure that every employee, including subcontractors and their employees, has a valid medical certificate of fitness issued in compliance with Construction Regulation 7(1)(g) or 7(8) as applicable.

D8. APPOINTMENT OF SAFETY PERSONNEL

D8.1 Construction manager

Refer to Construction Regulation 8(1), (2), (3) and (4).

The Contractor shall appoint a full-time **Construction Manager** with the duty of managing all the construction work on the site, including the duty of ensuring occupational health and safety compliance.

The Contractor may also have to appoint one or more **assistant construction managers** to assist the Construction Manager where justified by the scope and complexity of the works.

D8.2 Construction health and safety officer

Refer to Construction Regulation 8(5) and (6).

Taking into consideration the size of the project and the dangers, hazards or risks that can be expected, the Contractor shall appoint in writing a full-time or part-time **construction health and safety officer** to assist in the control of all health and safety related aspects on the site. The construction health and safety officer shall be registered as required by the Chief Inspector of the Department of Labour and shall have the necessary competencies and resources to assist the Contractor.

D8.3 Construction supervisor

Refer to Construction Regulation 8(7), (8), (9) and (10).

The Contractor shall appoint a **construction supervisor** responsible for construction activities and ensuring occupational health and safety compliance on the construction site.

The Contractor may also have to appoint one or more competent employees to assist the construction supervisor where justified by the scope and complexity of the works.

D8.4 Health and safety representatives

In terms of Sections 17 and 18 of the Act (OHSA 1993) the Contractor, being the employer in terms of the Act for the execution of the contract, shall appoint a **health and safety representative** whenever he has more than 20 employees in his employment on the site of the works. The health and safety representative must be selected from employees who are employed in a full-time capacity at a specific workplace.

The number of health and safety representatives for a workplace shall be at least one for every 50 employees.

The function of health and safety representative(s) will be to review the effectiveness of health and safety measures, to identify potential hazards and major incidents, to examine causes of incidents (in collaboration with his employer, the Contractor), to investigate complaints by employees relating to health and safety at work, to make representations to the employer (Contractor) or inspector on general matters affecting the health and safety of employees, to inspect the workplace, plant, machinery, etc. on a regular basis, to participate in consultations with inspectors and to attend meetings of the health and safety committee.

D8.5 Health and safety committee

In terms of Section 19 of the Act (OHSA 1993), the Contractor (as employer) shall establish one or more health and safety committees where there are two or more health and safety representatives at a workplace. The persons selected by the Contractor to serve on the committee shall be designated in writing.

The function of the health and safety committee shall be to hold meetings at regular intervals but at least once every three months, to review the health and safety measures on the contract, to discuss incidents related to health and safety with the Contractor and the inspector, to make recommendations regarding health and safety to the Contractor and to keep record of recommendations and reports made by the committee.

D8.6 Competent persons

The Contractor shall appoint in writing designated competent employees and/or other competent persons as required by the Act and Regulations. Such appointments shall be in accordance with the relevant applicable sections of the Act and Regulations as determined by the requirements of the contract.

A competent person may be appointed for more than one part of the construction work with the understanding that the person must be suitably qualified and able to supervise at the same time the construction work in all the work situations for which he has been appointed.

The appointment of competent persons to supervise parts of the construction work does not relieve the Contractor from any of his responsibilities for compliance with <u>all</u> requirements of the Construction Regulations.

D9. RECORDS AND REGISTERS

The Contractor shall keep records and registers related to health and safety on site as required by the relevant applicable sections of the Act and Regulations as determined by the requirements of the contract. Such records and registers shall be available for periodic inspection by inspectors, the Employer, the Employer's Agent, the Construction Health and Safety Agent, subcontractors, employees and representatives of trade unions.

D10. CONTRACTOR'S RESPONSIBILITIES

For this contract the Contractor will be the mandatary of the Employer (Client), as defined in the Act (OHSA 1993), which means that the Contractor has the status of employer in his own right in respect of the contract. The Contractor is therefore responsible for all the duties and obligations of an employer as set out in the Act (OHSA 1993) and the Construction Regulations 2014.

Before commencement of work under the contract, the Contractor shall enter into an agreement with the Employer (Client) in terms of C1.4 'Agreement in terms of Section 37(2) of the Occupational Health and Safety Act No. 85 of 1993', to confirm his status as mandatary (employer) for the contract under consideration.

The Contractor is advised in his own interest to make a careful study of the Act and the Construction Regulations, as ignorance of the Act and the Regulations will not be accepted in any proceedings related to non-conformance to the Act and the Regulations.

D11. MEASUREMENT AND PAYMENT

It is a condition of this contract that contractors who submit tenders for this contract shall make provision in their various tendered rates and prices for all costs related to the health and safety measures required in terms of the Act and Regulations during the construction process.

(a) Health and safety plan

The Contractor shall assess the risks associated with the Works when preparing the health and safety plan. In addition, the Contractor shall implement the health and safety plan, including the provision of a dedicated, full time health and safety officer, carrying out all the required site health and safety training and briefings, staff medical evaluations, monitoring and administrating the health and safety plan and for supplying all transport, personal protection safety items, other health and safety equipment, safety notices and any other health and safety related items that are required on site. Provision is made for the costs of preparing and implementing the health and safety plan in item B13.03 of the Bill of Quantities.

(b) Safety appointments

No separate additional payment will be made to cover the costs related to persons appointed as required in terms of the Act and Regulations to fulfil the various health and safety functions. Such persons include the Construction Manager, any assistant construction managers, the construction health and safety officer, the construction supervisor, any assistant construction supervisors, health and safety representatives, health and safety committee members and competent persons, all as referred to in subclauses E8.1 to E8.6 above. The Contractor shall therefore make provision in the various tendered rates and prices for all costs related to such persons, and for which no separate additional payment will be made except to the extent provided in item B13.03 of the Bill of Quantities.

(c) Records and registers

The keeping of records and registers related to health and safety on site as described in clause E9 above shall be regarded as a normal duty of the Contractor for which payment shall be deemed to be included in the Contractor's various tendered rates and prices, and for which no separate additional payment will be made except to the extent provided in item B13.03 of the Bill of Quantities.

(d) Medical certificates

No separate additional payment will be made to cover the costs related to obtaining the medical certificates of fitness required for every employee, including subcontractors and their employees, issued in compliance with Construction Regulation 7(1)(g) or 7(8) as applicable. The Contractor shall therefore make provision in the various tendered rates and prices for all costs related to such medical certificates, and for which no separate additional payment will be made except to the extent provided in item B13.03 of the Bill of Quantities.

ANNEXURE 2

OCCUPATIONAL HEALTH AND SAFETY ACT, 1993 (Regulation 4 of the Construction Regulations, 2014)

NOTIFICATION OF CONSTRUCTION WORK

| 1. | (a) | Name and postal address of principal contractor: |
|----|-------|--|
| | (b) | Name and telephone number of principal contractor's contact person: |
| 2. | Princ | sipal contractor's compensation registration number: |
| 3. | (a) | Name and postal address of client: |
| | (b) | Name and telephone number of client's contact person or agent: |
| 4. | (a) | Name and postal address of designer(s) for the project: |
| | (b) | Name and telephone number of designer's(s') contact person(s): |
| 5. | | and telephone number of principal contractor's construction manager on site appointed ms of regulation 8(1): |
| 6. | | e(s) of principal contractor's assistant construction manager(s) on site appointed in terms ulation 8(2): |
| | | |

ANNEXURE 2 - Continued

| 7. | Exact physical address of the construction site or site office: |
|-----|---|
| | |
| | |
| | |
| 8. | Nature of the construction work: |
| | |
| | |
| | |
| 9. | Expected commencement date: |
| 10. | Expected completion date: |
| 11. | Estimated maximum number of persons on the construction site: |
| | Total: Female: Female: |
| 12. | Planned number of contractors on the construction site accountable to principal contractor: |
| | |
| 13. | Name(s) of contractors already selected: |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| Pri | ncipal Contractor Date |

| Client's Agent (where applicable) | Date |
|-----------------------------------|------|
| Client | Date |

• THIS DOCUMENT IS TO BE FORWARDED TO THE OFFICE OF THE DEPARTMENT OF LABOUR **PRIOR TO COMMENCEMENT** OF WORK ON SITE.

C3.3 PARTICULAR SPECIFICATIONS

PART E: EXPANDED PUBLIC WORKS PROGRAMME

PART E: EXPANDED PUBLIC WORKS PROGRAMME

E1. SCOPE

This part provides the specifications with regard to the following:

- (a) The Expanded Public Works Programme (EPWP); and
- (b) The National Youth Service (NYS) programme, which is a government programme implemented by the National Department of Public Works forming part of the Expanded Public Works Programme (EPWP).

The Contractor shall be required to participate in job creation (employment of local labour) by executing various portions of the Works using local labour (<u>unskilled or semi-skilled</u>), recruited from the local community, who are South African Citizens or foreigners in possession of a work visa issued by the Department of Home Affairs (only one such foreigner may be employed on any project). Such local labour shall be the targeted participants in the EPWP and NYS programmes.

Furthermore, in order to avoid duplication of training facilities, the provision of training facilities for all structured training, including for the structured training described in Part F: Small Contractor Development (in those instances where Part F is included in the contract), shall be measured and paid for in terms of the pay items provided in this Part E.

E2. EXPANDED PUBLIC WORKS PROGRAMME (EPWP)

E2.1 Labour-enhanced construction, supervision and management for the Expanded Public Works Programme (EPWP)

The Expanded Public Works Programme (EPWP) is a multi-sectoral government initiative to create jobs. In the case of the infrastructure sector, existing government expenditure is realigned using labour-enhanced technologies to create job opportunities. This involves the use of both labour and construction equipment, where labour is preferred and construction equipment is used appropriately.

All work undertaken in terms of the Expanded Public Works Programme (EPWP) shall be implemented using labour-enhanced construction methods to the extent economically feasible, in accordance with the "Guidelines for the Implementation of Labour-Enhanced Infrastructure Projects under the Expanded Public Works Programme (EPWP) Third Edition 2015".

The aforementioned guidelines can be downloaded from the EPWP website of the Department of Public Works (<u>http://www.epwp.gov.za/)</u>.

Contractors shall note that they shall employ in labour-enhanced works only the following supervisory and management staff that have completed the required Skills Programme in terms of Appendix C of the aforementioned guidelines:

- (a) Foremen / Supervisors at NQF level 4 "National Certificate: Supervision of Civil Engineering Construction Processes";
- (b) Site Agent / Construction Manager at NQF level 5 "Manage Labour-Enhanced Construction Processes" or equivalent Quality Council for Trades and Occupations (QCTO) qualifications at NQF level 5 or 7.

In addition to their normal supervisory and management functions, the aforementioned supervisory and management staff shall also be responsible for setting the workers' daily tasks in accordance with labour-enhanced construction principles, and for ensuring that the EPWP job creation reporting data is accurately recorded on a daily basis and compiled and submitted to the Employer each month in accordance with clause E4 of this Part E.

E2.2 Labour laws applicable to the Expanded Public Works Programme (EPWP)

The work to be undertaken on this contract by unskilled or semi-skilled workers under the Expanded Public Works Programme (EPWP) shall be implemented in accordance with:

- (a) the Code of Good Practice for Employment and Conditions of Work for Expanded Public Works Programmes (EPWP), issued in terms of the Basic Conditions of Employment Act of 1997 by the Minister of Labour in Government Notice No. 129 of 18 February 2011 (Government Gazette No. 34032 of 18 February 2011); and
- (b) Ministerial Determination 4: Expanded Public Works Programmes, issued in terms of the Basic Conditions of Employment Act of 1997 by the Minister of Labour in Government Notice No. R347 of 4 May 2012.

The aforementioned Government Notice No. R347 contains the standard terms and conditions for workers employed in elementary occupations on an Expanded Public Works Programme (EPWP). These terms and conditions do not apply to persons employed in the supervision and management of an Expanded Public Works Programme (EPWP).

The above documents can be downloaded from the EPWP website of the Department of Public Works (<u>http://www.epwp.gov.za/)</u>.

E2.3 Persons to be employed under the Expanded Public Works Programme (EPWP)

All local labour required for the execution of labour-enhanced works shall be engaged strictly in accordance with prevailing legislation.

The Contractor shall, through the Project Liaison Committee (PLC) and with the assistance of the Community Liaison Officer (CLO), inform the local community of the labour-enhanced works proposed and the employment opportunities thereby presented.

The Contractor shall determine the minimum education level / skills required to undertake the works specified. In consultation with the PLC and the War Room convener for each relevant ward, selection of the local labour shall be made from households on the Operation Sukuma Sakhe (OSS) database profiled through the War Room for each ward. The list obtained from the OSS database must be accompanied by a letter from the War Room convener confirming that all the information provided was sourced from the War Room and that all listed incumbents reside within the relevant ward. The Contractor must maintain records of household profiles as part of the portfolio of evidence for selection. Selection shall be based on the minimum education level / skills required and the most-needy households, as determined by the household profiling. Preference shall be given for at least one person from each household in the community to be employed before further persons are considered for selection.

The Contractor shall endeavour to ensure that the number of temporary jobs using local labour (<u>unskilled or</u> <u>semi-skilled</u>), recruited from the local community, who are South African Citizens or foreigners in possession of a work visa issued by the Department of Home Affairs (only one such foreigner may be employed on any project), shall include for a minimum allocation of:

- (a) 60% women;
- (b) 55% youth who are between the ages of 18 and 35; and
- (c) 2% persons with disabilities.

All labour recruitment, employment and associated risks shall remain the sole responsibility of the contractor.

The contractor shall comply with the minimum supervisor to worker ratio stated below, required to ensure the effective supervision of the labour-enhanced works for all LI activities undertaken on this project:

Minimum supervisor to worker ratio = 1:10

E2.4 Contract of employment with persons employed under the Expanded Public Works Programme (EPWP)

The Contractor shall enter into a formal contract of employment with each person employed under the Expanded Public Works Programme (EPWP), using the pro forma contract of employment attached at the end of this Part E of section 3.3 Particular Specifications.

The Contractor shall note that all such formal contracts of employment entered into with persons employed under the Expanded Public Works Programme (EPWP) shall expire on 31 March each year, and the Contractor shall therefore be required to enter into new contracts with such persons as of 1 April each year.

E2.5 Employment of targeted labour under the Expanded Public Works Programme (EPWP)

The Contractor shall be contractually obliged to:

- (a) brief EPWP workers on the conditions of employment;
- (b) enter into a formal contract of employment with each EPWP worker, which contract will form part of the Employment Agreement;
- (c) keep personnel files for all EPWP workers and make copies available to the Employer if and when requested; and
- (d) ensure that payments to EPWP workers are made in accordance with Government Notice No. R347.

The rate of pay for persons employed under the Expanded Public Works Programme (EPWP) shall be the gazetted rate:

- (i) per task (for task-rated workers); or
- (ii) per day (for time-rated workers).

During those periods when an EPWP worker is engaged in formal classroom training (other than in-service training), the rate of pay shall be equal to the minimum wage rate as set on an annual basis in the Ministerial Determination for the Expanded Public Works Programme.

Tasks set by the Contractor shall be such that:

- (a) the average EPWP worker completes 5 tasks per week in 40 hours or less; and
- (b) the weakest EPWP worker completes 5 tasks per week in 55 hours or less.

The Contractor shall revise the time taken to complete a task whenever it is established that the time taken per week to complete the tasks set does not fall within the limits indicated in (a) and (b) above.

E2.6 Training of persons employed under the Expanded Public Works Programme (EPWP)

The training of persons employed under the Expanded Public Works Programme (EPWP) is described in clause F4 below.

E2.7 Contractor's obligations towards persons employed under the Expanded Public Works Programme (EPWP)

Over and above implementing in accordance with Government Notice Nos. 129 and R347 the EPWP work to be undertaken on this contract, it shall be the responsibility of the Contractor to carry out the following functions with respect to the EPWP workers:

(a) ensure that all participants are covered by the Compensation for Occupational Injuries and Diseases Act, 1993, for as long as they are contracted to the Contractor, and pay in full to the Compensation Commissioner such amounts as are due in terms of the Act;

- (b) pay in full to the Unemployment Insurance Fund for all participants such UIF contribution amounts as are due in terms of the Unemployment Insurance Act, 2001, as amended, and the Unemployment Insurance Contributions Act, 2002, as amended, and provide proof of such UIF payments upon request;
- (c) ensure that all participants are paid their wages on time through the pre-agreed payment method as stipulated in the participant contract of employment;
- (d) implement health and safety procedures with respect to the participants, ensuring that the health and safety regulations are adhered to;
- (e) ensure that all participants receive induction on site safety prior to commencing with work on site;
- (f) provide all participants with the necessary protective clothing and equipment as required by law for the specific tasks in which the participants are involved, in addition to the branded overalls stipulated for EPWP workers;
- (g) provide safe on-site storage facilities for apparel and tools issued to the participants;
- (h) assist in the assessment of participants with regard to their competencies;
- (i) provide overall supervision and day-to-day management of participants; and
- (j) implement strict quality control to ensure that the work carried out by the participants is of the required standard, and, where necessary, to train and mentor the participants to assist them in achieving the standards required.

E2.8 Apparel and tools for persons employed under the Expanded Public Works Programme (EPWP)

The Contractor shall provide Personal Protective Equipment (PPE) to all EPWP workers in accordance with the requirements arising from Part D: OHSA 1993 Health and Safety Specification and the Contractor's site-specific health and safety plan and accompanying risk assessments.

Where indicated below, certain items of the PPE issued by the Contractor to the EPWP workers shall include branded EPWP markings in accordance with the attached branding requirements.

PPE shall comprise the following:

- (a) Compulsory PPE issued to all EPWP workers for use during general work activities:
 - (i) Protective overalls (two sets), green in colour, with EPWP branding;
 - (ii) Lime green reflective safety vest with EPWP branding;
 - (iii) Protective footwear; and
 - (iv) Protective gloves.
- (b) PPE issued to EPWP workers for specific activities where required in terms of the Contractor's sitespecific health and safety plan and accompanying risk assessments, such as:
 - (i) Protective headwear, green in colour, with EPWP branding;
 - (ii) Protective eyewear such as spectacles and goggles;
 - (iii) Protective face shields;
 - (iv) Protective earplugs and earmuffs;
 - (v) Respiratory masks;
 - (vi) Disposable safety apparel;
 - (vii) Kidney belts;
 - (viii) Safety harnesses; and
 - (ix) Any other protective equipment identified.

The Contractor shall replace any item of issued PPE that becomes unserviceable.

The Contractor shall not charge any fee to the EPWP workers for the prescribed PPE issued except under the following circumstances:

- (i) where the employee requests the issue of additional PPE in excess of what is prescribed;
- (ii) where the employee has patently abused or neglected the issued PPE leading to early failure; or
- (iii) where the employee has lost the issued PPE.

The Contractor shall instruct and train the EPWP workers in the use of all PPE issued, and shall ensure that they use the prescribed equipment.

EPWP workers shall not have the right to refuse to use or wear the equipment prescribed by the Contractor. If it is not possible for an EPWP worker, through health or any other reason, to use or wear the prescribed PPE issued, such employee shall not be allowed to continue working under the hazardous conditions for which the equipment was prescribed. Under such circumstances an alternative solution shall be found, and this may include relocating or discharging the employee.

The Contractor shall provide each EPWP worker with hand tools of adequate quality and of the type required to carry out the assigned tasks safely and efficiently.

The Contractor shall instruct and train the EPWP workers in the safe and efficient use of all hand tools issued.

The Contractor shall maintain the issued tools in a serviceable and safe working condition.

The EPWP workers shall be responsible for the safe on-site storage of all PPE and tools issued to them, using the storage facilities provided on site by the Contractor.

No separate payment shall be made for providing the EPWP workers with PPE, or for providing relevant items of PPE in the specified colours with branded EPWP markings. Furthermore, no separate payment shall be made for providing the EPWP workers with hand tools or for providing them with safe storage facilities on site for PPE and tools. The Contractor shall therefore make provision for all costs related to providing the PPE, tools and safe storage facilities in the tendered rates and prices for the various items of work scheduled throughout the bill of quantities.

E2.9 EPWP contract signboard

The Contractor will be required to erect a contract signboard displaying the EPWP logo, indicating that this project is part of the Expanded Public Works Programme (EPWP). Provision for the costs related to the provision, erection and subsequent removal of the contract signboard is made in pay item provided in chapter 1.3 of the bill of quantities for this purpose.

E2.10 Payment matters relating to the EPWP work

E2.10.1 General

No separate pay items shall be provided in terms of Part E of the bill of quantities for the construction work activities carried out by EPWP participants. Payment for such work activities shall be made only indirectly, in terms of the pay items scheduled for the work activities in which such persons are engaged.

Furthermore, no direct payment will be made to cover the Contractor's costs associated with implementing the on-site work programme for the EPWP participants, for planning, organising, directing, controlling and administrating their day to day activities, including the setting of daily tasks, record keeping and any on-site liaison, training and mentoring required, and for the associated job creation reporting, and such costs shall therefore be built into the rates tendered for the various items of work scheduled throughout the bill of quantities.

E2.10.2 Payment for labour-enhanced components of the work

Payment will be made for items which are designated for labour-enhanced construction in the bill of quantities only in those instances where such items are constructed using labour-enhanced methods.

Any unauthorised use of construction equipment to carry out work which was scheduled to be carried out using labour-enhanced methods will not be condoned and any Works so constructed will not be certified for payment. Any non-payment for such Works shall not relieve the Contractor in any way from his obligations either in contract or in delict.

During the course of construction, as a result of unforeseen site conditions or operating conditions encountered, it may happen that an item designated for labour-enhanced construction can no longer be carried out in a safe and economically feasible manner, either in full or in part, using labour-enhanced methods. In such instances the Employer's Agent shall, where necessary, order a variation in terms of clause 6.3 of the of the General Conditions of Contract 2015 with respect to that portion of the item quantity that cannot be carried out using labour-enhanced methods.

E2.11 Penalty applicable to any shortfall in the local labour content achieved

The amount spent on wages for local labour (excluding VAT) for this project, as certified by the Employer's Agent, shall equal or exceed the specified minimum percentage of the contract amount which is the Contract Price (adjusted to exclude penalties and value added tax).

The Contractor is obliged to commit to or exceed the specified minimum percentage of local labour content stated in section C1.2.2 Data Provided by the Employer.

In the event that the Contractor fails to substantiate that any failure to achieve the minimum required local labour content for this project is due to quantitative underruns, the elimination of items contracted to local labour, or any other reason beyond the Contractor's control which may be acceptable to the Employer, the Contractor shall be liable for a financial penalty as prescribed in clause SCC 4.1.1 of section C1.2.1.2 Special Conditions of Contract. The financial penalty shall be calculated as follows:

 $P = 0.05 x [(E - E_0)/100] x C_A$

where:

- E is the specified minimum percentage for local labour content
- E_{\circ} is the local labour content percentage which the Employer's Agent certifies as being achieved upon completion of the contract
- C_A is the contract amount which is the Contract Price (adjusted to exclude penalties and value added tax)
- P is the monetary value of penalty payable

The penalty shall not apply to shortfalls in the allocations to the individual target groups (i.e., Women/Youth/Disabled as per clause F1.3 above), only to shortfalls in the total local labour content achieved.

The evaluation of the Contractor's achievement of the local labour content percentage shall be undertaken monthly by the Employer's Agent, based on the accumulative achievements in comparison to the programmed utilisation of local labour, as a means of monitoring the Contractor's performance in achieving the Contract Participation Goal.

Failure by the Contractor to achieve the Contract Participation Goal target by the time of Practical Completion, shall result in the financial penalty being applied as prescribed in this clause. The Employer's Agent shall make a final determination of the Contractor's achievement of the Contract Participation Goal based on the value of the Final Payment Certificate.

E3. NATIONAL YOUTH SERVICE (NYS)

The Employer requires the implementation of National Youth Service (NYS) programmes on this project.

E3.1 The National Youth Service (NYS) programme

The National Youth Service (NYS) programme aims to train young people and provide them with practical work experience. The young people will be allocated tasks by the Contractor that will assist the Contractor with the execution of the contract.

E3.2 Applicable labour laws

The work to be undertaken on this contract by unskilled or semi-skilled workers under the National Youth Service (NYS) programme shall be implemented in accordance with the same Code of Good Practice and Ministerial Determination as described in clause E2.2 above for work to be undertaken under the Expanded Public Works Programme (EPWP).

E3.3 Employer's project manager

The Contractor shall be required to liaise closely with the Employer's project manager who is responsible for the recruitment and training of the NYS workers.

E3.4 Persons to be employed under the NYS programme

For purposes of this contract, the Contractor shall be required to employ 10 youths aged between 18 and 35 for a period of 6 months each under the NYS programme.

The Employer's project manager shall provide the Contractor with a list of the 10 youths to be employed and the training that each of these 10 youths have received to date, and only these 10 youths shall be employed by the Contractor under the NYS programme.

E3.5 Contract of employment with persons employed under the NYS programme

The Contractor shall enter into a formal contract of employment with each youth employed under the NYS programme, using the pro forma contract of employment attached at the end of this Part E of section 3.3 Particular Specifications.

E3.6 Employment of NYS workers

The Contractor will be contractually obliged to:

- (a) employ all participants on the list provided by the Employer's project manager;
- (b) brief NYS workers on the conditions of employment;
- (c) enter into a formal contract of employment with each NYS worker, which contract will form part of the Employment Agreement;
- (d) keep personnel files for all NYS workers and make copies available to the Employer's project manager if and when requested; and
- (e) ensure that payments to NYS workers are made in accordance with Government Notice No. R347.

During the period when they are engaged in formal classroom training (other than in-service training), the youths employed under the NYS programme shall be paid the minimum wage rate as set by the Department of Labour on an annual basis in the Ministerial Determination for the Expanded Public Works Programme, and should there be an upward adjustment in the rate the Contractor will be compensated accordingly. During the period when they are engaged in productive work activities required for elements of the Works, they shall be paid in terms of the wage rates stated in clause F2.5 above.

E3.7 Training of youth workers

All NYS workers will be placed on an extensive training programme that will include:

- (a) an induction into NYS and EPWP;
- (b) life skills training;
- (c) technical training focusing on a vocational skill to be used on the project (e.g. painting or carpentry); and
- (d) entrepreneurship and business skills training.

All training will be arranged by the Employer's project manager, with whom the Contractor will be required to work closely to schedule the training sessions so that the timing of the training is aligned with the Contractor's work schedule and his demand for workers with specific skills. The Employer's project manager will make full details of the training programme available to the Contractor.

A compulsory 10-day life skills training must be provided before commencement of classroom training on NYS. This type of training must be provided by a NYDA accredited service provider as per the National Youth Service Framework from the National Department of Public Works.

The Contractor shall maintain comprehensive records of the training received by each NYS worker throughout the course of the contract, and shall submit to the Employer at each monthly site meeting a summary of the accumulated training received by each NYS worker.

The training of the NYS workers shall take place using the same training facility provided for the training of all other EPWP participants (refer to clause E5 below).

E3.8 Contractor's obligations towards persons employed under the NYS programme

Over and above implementing in accordance with Government Notice Nos. 129 and R347 the NYS programme work to be undertaken on this contract, it shall be the responsibility of the Contractor to carry out the following functions with respect to the NYS programme workers:

- (a) ensure that all participants are covered by the Compensation for Occupational Injuries and Diseases Act, 1993, for as long as they are contracted to the Contractor, and pay in full to the Compensation Commissioner such amounts as are due in terms of the Act;
- (b) pay in full to the Unemployment Insurance Fund for all participants such UIF contribution amounts as are due in terms of the Unemployment Insurance Act, 2001, as amended, and the Unemployment Insurance Contributions Act, 2002, as amended, and provide proof of such UIF payments upon request;
- (c) ensure that all participants are paid their wages on time through the pre-agreed payment method as stipulated in the participant contract;
- (d) implement health and safety procedures with respect to the participants, ensuring that the health and safety regulations are adhered to;
- (e) ensure that all participants receive induction on site safety prior to commencing with work on site;
- (f) provide all participants with the necessary protective clothing and equipment as required by law for the specific trades in which the participants are involved, in addition to the branded overalls stipulated for NYS workers;
- (g) provide safe on-site storage facilities for apparel and tools issued to the participants;
- (h) assist in the assessment of participants with regard to their competencies in their respective trades;
- (i) provide overall supervision and day-to-day management of participants; and
- (j) implement strict quality control to ensure that the work carried out by the participants is of the required standard, and, where necessary, to train and mentor the participants to assist them in achieving the standards required.

E3.9 Apparel and tools for NYS workers

The content of clause E2.8 above with regard to apparel and tools for EPWP workers shall apply equally to NYS workers, except that:

- (a) apparel and tools to be issued to NYS workers shall be determined in conjunction with the Employer's project manager;
- (b) the required branding of apparel to be issued to NYS workers shall be determined in conjunction with the Employer's project manager, and shall also include the NYS logo;
- (c) additional PPE may be required depending on the NYS worker's specific trade;
- (d) certain specified apparel and tools issued to the NYS workers will become the property of the NYS workers after the completion of their cycle of work on the project, in order to enable them to continue to practise their trade on future projects. Such apparel and tools shall be specified and authorised by the Employer's Agent; and
- (e) separate payment items have been provided in Part E of the bill of quantities to cover all costs associated with the provision of the necessary tools and apparel, including safety apparel, for the NYS workers, and the facilities for the safe storage thereof, all as authorised by the Employer's Agent.

E3.10 EPWP-NYS contract signboard

Where work takes place under the National Youth Service (NYS) programme, the NYS logo shall also be displayed on the EPWP contract signboard referred to in clause F2.9 above, indicating that this project is part of both the Expanded Public Works Programme (EPWP) and the NYS programme. Provision for the costs related to the provision, erection and subsequent removal of the contract signboard in the pay item provided in chapter 1.3 of the bill of quantities for this purpose.

E3.11 Payment matters relating to the NYS work

No direct payment will be made to cover the Contractor's costs associated with implementing the on-site work programme for the NYS workers, for planning, organising, directing, controlling and administrating their day to day activities, including the setting of daily tasks, record keeping and any on-site liaison, training and mentoring required, and for the associated job creation reporting, and such costs shall therefore be built into the rates tendered for the various items of work scheduled throughout the bill of quantities.

E4. JOB CREATION REPORTING FOR EPWP

In order to assist the Employer in complying with the goal of creating EPWP job opportunities, the Contractor must provide the information specified in clause E4.1 below for reporting purposes.

In addition, the Contractor's payment certificates shall be accompanied by the information specified in clause E4.2 below.

E4.1 Type of project data required per project

Every EPWP project shall collect and keep specific project data for the purpose of EPWP progress reporting on a monthly basis, using the EPWP Data Collection Tool template (this will be made available to the Contractor in Microsoft Excel format - refer to the pro forma spreadsheets at the end of this Part E of the Particular Specifications).

The data that is required to be kept, maintained and reported on a monthly basis for each project includes:

E4.1.1 Participant (local labour) data

A participant list of the local labour employed must be maintained for every EPWP project. The data required in this participant list is indicated below. This data shall be recorded, checked and signed off by the Contractor, and shall be submitted to the Employer at each monthly site meeting. The participant list shall contain the following data and shall be kept and maintained on site for audit purposes:

- (a) Participant identity name, surname, initials, date of birth and identity number (or other unique identifier) plus certified copy of ID book.
- (b) Participant profiles nationality, gender, age, education level and disability status.
- (c) Work data for participants daily wage to be received, number of calendar days training attended and number of calendar days worked.
- (d) Records of training as required in terms of the EPWP Data Collection Tool template.

In addition, the signed contracts of employment between the Contractor and each EPWP participant shall be kept and maintained on site for audit purposes.

E4.1.2 Project work data

The project work data generally seeks to confirm the number of people at work daily on the project. This data shall be recorded, checked and signed off by the Contractor, and shall be submitted to the Employer at each monthly site meeting. The data shall be maintained on site by the Contractor, in order that it can be provided by the Employer to the National Department of Public Works upon request when the latter is undertaking sample auditing. These records shall be kept by the Contractor for a period of three years after contract completion should they be required for audit purposes.

The data shall include:

- (a) Daily attendance register register for each day showing all the workers that were registered as being at work on that day. Attendance registers shall be completed on site on a daily basis and signed off by the Contractor on a weekly basis. Refer to pro forma attendance register attached at the end of this Part E of section 3.3.
- (b) Summary of monthly attendance.

E4.1.3 Project payment data

The project payment data generally seeks to confirm what was paid, for how much work and to whom. This data shall be recorded, checked and signed off by the Contractor, and shall be submitted to the Employer at each monthly site meeting.

It is required that the Contractor adopt one of the following methods as standard procedure for recording and maintaining this information:

- (a) Payment register this is a list of the workers showing the wages paid to each worker, and signed off by each worker as proof of receipt and acceptance of payment. Information on this register must include the name of the worker, either an identity number or other unique identifier, the number of calendar days that the pay period covers, the wage rate and the total wages paid; or
- (b) Bank records showing the transfers to each worker account, signed off by the Contractor as proof of payment these bank records must specifically show the name of the worker, either an identity number or other unique identifier, the period which the pay covers and the total wages paid.

The project payment data, as recorded and maintained by the Contractor in terms of either (a) or (b) above, must be available and applicable for the entire period for which the Employer claims an incentive reward for person-days of work created in terms of the project.

E4.1.4 Employment output data

The Contractor shall submit to the Employer at each monthly site meeting a progress report detailing production output compared to the programme of works, together with the data necessary to enable the Employer to calculate the following employment output data in accordance with the EPWP Data Collection Tool template:

- (a) Number of work opportunities created (where <u>one</u> work opportunity = paid work created for <u>one</u> individual on an EPWP project, for <u>any</u> period of time).
- (b) Number of person-days of work created (where <u>one</u> person-day = <u>one</u> day of work carried out by <u>one</u> individual). The total number of person-days of work created on a particular EPWP project shall be obtained by summing the total number of person-days worked by each individual employed during the course of that EPWP project.
- (c) Number of Full Time Equivalents (FTE) created (= total number of person-days of work created on the EPWP project divided by 230 working days). In terms of EPWP policy, <u>one</u> year of work created for <u>one</u> individual is assumed to comprise a total of 230 days of paid work carried out by that individual.
- (d) Average duration of work opportunities created (= total number of person-days of work created on the EPWP project divided by the number of work opportunities created on that EPWP project).
- (e) Average daily wage rates paid (= accumulated total of the wages paid to all individuals employed on an EPWP project divided by the total number of person-days of work created on that EPWP project).
- (f) Training information.

E4.2 Project data to be submitted with the Contractor's payment certificates

The Contractor's payment certificates shall be accompanied by labour returns providing the labour information for the corresponding period in a format specified by the Employer.

Should the Contractor choose to delay submitting payment certificates, the labour returns shall nevertheless still be submitted as per the frequency and timeframes stipulated by the Employer. The Contractor's payment certificates shall not be paid by the Employer until all pending labour information has been submitted.

The following information shall be maintained on site and submitted with each payment certificate in the format specified by the Employer:

- (a) Copies of the signed contracts between the Contractor and any new EPWP participants (the Contractor shall note that all such formal contracts of employment entered into with persons employed under the Expanded Public Works Programme (EPWP) shall expire on 31 March each year, and the Contractor shall therefore be required to enter into new contracts with such persons as of 1 April each year, and shall be required to submit copies of all such new contracts with the first payment certificate thereafter);
- (b) Certified ID copies of all local labour employed as EPWP participants;
- (c) Attendance registers for the EPWP participants;
- (d) Proof of payment of EPWP participants; and
- (e) Information as required in terms of the EPWP Data Collection Tool template.

E5. PROVISION OF STRUCTURED TRAINING

E5.1 Scope of structured training

In order to avoid duplication of training facilities, the training described in Part F: Small Contractor Development (in those instances where Part F is included in the contract), shall be provided utilising the training facility measured and paid for in accordance with the requirements of this Part E: Expanded Public Works Programme (EPWP).

The Employer's objectives include the training of local labour and Targeted Enterprises within a structured programme, in order to equip them with skills that will assist them in gaining future employment, and to facilitate targeted EPWP participants in gaining competencies and unit standard credits towards future full learnership qualifications.

Such training shall contain both theoretical and practical components and shall be conducted in accordance with the various laws and regulations contained in the South African Qualifications Authority (SAQA) statutes.

The following aspects of the structured training to be provided are noted:

- (a) The Employer has no service agreement or memorandum of understanding with any Education and Training Quality Assurance (ETQA) body, and therefore does not function as the employer as defined under any three-party learnership agreement between the learner, the training provider and the employer.
- (b) The structured training programmes implemented on this contract, although comprising several unit standards, are unlikely to total to sufficient credits for a full learnership qualification. Nevertheless, the competencies and credits achieved should contribute to a full learnership through the later acquisition by the learner of the remaining unit standards required for the full learnership.

The Contractor shall be required to provide a training facility on the Site, or in close proximity thereto, and to provide over the duration of the contract the following structured training for EPWP participants:

- (a) Generic skills training;
- (b) Entrepreneurial skills training;
- (c) Construction skills training; and
- (d) In-service training.

Generic skills training and in-service training shall be provided to all EPWP participants.

Entrepreneurial and construction skills training shall be provided to targeted EPWP participants only.

E5.2 Training provider and trainers

The Contractor shall be required to procure the services of a training provider accredited by the Construction Education and Training Authority (CETA).

The training provider shall have in its employ trainers who are registered as assessors with the Construction Education and Training Authority (CETA), and who shall deliver the training.

Proof of the accreditation of the service provider and the registration of the trainers by the CETA shall be submitted to the Employer's Agent. Such accreditation and registration shall be current and valid, and the proof submitted shall include the NQF levels and unit standards for which each trainer is accredited.

E5.3 Skills analysis and selection of targeted EPWP participants

Studying for any learnership requires minimum literacy and numeracy competencies as defined by SAQA. The actual literacy and numeracy levels of the persons employed on the Site shall provide a basis to guide the Contractor and the training provider on how to conduct the selection process.

The Contractor shall therefore conduct a skills analysis of the local labour and Targeted Enterprises employed, in order to determine the formal education qualifications of each employee.

The Contractor, in conjunction with the training provider, shall then identify those persons that display the potential to benefit from such structured entrepreneurial and construction skills training as may be provided for in the contract, and shall make recommendations in this regard to the Employer's Agent.

The final candidates selected for such training shall be decided between the Contractor and the Employer's Agent (or by the Project Management Team (PMT) in the case of training for Targeted Enterprises in terms of Part F: Small Contractor Development, where applicable).

E5.4 Structured training programmes

The Contractor, supported by the training provider, shall plan then implement structured training programmes for generic, entrepreneurial and construction skills training.

Training courses shall commence within four months of the Contractor taking possession of the Site, and shall be completed before the Due Completion Date.

All training shall take place within normal working hours, or as otherwise agreed with the learners.

The training provider shall design, compile and deliver the structured training programmes, based on the information obtained from the skills analysis.

E5.4.1 Generic skills training

The structured training programmes designed by the training provider for the generic skills training shall comprise relevant general courses such as basic hygiene and HIV/AIDS awareness, first aid, road safety, managing personal finance, and other courses that would be useful to workers in the road construction industry or as life skills generally.

E5.4.2 Entrepreneurial skills training

The structured training programmes designed by the training provider for the entrepreneurial skills training shall comprise unit standards that contribute towards one or more of the following full learnership qualifications, as appropriate taking into consideration the skills analysis information for the selected candidates (details of the learnership qualifications and the applicable unit standards may be found on the website <u>www.saqa.org.za</u>):

Г

| ENTREPRENEURIAL SKILLS TRAINING | | | | | | |
|--|-------|--------------|--------------------|---|--|--|
| Qualification title SAQA Qualification ID | | NQF level | Minimum credits | Purpose of qualification | | |
| National Certificate: Supervision of Construction Processes | 49053 | Level 4 | 176 | Learners found competent against this qualification will be able to execute the supervision of construction processes, with specialisation in a specific context | | |

E5.4.3 Construction skills training

The structured training programmes designed by the training provider for the construction skills training shall comprise unit standards that contribute towards one or more of the following full learnership qualifications, as appropriate taking into consideration the skills analysis information for the selected candidates (details of the learnership qualifications and the applicable unit standards may be found on the website <u>www.saqa.org.za</u>):

| CONSTRUCTION SKILLS TRAINING | | | | | |
|--|-----------------------------|--------------|--------------------|---|--|
| Qualification title | SAQA qualification ID | NQF level | Minimum credits | Purpose of qualification | |
| National Certificate: Supervision of Construction Processes | 49053 | Level 4 | 176 | Learners found competent against this qualification will be able to execute the supervision of construction processes, with specialisation in a specific context | |
| National Certificate: Construction: Roadworks | 24173 | Level 3 | 155 | This qualification is for persons who work or intend to work within a construction context on a site, and who seek recognition for essential skills in construction operations in roadworks. | |
| National Certificate: Construction: Roadworks | 24133 | Level 2 | 120 | This qualification is for persons who work or intend to work within a construction context on a site, and who seek recognition for essential skills in construction operations in roadworks. | |
| National Certificate: Occupational Health, Safety and Environment | 74269 | Level 2 | 120 | This qualification is to equip learners working in any type of workplace with a broad understanding and knowledge of Occupational Health, Safety and Environmental (HSE) concepts and practices with sufficient detail to enable them to function in a safe and healthy way and to deal with health and safety problems and issues. | |

E5.4.4 Training programme

The Contractor's proposed training programmes shall be subject to the approval of the Employer's Agent (or the approval of the Project Management Team (PMT) in the case of training for Targeted Enterprises in terms of Part F: Small Contractor Development, where applicable), and the Contractor shall, if so instructed by the Employer's Agent or the PMT, alter or amend the programmes and the course content to meet any additional needs identified.

The Contractor shall be responsible for everything necessary for the delivery of the training programmes, including:

- (a) the provision of the trainers;
- (b) the provision of a suitable secure venue, complete with adequate furniture, lighting, air conditioning, power and ablution facilities;
- (c) the provision of all necessary stationery, consumables and study materials;
- (d) the transportation of the learners to and from the training facility;
- the payment of wages to all learners during the classroom training at a rate equal to the minimum wage rate as set on an annual basis in the Ministerial Determination for the Expanded Public Works Programme;
- (f) the provision of any relevant Personal Protective Equipment (PPE) required for the training; and
- (g) additional supervision of the learners during the practical learning stage of the training carried out by constructing relevant elements of the Works (wages for the learners during this stage of the training will be paid through the rates tendered for the relevant scheduled work items for those elements).

At the successful completion of each course, the Contractor's training provider shall, as proof of attendance and completion, issue each learner with a certificate indicating the course content.

The training provider shall also ensure that each unit standard contributing towards a full learnership qualification and successfully completed by the learner is entered onto the national database.

The Contractor shall keep comprehensive records of the training given to each learner and the certificates issued, and shall provide copies of such records to the Employer's Agent when required.

The Contractor shall also complete and submit to the Employer's Agent each month, in a format acceptable to the Employer (using the EPWP Data Collection Tool template), a return detailing the training provided, both for the month and cumulatively for the contract.

E5.5 In-service training

The Contractor shall, from the commencement of the contract, implement an in-service training programme in which the various skills required for the execution and completion of the Works are imparted to the EPWP participants engaged thereon.

Throughout the duration of the contract, the EPWP participants shall be trained progressively through the various stages of each particular type of work in which they are engaged, and their work shall be supervised and monitored and their methods corrected where necessary.

The in-service training programme shall be submitted with the initial Works programme. The Contractor shall record the progress in relation to this programme on a monthly basis, and this progress report shall be incorporated in the monthly site meeting minutes and the payment certificate.

The Contractor shall provide sufficient skilled and competent trainers to train all EPWP participants engaged on the contract in the various skills required to enable them to carry out the required construction activities.

The in-service training of EPWP participants shall take place before commencement of the relevant construction activity, and the Contractor shall take into account in his programme the lead time required for such training. All in-service training shall be deemed to be an element of the relevant construction activity.

All formal in-service training shall be documented in terms of the EPWP Data Collection Tool template, and shall be accompanied by an attendance register of the EPWP participants on the applicable days.

All EPWP participants shall be remunerated at their agreed wage rate in respect of the time spent undergoing in-service training. The cost of the Contractor's in-service training obligations shall be deemed to be covered by the sums and rates tendered for items B13.01(a), (b) and (c) in the bill of quantities.

On termination of their employment, the Contractor shall provide each EPWP participant engaged on the contract with a certificate of service on which the following information shall be recorded:

- (i) name of the Contractor;
- (ii) name of the project / contract;
- (iii) name of the employee;
- (iv) nature of the work satisfactorily executed by the EPWP participant and the time spent thereon;
- (v) nature and extent of training provided to the EPWP participant; and
- (vi) dates of service.

E5.6 Training venue facility

The training venue facility to be provided by the Contractor shall be constructed, furnished and fully serviced for the duration of the contract in accordance with Chapter 1.4 of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020.

In order to minimise the cost of transporting the learners for training, the facility shall be located in secure premises on the Site, or in close proximity thereto.

This facility shall be used to deliver all training, irrespective of whether it is delivered in terms of Part E or Part F of the Particular Specifications.

The facility shall accommodate a class of up to 25 learners and shall comprise the following:

| (a) | Lecture room (interior area) | = | 48 m ² |
|-----|---|---|-------------------|
| (b) | Ablutions (male) | = | 6 m ² |
| (c) | Ablutions (female) | = | 6 m ² |
| (d) | Chairs for learners (individual chairs, with backs) | = | 25 off |
| (e) | Desk area for 25 learners (500 mm width) | = | 12,5 m² |
| (f) | Chairs for trainers and management (individual chairs, with backs) | = | 5 off |
| (g) | Table area for trainers and management | = | 3 m ² |
| (ĥ) | 220/250 volt power points | = | 6 off |
| (i) | Double 80 watt fluorescent light fittings complete with ballast and tubes | = | 6 off |
| (j) | Single incandescent light fittings complete with 100 watt globes | = | 4 off |
| (k) | Wash hand basins complete with taps and drains | = | 4 off |
| (I) | Fire extinguishers, 9,0 kg, all-purpose dry powder type, complete, | | |
| () | mounted on wall with brackets | = | 2 off |
| (m) | Air conditioning units with 2,2 kW minimum capacity, mounted and | | |
| () | with own power connection | = | 4 off |
| (n) | Voltage stabilizers | = | 2 off |
| (o) | Floodlights complete with poles and 500 watt minimum globes and | | |
| (0) | controlled by photocells | = | 2 off |
| (p) | White boards (3 m x 1,5 m) | _ | 1 off |
| | Venetian blinds | _ | 12 m ² |
| (q) | | = | 12 111- |

E6. MEASUREMENT AND PAYMENT

Item

Unit

E6.01 Provision of the training venue facility, including the cost of transporting the learners to and from this facility.....lump sum (Sum)

The tendered lump sum for subitem E6.01 shall include full compensation for the provision of the training venue facility complete and serviced as specified, including for the provision of power, water, sewerage and cleaning services for the duration of the contract, for lighting, power points and voltage stabilizers, for air conditioning, blinds, fire extinguishers, floodlights, furniture and whiteboards, for the provision of security at the facility, for all other costs necessary to maintain the facility for the duration of the contract, and for the removal of the facility on completion of the contract.

The tendered lump sum shall also include full compensation for transporting the learners on each day of training from their place of work to this training venue facility, and back again after the training for the day has been delivered by the accredited trainers.

Payment of the lump sum shall be made in three instalments as follows:

The first instalment, 50% of the lump sum, shall be paid after the Contractor has met all his obligations regarding the provision of the training venue facility, complete and serviced as specified, and the facility has been successfully commissioned for use.

The second instalment, 35% of the lump sum, shall be paid when 75% of the training courses proposed in accordance with the Contractor's approved structured training programme have been delivered to the learners by the accredited trainers.

The third and final instalment, 15% of the lump sum, shall be paid when all training has been concluded and the facility has been dismantled and removed from the site.

ltem

E6.02 Training of learners employed by the contractor or by the Targeted Enterprise subcontractors: Generic skills: (a) (i) Training costs provisional sum (Prov sum) (ii) Handling costs and profit in respect of subitem F6.02(a)(i) percentage (%) (b) Entrepreneurial skills: (i) Training costs provisional sum (Prov sum) (ii) Handling costs and profit in respect of subitem F6.02(b)(i) percentage (%) (c) Construction skills: Training costs provisional sum (Prov sum) (i) Handling costs and profit in respect of subitem F6.02(c)(i)percentage (%) (ii) Transportation and accommodation costs of selected (d) learners only, while receiving off-site training: Transportation and accommodation costs provisional sum (Prov sum) (i) (ii) Handling costs and profit in respect of subitem F6.02(d)(i) percentage (%)

Item

Expenditure under subitems E6.02(a)(i), (b)(i), (c)(i) and (d)(i) shall be in accordance with clause 6.6 of the General Conditions of Contract 2015.

The provisional sum for each of subitems E6.02(a)(i), (b)(i) and (c)(i) is provided to cover the total costs of the required training in generic, entrepreneurial and construction skills respectively, including for the procurement of the services of the accredited trainers and their delivery of the training courses to the learners, the provision of all training materials including all stationery and study materials, the wages of the learners for the duration of the courses including the associated COIDA and UIF payments, and the provision of any tools and PPE that may be required during those courses incorporating practical training modules. The payment of wages to learners in terms of subitems E6.02(a)(i), (b)(i) and (c)(i) will only be made to those learners who attend and successfully complete each course of the approved training programme. Payment shall not be made to learners who, once selected, do not attend or only partially complete structured training courses.

The tendered percentage for each of subitems E6.02(a)(ii), (b)(ii) and (c)(ii) is the percentage of the amount actually spent under each of subitems E6.02(a)(i), (b)(i) and (c)(i) respectively, and shall include full compensation for the handling costs of the Contractor and the profit in connection with the provision of the training in generic, entrepreneurial and construction skills respectively, including for the costs of record keeping and reporting with respect to the training received by each learner.

The provisional sum for subitem E6.02(d)(i) is provided to cover all costs related to the transportation and accommodation costs of selected learners only, while receiving off-site training, where such learners have been specifically selected to receive such off-site training and where such training cannot be delivered using the training venue facility provided by the Contractor in terms of subitem E6.01.

The tendered percentage for subitem E6.02(d)(ii) is the percentage of the amount actually spent under subitem E6.02(d)(i), and shall include full compensation for the handling costs of the Contractor and the profit in connection with the transportation and accommodation costs of selected learners only, while receiving off-site training.

| E6.03 | Payments associated with the NYS programme: |
|-------|--|
| (a) | Employment of NYS workers provisional sum (Prov sum) |
| (b) | Provision of tools and apparel for the NYS workers provisional sum (Prov sum) |
| (c) | Handling costs and profit in respect of subitems F6.03(a) and (b) percentage (%) |
| (d) | Training of NYS workers: |
| (i) | Provision of training for NYS workers provisional sum (Prov sum) |
| (ii) | Handling costs and profit in respect of subitem F6.03(d)(i) percentage (%) |
| (e) | Liaison with the Employer's project manager and the training service provider: |
| (i) | Liaison conducted by the Construction Manager hour (h) |
| (ii) | Liaison conducted by the senior site foreman hour (h) |

The provisional sums provided under subitems E6.03(a) and (b) shall be expended in accordance with clause 6.6 of the General Conditions of Contract 2015.

The provisional sum under subitem E6.03(a) shall be used to cover the cost of employment payments made by the Contractor to the NYS workers, including the associated COIDA and UIF payments, all as authorised by the Employer's Agent.

Unit

The provisional sum under subitem E6.03(b) shall be used to cover all costs associated with the provision of the necessary tools and apparel, including safety apparel, for the NYS workers, and the facilities for the safe storage thereof, all as authorised by the Employer's Agent.

The tendered percentage under subitem E6.03(c) is a percentage of the total amount of expenditure approved by the Employer's Agent under the provisional sum subitems E6.03(a) and (b), and shall include full compensation for attendance by the Contractor, for the handling costs of the Contractor, and for the profit in connection with payments made by the Contractor with respect to the NYS programme implementation.

The provisional sum provided under subitem E6.03(d)(i) shall be expended in accordance with clause 6.6 of the General Conditions of Contract 2015.

The provisional sum under subitem E6.03(d)(i) shall be used to cover all costs associated with the provision of training for the NYS workers, including the cost of procuring the services of the accredited trainers and their delivery of the training courses to the NYS workers, and the provision of all training materials including all stationery and study materials.

The tendered percentage under subitem E6.03(d)(ii) is a percentage of the total amount of expenditure approved by the Employer's Agent under the provisional sum subitem E6.03(d)(i), and shall include full compensation for attendance by the Contractor, for the handling costs of the Contractor, and for the profit in connection with payments made by the Contractor with respect to the provision of training for the NYS workers, including for the costs of record keeping and reporting with respect to the training received by each NYS worker.

The unit of measurement for subitems E6.03(e)(i) and (ii) shall be the hour. The tendered rates shall include full compensation for all costs related to the Construction Manager and the senior site foreman respectively for time spent at formal liaison meetings authorised and convened by the Employer's Agent for the specific purpose of liaising with the Employer's project manager and / or the training service provider. The payment shall be made only for the time spent in the formal meeting itself. No payment shall be made for time spent during any other on-site liaison, telephonic liaison, e-mail or written correspondence liaison between these parties, or for liaison conducted with the Employer's project manager and / or the training service provider by any other member of the Contractor's site staff or head office personnel, the cost of all of which shall be deemed to be included in the Contractor's time-related obligations under subitem C1.3.1.3

Expanded Public Works Programme:

PPE BRANDING

For EPWP Projects



T-Shirt/Overall/Safety Vest Branding




Logo Options

Implementing Agent Examples EPWP LOGO National Projects public works transport Department Transport Har PLIBLIC OF 3K EXPANDED PUBLIC WORKS PROGRAMME vironmental affairs Contains National Coat Of Arms and nam mental Affairs Provincial Department Projects The Logo shall not be disproportionately stretched. A monochrome black logo may be used on approval only. transport The above logo is the current logo. Logos with green text below the words EXPANDED PUBLIC WORKS PROGRAMME are old logos and should **Contains Provincial Coat** Of Arms and name not be utilised. **Municipal Projects** net PLEASE VERIFY WHICH LOGO NEEDS TO USED

Printing on PPE

PPE (Overalls) shall be Pantone Green with/without reflective tape and shall be branded as follows:

- Implementer's Logo (printed or embroidered) on the left front pocket location ie over the heart position. (full colour)
- EPWP logo on the right front pocket (printed or embroidered) location (full colour)
- The letters EPWP on the back of the PPE in BLACK
- The program name eg Vuk'uphile is to be printed on the right sleeve of short sleeved apparel and need not be placed on long sleeved apparel.
- Where required, lime green safety vests are to be branded with similar specification above. In this instance the Overalls may not necessarily be branded provided that the use of high visibility vests is mandatory.
- All artwork and PPE samples shall be approved and signed off by the consultant prior to printing/embroidering.



For further information contact: Petronella Sithebe

Petronella.Sithebe@Kzntransport.gov.za

033-355-8023



PRO FORMA EPWP CONTRACT OF EMPLOYMENT





EXPANDED PUBLIC WORKS PROGRAMME

This contract must be read in conjunction with the standard terms and conditions of employment on EPWP attached herein.

EPWP CONTRACT OF EMPLOYMENT between

| Employer Details | | | | | | | | | | |
|------------------|----------------------------------|---------|-----------------------------------|--|--|--|--|--|--|--|
| Name | Click or tap here to enter text. | Address | Click or tap here to enter text. | | | | | | | |
| Telephone | Click or tap here to enter text. | | click of tup here to clicer text. | | | | | | | |
| Email | Click or tap here to enter text. | | | | | | | | | |
| Contact | Click or tap here to enter text. | | | | | | | | | |

And

Employee Details

| Name | Click or tap here to enter text. | Surname | Click or tap here to enter text. | | |
|-------------------------------------|----------------------------------|-----------------------|----------------------------------|--|--|
| ID: | Click or tap here to enter text. | Cell | Click or tap here to enter text. | | |
| Sex (M/F) | Male 🗆 Female 🗆 | Disability | Yes 🗆 No 🗆 | | |
| Primary Language | Click or tap here to enter text. | Physical | | | |
| Other Languages | Click or tap here to enter text. | Address | Click or tap here to enter text. | | |
| Highest Education Level Achieved | Click or tap here to enter text. | Local Municipality | Click or tap here to enter text. | | |
| Other qualifications | Click or tap here to enter text. | Ward | Click or tap here to enter text. | | |
| Grant Received (Y/N) | Yes 🗆 No 🗆 | Grant type: | | | |

Employment Details

| Name of project: | Click or tap here to enter text. | | | | | | | |
|---------------------------|---|----------------------------------|--|--|--|--|--|--|
| Job Title: | Click or tap here to enter text. | | | | | | | |
| Duties: | Click or tap here to enter text. | | | | | | | |
| Contract Start Date | Click or tap here to enter text. | Click or tap here to enter text. | | | | | | |
| The wage per task/day is: | R Click or tap here to enter text. / Hour/Day/task (Specifier to select correct rate) | | | | | | | |

Special Conditions

| You must be aware that this employment contract is a limited term contract and not a permanent job. This employment contract may be terminated for any one of the following reasons: a) The contractor does not get additional contracts from the EPWP. b) Funding for the programme in your area comes to an end. c) Underperformance: first offence – final written warning. Second offence – dismissal. | Payment a) You will be paid a fixed amount stipulated above for completing a fixed amount of work. b) The amount of work required for the agreed rate of pay will vary from task to task. You will be informed at the beginning of each task or group of tasks how much work you are expected to complete per day. c) You will only be paid for work completed. d) Payment during classroom training shall be R /day |
|---|--|
| Personal Protective Clothing will be supplied to the employee by the employee provided that the employee has worked for at least 3 months. | over depending on the work to be performed, and will remain the property of |
| | |

Acceptance

| Employer Name: | Employer Signature: | Employee Name: | Employee Signature: |
|-----------------|----------------------|-----------------|----------------------|
| Witness 1 Name: | Witness 1 Signature: | Witness 2 Name: | Witness 2 Signature: |

APPENDIX E – Conditions of Service

1. Introduction

1.1. This document contains the standard terms and conditions for workers employed in elementary occupations on an Expanded public Works Programme (EPWP). These terms and conditions do NOT apply to persons employed in the supervision and management of an EPWP. 1.2. In this document –

- a) "department" means any department of the State, implementing agent or contractor;
- b) "employer" means any department, implementing agency or contractor that hires workers to work in elementary occupations on an EPWP;
- c) "worker" means any person working in an elementary occupation on an EPWP;
- d) "elementary occupation" means any occupation involving unskilled or semi-skilled work;
- e) "management" means any person employed by a department or implementing agency to administer or execute an EPWP;
- f) "task" means a fixed quantity of work;
 g) "task-based work" means work in which a worker is paid a
- fixed rate for performing a task;
 h) "task-rated worker" means a worker paid on the basis of the number of tasks completed;
- i) "time-rated worker" means a worker paid on the basis of the length of time worked.

2. Terms of Work

- 2.1. Workers on an EPWP are employed on a temporary basis.
- 2.2. A worker may NOT be employed for longer than 24 months in any five-year cycle on an EPWP.
- 2.3. Employment on an EPWP does not qualify as employment as a contributor for the purposes of the Unemployment Insurance Act 30 of 1966.

3. Normal Hours of Work

- An employer may not set tasks or hours of work that require a 9.2. worker to work–
- a) more than forty hours in any week
- i. on more than five days in any week; and
- ii. for more than eight hours on any day.
- 3.2. An employer and worker may agree that a worker will work four days per week. The worker may then work up to ten hours per day.
- 3.3. A task-rated worker may not work more than a total of 55 hours in any week to complete the tasks allocated (based on a 40-hour week) to that worker.

4. Meal Breaks

- 4.1. A worker may not work for more than five hours without taking 9.8. a meal break of at least thirty minutes duration.
- 4.2. An employer and worker may agree on longer meal breaks.
- 4.3. A worker may not work during a meal break. However, an employer may require a worker to perform duties during a meal break if those duties cannot be left unattended and cannot be performed by another worker. An employer must take reasonable steps to ensure that a worker is relieved of his or her duties during the meal break.
- 4.4. A worker is not entitled to payment for the period of a meal break. However, a worker who is paid on the basis of time worked must be paid if the worker is required to work or to be available for work during the meal break.

5. Special Conditions for Security Guards

- 5.1. A security guard may work up to 55 hours per week and up to eleven hours per day.
- 5.2. A security guard who works more than ten hours per day must have a meal break of at least one hour or two breaks of at least 30 minutes each.

6. Daily Rest Period

Every worker is entitled to a daily rest period of at least eight consecutive hours. The daily rest period is measured from the time the worker ends work on one day until the time the worker starts work on the next day.

7. Weekly Rest Period

Every worker must have two days off every week. A worker may only work on their day off to perform work which must be done without delay and cannot be performed by workers during their ordinary hours of work ("emergency work").

8. Work on Sundays and Public Holidays

- 8.1. A worker may only work on a Sunday or public holiday to
- perform emergency or security work. 8.2. Work on Sundays is paid at the ordinary rate of pay.
- 8.3. A task-rated worker who works on a public holiday must be paid –
- a) the worker's daily task rate, if the worker works for less than four hours:
- b) double the worker's daily task rate, if the worker works for more than four hours.
- A time-rated worker who works on a public holiday must be paid –
- the worker's daily rate of pay, if the worker works for less than four hours on the public holiday;
- b) double the worker's daily rate of pay, if the worker works for more than four hours on the public holiday.

9. Sick Leave

- 9.1. Only workers who work four or more days per week have the right to claim sick-pay in terms of this clause.
 - A worker who is unable to work on account of illness or injury is entitled to claim one day's paid sick leave for every full month that the worker has worked in terms of a contract.
- 9.3. A worker may accumulate a maximum of twelve days' sick leave in a year.
- 9.4. Accumulated sick-leave may not be transferred from one contract to another contract.
- An employer must pay a task-rated worker the worker's daily task rate for a day's sick leave.
- 9.6. An employer must pay a time-rated worker the worker's daily rate of pay for a day's sick leave.
- An employer must pay a worker sick pay on the worker's usual payday.
 - Before paying sick-pay, an employer may require a worker to produce a certificate stating that the worker was unable to work on account of sickness or injury if the worker is –
- a) absent from work for more than two consecutive days; or
 b) absent from work on more than two occasions in any eight-
- week period.
 9.9. A medical certificate must be issued and signed by a medical
- .9. A medical certificate must be issued and signed by a medical practitioner, a qualified nurse or a clinic staff member authorised to issue medical certificates indicating the duration and reason for incapacity.
- 9.10. A worker is not entitled to paid sick-leave for a work-related injury or occupational disease for which the worker can claim compensation under the Compensation for Occupational Injuries and Diseases Act.



10. Maternity Leave

- 10.1. A worker may take up to four consecutive months' unpaid maternity leave.
- 10.2. A worker is not entitled to any payment or employment-related benefits during maternity leave.
- 10.3. A worker must give her employer reasonable notice of when she will start maternity leave and when she will return to work. 14.3.
- 10.4. A worker is not required to take the full period of maternity leave. However, a worker may not work for four weeks before the expected date of birth of her child or for six weeks after the birth of her child, unless a medical practitioner, midwife or qualified nurse certifies that she is fit to do so.
- 10.5. A worker may begin maternity leave –
 a) four weeks before the expected date of birth; or
- b) on an earlier date –
- if a medical practitioner, midwife or certified nurse certifies that it is necessary for the health of the worker or that of her unborn child; or
- ii. if agreed to between employer and worker; or
- iii. on a later date, if a medical practitioner, midwife or certified nurse has certified that the worker is able to continue to work without endangering her health.
- 10.6. A worker who has a miscarriage during the third trimester of pregnancy or bears a stillborn child may take maternity leave for up to six weeks after the miscarriage or stillbirth.
- 10.7. A worker who returns to work after maternity leave, has the right to start a new cycle of twenty-four months employment, unless the EPWP on which she was employed has ended.

11. Family responsibility leave

- 11.1. Workers, who work for at least four days per week, are entitled to three days paid family responsibility leave each year in the following circumstances
 - a) when the employee's child is born;
 - b) when the employee's child is sick;
 - c) in the event of a death of -
 - i. the employee's spouse or life partner;
 - ii. the employee's parent, adoptive parent, grandparent, child, adopted child, grandchild or sibling.

12. Statement of Conditions

- 12.1. An employer must give a worker a statement containing the following details at the start of employment
 - a) the employer's name and address and the name of the EPWP;
 - b) the tasks or job that the worker is to perform; and
 - c) the period for which the worker is hired or, if this is not certain, the expected duration of the contract;
 - the worker's rate of pay and how this is to be calculated;
- e) the training that the worker will receive during the EPWP
- 12.2. An employer must ensure that these terms are explained in a suitable language to any employee who is unable to read the statement.
- 12.3. An employer must supply each worker with a copy of these conditions of employment.

13. Keeping Records

- Every employer must keep a written record of at least the following –
 - a) the worker's name and position;
 - b) in the case of a task-rated worker, the number of tasks completed by the worker;
 - c) in the case of a time-rated worker, the time worked by the worker,
 - d) payments made to each worker.
 - 13.2. The employer must keep this record for a period of at least three years after the completion of the EPWP.

14. Payment

- 14.1. An employer must pay all wages at least monthly in cash or by cheque or into a bank account.
- A task-rated worker will only be paid for tasks that have been completed.
 - 1.3. An employer must pay a task-rated worker within five weeks of the work being completed and the work having been approved by the manager or the contractor having submitted an invoice to the employer.
- 14.4. A time-rated worker will be paid at the end of each month.
- 14.5. Payment must be made in cash, by cheque or by direct deposit into a bank account designated by the worker.
- 14.6. Payment in cash or by cheque must take place
 - a) at the workplace or at a place agreed to by the worker;
 b) during the worker's working hours or within fifteen minutes of the start or finish of work;
- c) in a sealed envelope which becomes the property of the worker.
- 14.7. An employer must give a worker the following information in writing
 - a) the period for which payment is made;
 - b) the numbers of tasks completed or hours worked;
 - c) the worker's earnings;
 - d) any money deducted from the payment;
 - e) the actual amount paid to the worker.
- 14.8. If the worker is paid in cash or by cheque, this information must be recorded on the envelope and the worker must acknowledge receipt of payment by signing for it
- 14.9. If a worker's employment is terminated, the employer must pay all monies owing to that worker within one month of the termination of employment.

15. Deductions

- 15.1. An employer may not deduct money from a worker's payment unless the deduction is required in terms of a law.
- 15.2. An employer must deduct and pay to the SA Revenue Services any income tax that the worker is required to pay.
- 15.3. An employer who deducts money from a worker's pay for payment to another person must pay the money to that person within the time period and other requirements specified in the agreement law, court order or arbitration award concerned.
- 15.4. An employer may not require or allow a worker to –
 a) repay any payment except an overpayment previously made by the employer by mistake;
 - b) state that the worker received a greater amount of money than the employer actually paid to the worker; or
 - c) pay the employer or any other person for having been employed.

16. Health and Safety

- 16.1. Employers must take all reasonable steps to ensure that the working environment is healthy and safe.
- 16.2. A worker must
 - a) work in a way that does not endanger his/her health and safety or that of any other person;
 - b) obey any health and safety instruction;
 - c) obey all health and safety rules of the EPWP;
 - use any personal protective equipment or clothing issued by the employer;
 - report any accident, near-miss incident or dangerous behaviour by another person to their employer or manager.

17. Compensation for Injuries and Diseases



- 17.1. It is the responsibility of the employers (other than a contractor) to arrange for all persons employed on an EPWP to be covered in terms of the Compensation for Occupational Injuries and Diseases Act, 130 of 1993.
- 17.2. A worker must report any work-related injury or occupational disease to their employer or manager.
- 17.3. The employer must report the accident or disease to the Compensation Commissioner.
- 17.4. An employer must pay a worker who is unable to work because of an injury caused by an accident at work 75% of their earnings for up to three months. The employer will be refunded this amount by the Compensation Commissioner. This does NOT apply to injuries caused by accidents outside the workplace such as road accidents or accidents at home.

18. Termination

- 18.1. The employer may terminate the employment of a worker for good cause after following a fair procedure.
- 18.2. A worker will not receive severance pay on termination.
- 18.3. A worker is not required to give notice to terminate employment. However, a worker who wishes to resign should advise the employer in advance to allow the employer to find a replacement.
- 18.4. A worker who is absent for more than three consecutive days without informing the employer of an intention to return to work will have terminated the contract. However, the worker may be re-engaged if a position becomes available for the balance of the 24-month period.
- 18.5. A worker who does not attend required training events, without good reason, will have terminated the contract. However, the worker may be re-engaged if a position becomes available for the balance of the 24-month period.

19. Certificate of Service

- On termination of employment, a worker is entitled to a certificate stating
 - a) the worker's full name;
 - b) the name and address of the employer,
 - c) the EPWP on which the worker worked;
 - d) the work performed by the worker;
 - e) any training received by the worker as part of the EPWP;
 - f) the period for which the worker worked on the EPWP;
 - g) any other information agreed on by the employer and worker. Either party can terminate this agreement with four weeks written notice. In the case where an employee is illiterate notice may be given by that employee verbally.

<u>EPWP DATA COLLECTION TOOL TEMPLATE</u> (PRO FORMAS OF MICROSOFT EXCEL SPREADSHEETS)

| Field requested | Description if pooled | Please complete the |
|--|---|---------------------|
| Field requested | Description if needed | sections in white |
| Profile ID | Project Details Generated by the system | |
| Project Name | The name of the project | |
| Project Reference Number | Contract number | |
| , | Full description of what is happening in the project | |
| Project description | (as per the appointment letter) and the community | |
| | benefiting from the project | |
| Project Start Date | Duration Planned Start date of the particular contract | |
| Project End Date | Planned End date of the particular contract | |
| • | Overall Contract budget (excluding professional | |
| Estimated Budget | fees) for Current Financial Year | |
| | Project Location | |
| Province | In which province is the project implemented? | KZN |
| District Municipality | Under which District Municipality does this project falls? | |
| Local Municipality | Under which Local Municipality does this project falls? | |
| _atitude (in decimal format) | Is generated by the system | |
| Longitude (in decimal format) | Is generated by the system | |
| | Project Location per site | |
| _ocality name | Where exactly is the project implemented? (Ward name) | |
| Subplace | Town / Village | |
| Ward | The project site is located in which ward? | |
| Government facility | Landmark near the project (Post | |
| Spatial Data Type | office/school/clinic/library) Geopoint (structure)/ Line (road)/ Polygon(area) | |
| Site physical address | Physical address of the site office | |
| | | |
| | Public Body Details In which sphere is the project implemented? | |
| Public body sphere | (National, Provincial or Municipal) | Provincial |
| Reporting public body that | Which Institution or Department that owns / | KZN Department of |
| s the project owner (and | approved this project (Education, Health, City of | Transport |
| will report on the project) Department in the Public | Tshwane Metro etc.) Which department /unit is responsible for this | - |
| body that is responsible for | project? (e.g. Roads & storm water, Education, | KZN Department of |
| he project | Community safety etc.) | Transport |
| mplementing public body | In which sphere is this project implemented? | Provincial |
| type Public body that will | (Metro,Distr,Mun, National or Provincial Dept.) | KZN Department of |
| mplement the project | Which institution that implements the project? | Transport |
| a this the project on the | Project Implementation | |
| s this the project on the municipal IDP | Yes / No | N/A |
| DP reference number allocated to the project | The number reflected in your Municipal IDP document | N/A |
| | EPWP Details | |
| | The project is implemented in which sector? | |
| EPWP Sector | (Infrastructure, Environment & culture, Non-state or Social) | Infrastructure |
| EPWP Programme | The project is implemented under which programme? | |
| | The project is implemented under which sub- | |

| | EPWP BUSINESS FORM | | | | | | | | | |
|---|--|---------------------------------------|--|--|--|--|--|--|--|--|
| Field requested | Description if needed | Please complete the sections in white | | | | | | | | |
| | Project Details | | | | | | | | | |
| Profile ID | Generated by the system | | | | | | | | | |
| Project Name | The name of the project | | | | | | | | | |
| Project Reference Number | Contract number | | | | | | | | | |
| Project description | Full description of what is happening in the project (as per the appointment letter) and the community benefiting from the project | | | | | | | | | |
| | Duration | | | | | | | | | |
| Project Start Date | | | | | | | | | | |
| Project End Date | | | | | | | | | | |
| Estimated Budget | Project Budget | | | | | | | | | |
| | Project Location | | | | | | | | | |
| Province | | KZN | | | | | | | | |
| District Municipality | Under which District Municipality does this projects falls | | | | | | | | | |
| Local Municipality | Under which Local Municipality does this projects falls | | | | | | | | | |
| Latitude (in decimal format) | GPS coordinates | | | | | | | | | |
| Longitude (in decimal format) | | | | | | | | | | |
| ionnat) | Public Body Details | | | | | | | | | |
| Public body | | | | | | | | | | |
| sphere | Such as Municipal or Provincial | Provincial | | | | | | | | |
| Reporting public body that is the project owner (and will report on the project) | Which Department approved the project in (education, Health etc.) | KZN Department of Transport | | | | | | | | |
| Department / Unit in the Public body that is responsible for the project | Which Department budgeted for the project e.g. Education, Health Directorate | KZN Department of Transport | | | | | | | | |
| Implementing public body type | Example(Local Municipality, Distr. Mun or Provincial Dept. | Provincial | | | | | | | | |
| Public body that will implement the project | Infrastructure, Environment or Social | KZN Department of Transport | | | | | | | | |
| Is this project on the Municipal IDP | Municipal projects | N/A | | | | | | | | |
| IDP reference number allocated to the project | | N/A | | | | | | | | |

| | EPWP Details | |
|--|--|-----------------------------|
| EPWP Sector | The project is implemented in which sector? (Infrastructure, Environment & culture, Non-state or Social) | Infrastructure |
| EPWP programme | The project is implemented under which programme? | |
| EPWP Sub Programme | The project is implemented under which sub- programme? | |
| y | Budget Amount-(Allocations for the | project duration) |
| Funding Body | Which Dept. is funding the project | KZN Department of Transport |
| Funding Year | Financial year/s for the project | · · · · · |
| Total Budget Amount | (Exclude Professional Fees) | |
| Incentive Grant(e.g. landcare / EPWP grant) | Grant funding received | |
| Total wages paid for the duration of the projects | What amount will be spent on wages during the duration of the project | |
| Wage Rate | Daily Wage rate to be paid during productive work | |
| Stipend Rate | Daily wage rate to be paid during training | |
| UIF | The amount being paid to UIF (if applicable) | |
| COIDA | The amount being paid to COIDA(if applicable) | |
| Training | What amount will be spent on training | |
| Administration | The Administration costs | |
| Equipment and materials | Budget for Materials and Equipment | |
| Other | If other where chosen describe the other Such as Professional fees) | |
| Describe other | | |
| | Project Outputs and Trai | ning |
| Planned Primary Output | eg walkways, gabions, kerb * channel, km of road constructed | |
| Description of Planned Primary Output | Describe the project output (end product and not the milestone) (e.g. kms of tar road constructed) Start with the unit of measure such as number of, kms, ha, sqms etc | |
| Unit of measure of primary output | Eg. m, m², m³, km, no, ha etc | |
| Planned primary output quantity | Specify the quanity of output planned | |
| Number of persons to be trained | How many persons are targeted for on job training | |

| | Contact person | |
|-----------------------|--|--|
| Title | | |
| Initials | | |
| First Name | | |
| Surname | | |
| Email | | |
| Tel (Office) | | |
| Fax Number | | |
| Cell Number | | |
| Physical | | |
| Address 1 | | |
| Physical | Dereen reenensible for the Dreiget in the Dublic Dedu | |
| Address 2 | Person responsible for the Project in the Public Body (Project Manager) | |
| Physical Address 3 | (Froject Manager) | |
| Physical | | |
| Address 4 | | |
| Postal | | |
| Address 1 | | |
| Postal | | |
| Address 2 | | |
| Postal | | |
| Address 3 Postal | | |
| Address 4 | | |
| Position of | | |
| person | | |

| Participant's personal details | | | | | | | Grants | Exp Lit | erience/ eracy | Locat Deta | tion ails | Nation- ality | Но | usehold [| Details | | | Quality C | heck | | | | | | |
|--------------------------------|-------------------------------------|----------|---------|-----------|------------------|--------------------|------------|------------|-------------------|---------------|--------------|---------------------------------------|---------------------|---------------------|--------------------------|-----------------------|-----------------------------------|-------------------------------------|---|--|---------------|------------|---|---------------------------------|-------------------------------|
| No | First Name as per ID document | Initials | Surname | ID number | Disability (Y/N) | Education Level | Start Date | End Date | Language ID | Address | Cell Number | Government Grant (Y/N) and Type | Other Language 1 | Other Language 2 | District Municipality | Local Municipality | Nationality (RSA/ Non- RSA) | Number of people in Household | Number of Dependants in Household | Number of Children attending school | Picture Clear | Text clear | Certification within 3 months of employment | Clear certification Stamp | Commissioner details clear |
| | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | ┝──┤ | |
| | - | | | | | | | | | | | | | | | | | | | | | | | ├───┤ | |
| | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | - | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | |
| | - | | | | | | | | | | | | | | | | | | | | | | | ──┤ | |
| | | | | | | | | | | | | | | | | | | | | | | | | \vdash | |
| - | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | \square | |
| | | | | | | | | | | | | | | | | | | | | | | | | | |

| | Participant Training Data | | | | | | | | | | | | |
|--------------|---------------------------|------|--|---|-------|--|-----------------------|-------------------|---|--|------------------------------|---|---------------------------------|
| Course ID | Course Name | Code | Training category (Accredited / non- accredited) | Type of training course (Unit standard, Trade Titles, Short courses, Public body specific) | Start | End (for the entire training duration) | Number of Trainees | Number of Days | Cost (for the entire training course) | Status of training (Not started, In progress, Completed) | Training Provider Name | Training Provider Contact Number | Training Provider Address |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | l |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | <u> </u> |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | ļ |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | <u> </u>] |
| | | | | | | | | | | | | | <u> </u> |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | ļ] |
| | | | | | | | | | | | | | i l |

| EPWP Monthly Progress Form | | | | | | | | | |
|---|--|---|--|--|--|--|--|--|--|
| Field requested | Description if needed | Please complete the sections in white | | | | | | | |
| | Project Details | | | | | | | | |
| Profile ID | full descripton of what is happening in the project (as per the appointment letter) and the community benefiting from the project | | | | | | | | |
| Project Name | The name of the project | | | | | | | | |
| Project Reference Number Project description | Contract number Full descripton of what is happening in the project (as per the appointment letter) and the community | | | | | | | | |
| | benefiting from the project Month | | | | | | | | |
| Reporting Month | | April | | | | | | | |
| | Budget Expenditure | | | | | | | | |
| Cumulative Expenditure Amount | What is the Overall amount spend on this project? | | | | | | | | |
| Current Expenditure Amount | What is the amount spend including all grants for this month? | | | | | | | | |
| Wages | How much paid on wages for this month only? | | | | | | | | |
| UIF | How much paid on UIF for this month only? | | | | | | | | |
| COIDA | How much paid on COIDA for this month only? | | | | | | | | |
| Stipends for training | Amount paid to participants whilst on training (this month only) | | | | | | | | |
| Amount spent on service providers for training | How much paid to service providers for training for this month only? | | | | | | | | |
| Training | Total Cost of training for this month? (number captured on ERS) | | | | | | | | |
| Administration | How much paid on administration for this month only? | | | | | | | | |
| Equipment and materials | How much paid on equipment and materials for this month only? | | | | | | | | |
| Other | How much paid on other? | | | | | | | | |
| Describe other | Be specific e.g. Consulting fees, Transport etc. | | | | | | | | |
| Project output description | Describe the project output (end product and not the milestone) (e.g. kms of tar road constructed) Start with the unit of measure such as number of, kms, ha, sqms etc | | | | | | | | |
| Unit of measure of primary output | Eg. m, m², m³, km, no, ha etc | | | | | | | | |
| Cumulative primary output achieved | Since the onset of the project | | | | | | | | |
| Quantity Achieved | enter numeric output for this month only | | | | | | | | |
| Percentage achieved | How much work done / achieved in percentages? | | | | | | | | |
| | EPWP Branding | | | | | | | | |
| Branding compliant | Yes / No | | | | | | | | |
| Date that the branding was provided | When was the project branded? | | | | | | | | |
| Has a photo of project branding been provided? | Yes / No | | | | | | | | |
| First name of Official Who Branded Project | Official Name | | | | | | | | |
| Surname of Official Who Branded Project | Official Surname | | | | | | | | |
| Phone number of official who erected branding for the project | Official contact number | | | | | | | | |
| Give the public body reference and name, and organisational details of the person that provided branding. | Public body details (reference & name) | | | | | | | | |

| First Name | Initials | Surname | ID number | Date Of Birth | Wage Rate | Total Paid Days | Amount Paid | Work Days | Training Days Paid | Training Days Non Paid | Total Training Days | Training Course ID | Project Profile ID | Month | Year | Beneficiary Code |
|------------|----------|---------|-----------|---------------|-----------|-----------------|-------------|-----------|-----------------------|---------------------------|------------------------|-----------------------|--------------------|-------|------|------------------|
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |



The Attendance Register for on-site Workers

| Reporting month: | Mobile No: |
|------------------|--------------|
| Project Name: | Contract no: |
| Surname: | - |
| First Name: | |
| | |

| Dav Date | Time | 1 | Sign | - | Time | A 4 | <u> </u> | gnatu | | A | A | Formal |
|----------|------|---|------|---|------|------------|----------|-------|--|----------|---|--------|
| | | | | | | | | | | | | |

| Day | Date | Time in | Signature | Time Out | Signature | Training Provided In The Reporting Month |
|-----------------|------|---------|-----------|----------|-----------|---|
| WEEK 1 | | | | | | |
| MONDAY | | | | | | |
| TUESDAY | | | | | | |
| WEDNESDAY | | | | | | |
| THURSDAY | | | | | | |
| FRIDAY | | | | | | |
| | | | | | | |
| WEEK 2 | | | | | | |
| MONDAY | | | | | | |
| TUESDAY | | | | | | |
| WEDNESDAY | | | | | | |
| THURSDAY | | | | | | |
| FRIDAY | | | | | | |
| | | | | | | |
| WEEK 3 | | | | | | |
| MONDAY | | | | | | |
| TUESDAY | | | | | | |
| WEDNESDAY | | | | | | |
| THURSDAY | | | | | | |
| FRIDAY | | | | | | |
| | | | | | | |
| | | | | | | |
| WEEK 4 | | | | | | |
| MONDAY | | | | | | |
| TUESDAY | | | | | | |
| WEDNESDAY | | | | | | |
| THURSDAY | | | | | | |
| FRIDAY | | | | | | |
| WEEK 5 | | | | | | |
| MONDAY | | | | 1 | 1 | |
| TUESDAY | | | + | | 1 | + |
| WEDNESDAY | | | + | | 1 | + |
| THURSDAY | | | | | | |
| FRIDAY | | | | | | |
| | | | | | | |
| | | | | | | |
| Total Days work | kea | | | | | |

C3.3 PARTICULAR SPECIFICATIONS

PART F: SMALL CONTRACTOR DEVELOPMENT

PART F: SMALL CONTRACTOR DEVELOPMENT

F1. SCOPE

This part provides the procedures that relate to the Contractor implementing the Employer's policies and initiatives, enabling the Employer to realise its social and development objectives through the participation of Targeted Enterprises and Labour in the construction of the Works. The approach adopted enables the delivery of a wide range of social and economic deliverables, including the employment of local resources, employment opportunities for labour enhanced works, business opportunities, enterprise support and development programmes, and skills development.

The participation of Targeted Enterprises and Labour, measured in monetary terms, is specified as a contract participation goal by the Employer, for the Contractor to achieve.

F2. DEFINITIONS

Unless inconsistent with the context, in these specifications the following terms, words or expressions shall have the meanings hereby assigned to them:

F2.1 "**Black People**" has the meaning assigned to it in section 1 of the Broad-Based Black Economic Empowerment Act, 2003 (Act No 53 of 2003), and the Broad-Based Black Economic Empowerment Amended Act, 2013 (Act No 46 of 2013).

F2.2 **"Contract Participation**" means a process whereby the Employer sets a target to achieve its social and development objectives through the participation of Targeted Enterprises and Labour in the construction of the Works.

F2.3 **"Contract Participation Goal (CPG)**" means the value of goods, services and works for which the Contractor contracts Targeted Enterprises and Labour exclusive of any value added tax which the law requires the Employer to pay to the Contractor, expressed as a percentage of the Contract Price (adjusted to exclude penalties and value added tax).

F2.4 "**EME**" means an exempted micro enterprise in terms of a code of good practice on black economic empowerment issued in terms of section 9(1) of the Broad-Based Black Economic Empowerment Act, 2003 (Act No 53 of 2003).

F2.5 **"Military Veteran**" has the meaning assigned to it in section 1 of the Military Veterans Act, 2011 (Act No 18 of 2011).

F2.6 **"people with disabilities**" has the meaning assigned to it in section 1 of the Employment Equity Act, 1998 (Act No 55 of 1998).

F2.7 **"Project Management Team (PMT)**" means a team established at the commencement of the contract, comprising a representative from each of the Employer, the Employer's Agent and the Contractor, that will be responsible for various functions related to the implementation of the Contract Participation process.

F2.8 "**QSE**" means a qualifying small enterprise in terms of a code of good practice on black economic empowerment issued in terms of section 9(1) of the Broad-Based Black Economic Empowerment Act, 2003 (Act No 53 of 2003).

F2.9 **"Target Area**" means the geographic area stated in the Contract Data.

F2.10 **"Targeted Enterprise**" means an entity to which the Contractor subcontracts a percentage of the contract value as a condition of contract and which is:

- (i) an EME or QSE which is at least 51% owned by black people;
- (ii) an EME or QSE which is at least 51% owned by black people who are youth;

- (iii) an EME or QSE which is at least 51% owned by black people who are women;
- (iv) an EME or QSE which is at least 51% owned by black people with disabilities; or
- (v) an EME or QSE which is at least 51% owned by black people who are military veterans.

F2.11 **"Targeted Labour**" means individuals, employed by the Contractor and subcontractors in the performance of the contract, who permanently reside in the target area or who are recognised as being residents of the target area on the basis of identification and association with and recognition by the residents of the target area, and excludes any labour employed by suppliers and manufacturers.

F2.12 "Youth" means persons between the ages of 18 and 35.

F3. CONTRACT PARTICIPATION

F3.1 Objective

In order for the Employer to realise its social and development objectives, the Contractor is required to provide business and labour opportunities through the participation of Targeted Enterprises and Labour in the construction of the Works. The participation of Targeted Enterprises and Labour, measured in monetary terms, is specified by the Employer as a contract participation goal, for the Contractor to achieve.

F3.2 Contract Participation process

The Contractor shall engage Targeted Enterprises and Labour in the performance of the contract to the extent that the total monetary value of such engagements exclusive of any value added tax, expressed as a percentage of the Contract Price (adjusted to exclude penalties and value added tax), is not less than the Contract Participation Goal specified in the contract.

F3.2.1Contract Participation plan

The Contractor shall submit to the Employer's Agent details of his plan to achieve the Contract Participation Goal with his initial programme in terms of which he will carry out the Works. The Contract Participation plan shall be submitted with all subsequent adjusted programmes. The tender process for the procurement of Targeted Enterprise subcontractors shall be indicated on the programme.

The Contract Participation plan shall indicate the expected delivery dates of goods provided by Targeted Enterprises, and the commencement and completion dates of work and services to be performed by all the Targeted Enterprises and Labour engaged on the contract for the purpose of securing credits towards the Contract Participation Goal.

The information contained in the Contract Participation plan facilitates, in the first instance, the monitoring by the Employer's Agent of the performance of the Contractor in terms of his Contract Participation Goal obligations and, in the second instance, the making of any adjustments by the Contractor to compensate for quantitative underruns, the elimination of items contracted to Targeted Enterprises or Labour, or any other reason beyond the Contractor's control which may be acceptable to the Employer

F3.2.2Targeted Enterprises

The Contractor shall engage Targeted Enterprises comprising subcontractors and suppliers directly or indirectly in the performance of the contract. Prior to such Targeted Enterprises being engaged, the Contractor shall submit to the Employer's Agent documentation in a form approved by the Employer's Agent, to confirm that the enterprise satisfies the eligibility criteria for recognition as a targeted enterprise.

The Contractor shall enter into written contractual agreements with all the Targeted Enterprises, in a form approved by the Employer's Agent. Copies of such agreements and the written acceptance thereof shall be submitted to the Employer's Agent.

In the case of Targeted Enterprise subcontractors, only those subcontractors procured through a tender process as specified in clause F6 Tender Process for Targeted Enterprise Subcontractor Procurement, shall qualify to have their contribution count towards the Contract Participation Goal.

The Contractor may not subcontract more than 25% of the Contract Price to Targeted Enterprises whose B-

BBEE status level of contributor is lower than the Contractor's.

F3.2.3Targeted Labour

The Contractor shall engage Targeted Labour directly or indirectly in the performance of the contract. It is a requirement of the contract that such Targeted Labour be engaged by means of a written contract, in a form approved by the Employer's Agent.

The requirements for the engagement of such Targeted Labour is contained in Part E: Expanded Public Works Programme.

F3.3 Contract Participation Goal

The Contract Participation Goal comprises two targets, namely subcontracting of the Works to Targeted Enterprises, and employment of Targeted Labour. The Contract Participation Goal targets are stated as a percentage unit of measure in the Contract Data, for the Contractor to achieve to the extent that the total monetary value of such subcontracting and employment engagements exclusive of any value added tax, expressed as a percentage of the Contract Price (adjusted to exclude penalties and value added tax), are each not less than the respective Contract Participation Goal target stated in the contract.

F3.3.1Monthly submission of supporting documentation

The Contractor shall prepare and submit on a monthly basis to the Employer's Agent in a form approved by the Employer's Agent, the following:

- a brief report which describes the commercially useful functions performed by the Targeted Enterprises and Labour in the performance of the contract, both during the interim period and on a cumulative basis;
- a schedule reflecting the estimated total value of the contracts, the cumulative value of the contracts, and the value of goods provided, and work and services performed over the period for which payment is claimed with respect to each and every Targeted Enterprise; and
- (iii) a schedule which lists the names, identity numbers, gender, trade/occupation, period of employment, employment number and the like, as directed by the Employer's Agent, together with the respective wage rates payable in respect of Targeted Labour, including the monetary value of wages paid both on a cumulative basis and over the period for which payment is claimed.

Should random inspections conducted by the Employer's Agent on Targeted Enterprise and Labour activities indicate that such Targeted Enterprises and Labour are not performing in accordance with the requirements of the contract, the Contractor shall provide, in addition to the monthly reporting requirements, separate weekly resource returns and any other relevant information with respect to such Targeted Enterprises and Labour in a form approved by the Employer's Agent.

F3.3.2Contract Participation Goal credits

F3.3.2.1 Granting of credits

The Employer's Agent shall certify the value of the credits counted towards the Contract Participation Goal whenever a claim for payment is issued to the Employer, and shall notify the Contractor of the amount. The value of the credits counted shall not include any expenditure on Goods and Labour which forms part of the monetary value of the contributions made by Targeted Enterprise subcontractors.

Credits towards the Contract Participation Goal shall be granted by converting the value of the following (including contract price adjustment and rise/fall on special materials, but excluding value added tax) to a percentage of the Contract Price (adjusted to exclude penalties and value added tax), as relevant:

(i) subcontracting CPG:

- the total monetary value of the contributions made by Targeted Enterprise subcontractors in fulfilling contractual obligations; and
- expenditure on Goods required for the contract, which are obtained from Targeted Enterprise suppliers.
- (ii) employment CPG:
 - the total monetary value of wages paid to Targeted Labour.

F3.3.2.2 Denial of credits

No credits shall be granted should the Contractor make a direct payment to a supplier or manufacturer on behalf of a Targeted Enterprise when such payment is recovered by making deductions from payments to the Targeted Enterprise in connection with the contract; or should the Contractor fail to enter into a written agreement with the relevant Targeted Enterprise.

In addition, credits claimed towards the Contract Participation Goal shall be denied where written contractual agreements contain any of the following:

- (i) a right to set off in favour of the employing Contractor not provided for by law;
- (ii) authoritarian rights given to the employing Contractor or his agent, with no recourse to independent adjudication in the event of a dispute arising;
- (iii) payment procedures based on a pay-when-paid system;
- (iv) a dispute resolution process which does not include inexpensive alternative dispute resolution procedures, such as mediation or adjudication, but which only makes use of formal proceedings such as arbitration or litigation; or
- (v) conditions which are more onerous than those which exist in the main contract.

Credits shall be denied should Targeted Enterprises not adhere to statutory labour practices or fail to perform commercially useful functions.

F3.3.3Contract Participation Goal evaluation

The Contractor shall, upon completion of each individual Targeted Enterprise's contract, issue a completion certificate and certify the amount paid to such Targeted Enterprises. The Contractor shall submit the certificates, counter-certified by the relevant Targeted Enterprises, to the Employer's Agent for record-keeping purposes. The Contractor shall furnish justification to the Employer's Agent whenever it is not possible to obtain such counter-certification.

The Contractor shall, upon termination of the services of the individuals classed as Targeted Labour engaged in activities relating to the performance of the contract, certify the amount paid to such individuals and submit the certificate, counter-certified by the relevant individual, to the Employer's Agent for record-keeping purposes. The Contractor shall furnish justification to the Employer's Agent whenever it is not possible to obtain such counter-certification.

On completion of the contract, the Employer's Agent shall determine the final credits to be granted towards the Contract Participation Goal targets, by converting the value of credits (including contract price adjustment and rise/fall on special materials, but excluding value added tax) to a percentage of the Contract Price (adjusted to exclude penalties and value added tax)

F3.3.4Sanctions

In the event that the Contractor fails to substantiate that any failure to achieve any of the Contract Participation Goal targets, is due to quantitative underruns, the elimination of items contracted to Targeted Enterprises, or any other reason beyond the Contractor's control which may be acceptable to the Employer, the Contractor shall be liable for a financial penalty as prescribed in clause SCC 4.1.1 of section C1.2.1.2 Special Conditions of Contract. The subcontracting financial penalty shall be calculated as follows:

$$P = 0.05 x [(D - D_0)/100] x C_A$$

where

- D is the Contract Participation Goal percentage
- D_o is the Contract Participation Goal percentage which the Employer's Agent certifies, based on the credits passed, as being achieved upon completion of the contract
- C_A contract amount which is the Contract Price (adjusted to exclude penalties and value added tax)
- P is the monetary value of penalty payable

The evaluation of the Contractor's achievement of the Contract Participation Goal for the subcontracting of the Works to Targeted Enterprises, shall be undertaken monthly by the Employer's Agent based on the accumulative achievements in comparison to the programmed utilisation of Targeted Enterprises, as a means of monitoring the Contractor's performance in achieving the Contract Participation Goal.

Failure by the Contractor to achieve the Contract Participation Goal target by the time of Practical Completion, shall result in the financial penalty being applied as prescribed in this clause. The Employer's Agent shall make a final determination of the Contractor's achievement of the Contract Participation Goas based on the value of the Final Payment Certificate.

F4. DUTIES OF THE EMPLOYER AND ENGINEER

The Employer, Engineer, and the Contractor, or their representatives, are parties to the Project Liaison Committee and are co-responsible for successful project Stakeholder and Community liaison. The Employer and the Engineer also play a supporting role in the successful implementation of the Employer's Targeted Labour and Targeted Enterprise utilisation and development goals.

To implement the Employer's Targeted Labour and Targeted Enterprise goals, the Employer and the Engineer shall provide support to the Contractor by executing the following duties:

- (i) Make recommendations to the Contractor in the identification and structuring of the work packages to be subcontracted to Targeted Enterprises, and agree to the scope and extent of the work packages.
- (ii) Verify that the Targeted Enterprise Database(s), have been updated prior to the letting of every new set of subcontracts.
- (iii) Endorse all Databases, and approve tender procedures, tender documents, tender submission requirements and adjudication processes for the subcontracting of Targeted Enterprises.
- (iv) Review all tender adjudication reports and monitor that the criteria and procedures applied by the Contractor to subcontract work to Targeted Enterprises are executed in a fair and transparent manner, and are in accordance with the Employer's standards.
- (v) Endorse subcontract agreements and ensure that the conditions of subcontracting with Targeted Enterprises are fair and transparent and within the prescripts of the Contract requirements.
- (vi) Monitor the management of Targeted Enterprise subcontracts and ensure that conditions such as the application of penalties and the termination of contracts, are applied in a fair and transparent manner and within the prescripts of the agreement.
- (vii) Verify that the Labour Database(s) from which Targeted Labour will be employed is updated prior to every new Labour intake.

- (viii) Monitor that the criteria and procedures applied by the Contractor to employ Targeted Labour are executed in a fair and transparent manner, and is within the Contract requirements.
- (ix) Monitor that the conditions of employment of Targeted Labour are applied in a fair and transparent manner and within the prescripts of the current and relevant Labour legislation.
- (x) Make recommendations to the Contractor in the identification of the training requirements of Targeted Enterprises and Targeted Labour and approve the proposed training programmes.
- (xi) Monitor that training programmes and support programmes, which the Contractor committed to, are implemented and executed as intended.

F5. SPECIFIC WORK TO BE CARRIED OUT BY TARGETED ENTERPRISE SUBCONTRACTORS

F5.1 Subcontract scope of work

It is a requirement of the contract that only those Targeted Enterprise subcontractors procured through a tender process by the Contractor, shall qualify to have their contribution count towards the Contract Participation Goal.

For this particular contract, the following listed work has been identified in terms of this Particular Specification, Part F, as suitable for execution by Targeted Enterprise subcontractors in order to assist the Contractor in achieving the Contract Participation Goal:

- (i) Clearing and grubbing.
- (ii) Construction and clearing of drains.
- (iii) Installation of prefabricated culverts including inlet and outlet structures.
- (iv) Concrete channelling and concrete linings for open drains.
- (v) Breaking up existing pavement layers
- (vi) Pitching, stonework and protection against erosion.
- (vii) Construction of gabions.
- (viii) Erection of guardrails.
- (ix) Erection of road signs.
- (x) Fencing
- (xi) Road Markings
- (xii) Landscaping.
- (xiii) Structural Work
- (xiv) Finishing the road and road reserve.
- (xv) Other work identified by the Employer to be executed in the community area.

The work to be carried out by Targeted Enterprise subcontractors is not limited to the work listed above, and the Contractor may need to engage Targeted Enterprises and Labour on other aspects of the Works in order to achieve the Contract Participation Goal.

F5.2 Subcontract work packages

The work activities shall be grouped into varying sizes of work packages according to the CIDB contractor grading designation and class of construction works. The typical scope of work may include the following class of construction works and specialist works:

- (i) Class of construction works Civil Engineering (CE); and
- (ii) Specialist Works:
 - Asphalt works (SB);
 - Demolition and blasting (SE);
 - Piling (SJ);

- Road marking and signage (SK); and
- Structural steelwork fabrication and erection (SL).

For this contract the minimum number of prescribed work packages for execution by Targeted Enterprise subcontractors is indicated in table F1/1 according to the CIDB contractor grading designation and the scope of work according to the Chapters of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020.

Provision is made for each of the work packages to include Chapter 1.3 Contractor's Establishment on Site and General Obligations to cover the costs of the Targeted Enterprise subcontractors' own establishment

TABLE F1/1: PRESCRIBED MINIMUM NUMBER OF WORK PACKAGES ACCORDING TO CIDB CONTRACTOR GRADING DESIGNATION

| | | TARGETED ENTERPRISE SUBCONTRACTOR CIDB CONTRACTOR GRADING DESIGNATION | | | | | | | | |
|---|--|--|-------------------|-------------------|-------------------|--------------------|--------------------|--|--|--|
| CHAPTER | DESCRIPTION | 1 Max: R0,5 m | 2 Max: R1 m | 3 Max: R3 m | 4 Max: R6 m | 5 Max: R10 m | 6 Max: R20 m | | | |
| C1.6 | CLEARING AND GRUBBING | X(1) | | | | | | | | |
| C3.1 | DRAINS | | X(3) | | | | | | | |
| C3.2 | CULVERTS | | | | X(1) | | | | | |
| C3.3 | CONCRETE KERBING AND CHANNELING, ASPHALT BERMS, CHUTES, DOWNPIPES, AS WELL AS CONCRETE, STONE PITCHED AND GABION LININGS FOR OPEN DRAINS | | X(2) | X(3) | | | | | | |
| C11.1 & C11.2 | PITCHING, STONEWORK, CAST IN SITU CONCRETE FOR PROTECTION AGAINST EROSION & NON-STRUCTURAL GABIONS | X(4) | X(3) | | | | | | | |
| C11.4 | ROAD RESTRAINT SYSTEMS | | X(2) | | | | | | | |
| C11.5 | FENCING | X(2) | | | | | | | | |
| C11.7 | ROAD MARKINGS AND ROAD STUDS | X(2) | | | | | | | | |
| C11.8 & C11.9 | LANDSCAPING AND PLANTING PLANTS FINISHING THE ROAD AND ROAD & RESERVE AND TREATING OLD ROADS | | | X(1) | | | | | | |
| C13.1, C13.2, C13.3, C13.4, C13.7, C13.8 | FOUNDATIONS FALSEWORK, FORMWORK AND CONCRETE FINISH STEEL REINFORCEMENT CONCRETE JOINTS ANCILLARY STRUCTURAL ELEMENTS | | | | | X(1) | | | | |
| | MINIMUM TOTAL NUMBER OF TARGETED ENTERPRISE SUBCONTRACTORS <u>PRESCRIBED</u> FOR EACH CIDB CONTRACTOR GRADING DESIGNATION | 8 | 10 | 4 | 1 only | 1 only | | | | |

and general obligations.

NOTE:

X* denotes inclusion of Chapter 1.3 for all subcontract work packages.

X(1) denotes "one" prescribed subcontract work package according to the respective CIDB contractor grading designation and the scope of work according to the Chapter of the Standard Specifications for Road and Bridge Works for South African Road Authorities (COTO), Draft Standard (DS), October 2020. For subcontractors with a higher CIDB contractor grading designation, it may be possible for the work package to comprise more than one chapter which is shown as "X" in the above table. The minimum total number of targeted enterprise subcontractors prescribed for each CIDB contractor grading designation is listed in the above table.

F5.3 Subcontract bill of quantities

The items of work identified for execution by Targeted Enterprise subcontractors is shown in the bill of quantities at the end of Part F: Small Contractor Development. The quantities of work shown for each item of work, is the anticipated work to be subcontracted, and the Contractor is not required to tender rates and prices for these items of work.

Payment of the works executed by Targeted Enterprise subcontractors will be made under the provisional sum allowed for in clause F10 Measurement and Payment and included in Schedule F: Small Contractor Development in Section C2.2 Bill of Quantities.

F6. TENDER PROCESS FOR TARGETED ENTERPRISE SUBCONTRACTOR PROCUREMENT

F6.1 Subcontract scope of work

The Contractor shall refer to Table F1/1 for the work packages identified to be subcontracted, the bill of quantities contained in these Particular Specifications, and to any other construction activities required to execute the Works in terms of the contract, to determine how he intends to unbundle or package specific subcontracts for execution by Targeted Enterprise subcontractors, and shall present his proposal to the Employer and Employer's Agent for approval.

F6.2 Compilation of subcontract tenders

The Contractor shall be responsible for compiling the tender documents that will enable him to engage the Targeted Enterprise subcontractors for the various work packages, according to the contractor grading designation and class of construction works or specialist works. The Contractor shall compile each subcontract tender document in such a manner that it shall facilitate the achievement of all objectives and principles pertaining to the development of the Targeted Enterprise subcontractors.

The tender documentation shall comply with the Employer's standards, including its standard conditions of tender. The following returnable schedules shall form part of the tender document for submission by tenderers:

- certificate of registration of the tenderer in the required CIDB contractor grading designation, confirming the tenderer's registration Status as "Active" at the closing date of tender submission;
- (ii) tax compliance status report;
- (iii) B-BBEE verification certificate or sworn affidavit;
- (iv) proof of registration on the Central Supplier Database; and
- (v) compliance with the COID Act.

The tender documents shall also contain the proposed subcontract agreement in accordance with clause F8.1.

The draft tender documents shall be subject to approval by the Employer and Employer's Agent. The Contractor may then proceed with the preparation of tender documents for the work packages.

F6.3 Tender process

The Contractor shall be responsible for advertising the tenders for the work packages, and inviting tenders from Targeted Enterprise subcontractors in consultation with the Employer and Employer's Agent and the local PLC.

The Employer shall identify the number of work packages which are to be executed by Targeted Enterprise subcontractors from specific designated groups.

The Contractor shall conduct a compulsory briefing session for tenderers, attended by the Employer and Employer's Agent, to explain the Works required and the tender process to the Targeted Enterprise subcontractors.

Tenders for the subcontracted works must close at a stipulated time and date. Tenders shall be placed in a suitable formal Tender Box, located at the Contractor's site office. The tender opening shall be conducted by the Project Management Team.

F6.4 Tender evaluation

The Project Management Team shall evaluate the tenders according to the Employer's standards. The Contractor shall prepare the tender adjudication report for each subcontract, and submit it to the Project Management Team for review prior to award of each subcontract.

F6.5 Allocation of subcontract work packages

The Project Management Team shall identify responsive tenders received for the various work packages from Targeted Enterprises in the following designated groups:

- (i) an EME or QSE which is at least 51% owned by black people;
- (ii) an EME or QSE which is at least 51% owned by black people who are youth;
- (iii) an EME or QSE which is at least 51% owned by black people who are women;
- (iv) an EME or QSE which is at least 51% owned by black people with disabilities; or
- (v) an EME or QSE which is at least 51% owned by black people who are military veterans.

The selection of subcontract work packages shall then be made, in consultation with the Employer in accordance with the provisions of clause 4.4.4 of the General Conditions of Contract 2015, in order to comply with the Employer's targeted procurement objectives.

F6.6 Award of subcontract work packages

Following the selection of the Targeted Enterprise subcontractors for the various work packages in consultation with the Employer in accordance with clause 4.4.4 of the General Conditions of Contract 2015, the Employer's Agent shall provide written confirmation of the Targeted Enterprise subcontractor selected for each work package, to the Contractor. The Contractor shall award each work package to the respective Targeted Enterprise subcontractor.

F7. GENERAL RESPONSIBILITIES OF THE CONTRACTOR TOWARDS TARGETED ENTERPRISES

F7.1 Obligations

The Contractor shall ensure that he complies with the following obligations:

- (i) institute a quality assurance system;
- (ii) provide adequate training, coaching, guidance, mentoring and assistance to Targeted Enterprises;
- (iii) provide financial support and other assistance to ensure that Targeted Enterprises are able to meet their obligations and commitments with respect to their subcontracts, including acquisition of labour, construction equipment and materials;
- (iv) ensure that the contract participation goals and objectives are achieved; and

(v) make provision for Targeted Enterprises to be established within the Contractor's own camp facilities, and be responsible for the provision of site offices, common camp facilities, medical, security, safety, electricity, water, sewage services, waste disposal and all other camp services.

F7.2 Subcontracts

In the subcontracts arranged by the Contractor involving Targeted Enterprises, the following shall apply:

- (i) the appointment of Targeted Enterprises by the Contractor shall be made in accordance with the provisions of clause 4.4 of the General Conditions of Contract 2015; and
- (ii) no provision or requirements set out in the specifications shall be deemed to relieve the Contractor of any liability or obligation under the contract, and in accordance with the provisions of clause 4.4.3 of the General Conditions of Contract 2015, the Contractor shall be liable for the acts, defaults and negligence of any Targeted Enterprise, his agents or employees as fully as if they were the acts, defaults or negligence of the Contractor.

F8. MANAGEMENT OF TARGETED ENTERPRISE SUBCONTRACTS

The Contractor shall conclude the subcontract agreements, and provide the necessary management support to the Targeted Enterprises. Failure by a Targeted Enterprise to comply with the terms and conditions of the subcontract agreement shall result in penalties being applied or the subcontract terminated.

G8.1 Compilation of subcontract conclusion agreement

- (a) The Contractor in liaison with the Employer and Employer's Agent shall be responsible for the conclusion of each subcontract agreement. The agreement shall be in accordance with the provisions of clause 4.4 of the General Conditions of Contract 2015 and shall be consistent with the terms and conditions in this contract. The agreement shall be subject to approval by the Employer and Employer's Agent.
- (b) The terms and conditions of the subcontract agreement shall also specify the following:
 - (i) an entitlement of the Targeted Enterprise to receive such training as is contemplated in this contract;
 - (ii) an obligation on the Targeted Enterprise to participate and co-operate in such training as is provided for in this contract;
 - (iii) the allowable sources from which workers may be drawn in terms of the contract;
 - (iv) the terms and conditions relating to the recruitment, employment and remuneration of workers engaged on the contract;
 - (v) the training to be provided to the workers; and
 - (vi) the terms and conditions relating to payment of the Targeted Enterprise. Such terms and conditions shall also include a clause stipulating that payment to a Targeted Enterprise for work done shall be made within 30 days of submission of the invoice by the Targeted Enterprise to the Contractor. In the event of failure by the Contractor to make the payment by the due date, he shall pay to the Targeted Enterprise interest, at the prime overdraft rate charged by the Targeted Enterprise's bank, compounded monthly, on all overdue payments from the date on which the same should have been paid to the date when payment is effected, without prejudice to the Targeted Enterprise's other rights under the contract or by law.

F8.2 Quality of work and performance of the Targeted Enterprise

(a) The Contractor shall closely monitor and supervise all Targeted Enterprises and shall train, mentor, guide and assist each Targeted Enterprise in all aspects of management, execution and completion of his subcontract. This shall typically include assistance with planning of the works, sourcing and ordering of materials, labour relations, monthly measurements and invoicing procedures. The extent and level of such training, mentoring, guidance and assistance to be provided by the Contractor shall be commensurate with the basic level of subcontract applicable and shall be directed at enabling the Targeted Enterprise to achieve the successful execution and completion of their subcontract.

(b) The Contractor shall closely monitor and supervise all Targeted Enterprises and shall give reasonable warning to the Targeted Enterprise when any contravention of the terms and conditions of the subcontract has occurred or appears likely to occur. The Contractor shall, whenever feasible, give the Targeted Enterprise reasonable opportunity to make good any such contravention, or to avoid such contravention, and shall render all reasonable assistance to the Targeted Enterprise in this regard.

F8.3 Dispute avoidance and resolution procedures

- (a) When taking any disciplinary action or imposing a penalty as provided for in the subcontract, the Contractor shall explain fully to the Targeted Enterprise that such actions are provided for in the subcontract. If such action is contemplated this shall be discussed with the Employer's Agent before any action is taken.
- (b) If the Targeted Enterprise, in the opinion of the Employer's Agent, fails to comply with any of the criteria listed below, the Employer's Agent shall issue a written warning to the Contractor, stating all the areas of non-compliance. A copy of the letter of warning shall be forwarded to the Employer. The criteria are as follows:
 - (i) acceptable standard of work as set out in the specifications;
 - (ii) progress in accordance with the time constraints in the Targeted Enterprise's contract;
 - (iii) punctual and full payment of the workforce and suppliers;
 - (iv) site safety; and
 - (v) accommodation of traffic.
- (c) The Targeted Enterprise shall have 21 days from the date of receipt of the letter of warning by the Contractor to address and rectify the issues raised by the Employer's Agent, with the exception of the above subclauses (b)(iv) and (v) for which the reaction time shall be in accordance with the relevant specifications for those aspects of the Works but shall not be longer than 24 hours. Failure by the Targeted Enterprise to comply with the deadline set, will be sufficient grounds for the Contractor to apply a penalty, or terminate the subcontract provided that the Employer's Agent is satisfied that the Contractor has made every effort to correct the performance of the Targeted Enterprise.
- (d) The Targeted Enterprise shall have the right to dispute any ruling given or deemed to have been given by the Contractor, Employer's Agent or Employer. Provided that, unless the Targeted Enterprise shall, within 21 days after his receipt of a ruling or after a ruling shall have been deemed to be have been given, give written notice (hereinafter referred to as a Dispute Notice) to the Contractor, referring to this clause, disputing the validity or correctness of the whole or a specified part of the ruling, he shall have no further right to dispute that ruling or the part thereof not disputed in the said notice.

F9. TRAINING, COACHING, GUIDANCE AND MENTORING

F9.1 Obligations

This section provides details of the Contractor's obligations of implementing the National Skills Development Strategy. This strategy sets priorities for the skills development of workers. The Sector Education and Training Authorities (SETA) and provincial offices of the Department of Labour will play key roles in transforming the vision of the strategy into reality.

Supervision is included as part of the contractor's general obligations for the administration and management of the Targeted Enterprises. However, training, coaching, guidance and mentoring are not included as part of the Contractor's general obligations unless specific provision to that effect has been made in the project specifications.

The Contractor shall, from the commencement of the contract, provide a structured development programme designed to improve the entrepreneurial and basic business management skills of identified Targeted Enterprises and hired labour, as well as to improve their specific task skills (construction skills) commensurate with the applicable levels of subcontract that will enable the Targeted Enterprises to achieve the successful execution and completion of their subcontracts. The ultimate objective of training, coaching, guidance and mentoring is to develop the Targeted Enterprises as far as their potential allows.

F9.2 Definitions

F9.2.1 Training

Training refers to the process of teaching a learner – usually in a classroom or simulated work environment situation. Training usually takes place with one teacher/trainer and several learners. Principles and theory are taught. Demonstrations are given. Assignments are then set to ensure that the learner is able to apply what has been taught. Training is done by a specialist in the subject, who is also qualified to train.

Example: Use of a dumpy level

Training would involve the theory of how a dumpy level works and how to calculate levels. A demonstration of how to set up and read a level could be given.

F9.2.2 Coaching

Coaching refers to hands-on training and is mostly on a one-on-one basis of tangible and measurable skills. It is typically on-site training, or learning-on-the-job. Coaching is training by the process of "watch-docorrect-practice". The coach does the task while the learner watches and asks questions. Then the learner does the same task while the coach watches. The learner is corrected until the coach feels that he has the gained competence in the function. The learner is then left to practise the task or skill, which the coach oversees. Coaching is imparting a skill – usually manual or physical. A coach is usually a person doing the same type of work on a higher or more competent level, or a person who has a mastery of the skill/task. While training gives the theory or shows/explains the principles, coaching helps the learner become competent and master a skill. A coach is often in the direct reporting line, i.e. someone in authority. Coaching could be part of the management function and would make the job run more smoothly.

Example: Use of a dumpy level

Coaching would involve taking the learner onto site, setting up a dumpy level, reading levels. Then the coach would get the learner to do the job, while the coach checked the setting up and reading. Once the learner understands and can do the tasks, the coach checks periodically to ensure the learner is still doing the job properly.

The desired outcome of coaching is for the learner to "fit-the-mould", and to do things the same way and to the same standard as the coach.

F9.2.3 Guidance

Guidance is anticipating where one might go wrong, or where one is doing a task in a complicated, inefficient or ineffective way, and giving advice as to how to achieve a better result. Guidance is mostly given by a person in the direct reporting line, but can be given by anyone. Guidance is not imparting skills, but suggesting ways to improve performance.

Example: Use of a dumpy level

A person who knows how to use a dumpy level would be given guidance as to where he would next set up the level to limit the number of set-ups. Guidance could be an extension of coaching.

F9.2.4 Mentoring

Mentoring is developing a person on a long-term career path. It is mostly about imparting skills that are often intangible and non-measurable. A mentor is seldom anyone in the direct reporting line – although he could be a person several levels higher in that reporting line. Mentoring is more about developing a

relationship and taking a personal interest in an individual. A mentor looks out for that individual and gives him advice that cannot be found in a book or in the normal course of business. The sort of issues a mentor discusses with the protégé include company politics, how to pick up work before others get wind of it, how to position one's company to get a better competitive advantage, how to tender such that the tender is lowest but the profit is as good as or better than the next person, how to determine and assess risk. Mentoring helps the protégé think strategically, sharpen entrepreneurial skills and grow – both personally and in terms of the company. A mentor helps the protégé to develop insight and shrewdness. It is more about business skills to survive long-term than the technical, tactical or day-to-day activities of doing business.

The desired outcome of mentoring is for the protégé to develop his own style, i.e., to shape his own "mould".

F9.2.5 Supervision

Supervision is instruction regarding the work to be performed, and ensuring it is carried out to specification and to the satisfaction of the supervisor. It is not instruction on how the work is to be performed, but rather on what work has to be performed, and usually has specific time frames.

F9.3 Assessment of Targeted Enterprise potential

It is the responsibility of the Contractor to determine the level of development required by each Targeted Enterprise. This will require that the Contractor determine the level at which the Targeted Enterprise can operate competently and determine the skills already acquired by the Targeted Enterprise in terms of training and on-the-job experience. In some circumstances Adult Basic Education Training (ABET) will need to be started before any formal training can commence. The assessment of each appointed Targeted Enterprise is to be produced by the Contractor for discussion with the Employer and Employer's Agent at a meeting following the appointment of the Targeted Enterprise.

F9.4 Development Plan

Within a month of the meeting with the Employer and Employer's Agent on the Targeted Enterprise assessments, the Contractor is to present a development plan, specific to each Targeted Enterprise. The development plan is to be reviewed by the Employer and Employer's Agent for appropriateness before being implemented.

The development plan is to include the following:

- (i) specify the development needs of each Targeted Enterprise contracting entity the systems the entity lacks;
- (ii) specify the development needs of the individuals comprising the entity the skills the individuals within the entity lack;
- (iii) the level to which that activity will be developed within the period of the contract;
- (iv) whether training, coaching, guidance and/or mentoring is to be given in each activity; and
- (v) the person/s responsible for each activity.

F9.5 Identification and general training of potential Targeted Enterprises

- (a) The progression of training, coaching and mentorship may need to start with the identification and general training of identified Targeted Enterprises and hired labour, and should end with their acquisition of sufficient management skills that will equip them to compete confidently for subcontract work beyond the duration of this contract. In addition, generic skills shall be taught where the need for these has been identified as being necessary amongst Targeted Enterprise workforces and hired labour.
- (b) Before commencing with any structured training, the Contractor shall submit his intended programme to the Employer and Employer's Agent for approval of its subject content and proposed trainers, and the Contractor shall, if so, instructed by the Employer and Employer's Agent, alter or amend the programme and/or course content.

The Contractor shall be responsible for the provision of everything necessary for the delivery of the various

training workshops and modules including:

- (i) provision of a suitable fully serviced training venue facility;
- (ii) procurement of suitable accredited trainers;
- (iii) provision, in conjunction with the accredited trainers, of all the necessary training materials, including stationery and study materials; and
- (iv) transportation of the learners to and from the training venue facility (it is therefore in the Contractor's interest that the training venue facility be provided on the site in order to reduce these transportation costs).

Payment to the Contractor for carrying out the training function shall be effected through the pay items provided in this Part F, using the training facility provided under Part E: Expanded Public Works Programme.

F9.6 Activities

The tasks for each of the activities making up the development plan include material, equipment and general tasks, for training on technical, contractual, financial, human resources, legislative and general administrative functions.

The Construction Manager, site clerk and HR Manager will train/coach or mentor the above listed functions as part of on-site training.

F9.7 Portfolio of Evidence

The Contractor is to develop and/or maintain a portfolio of evidence for each Targeted Enterprise. The Portfolio of Evidence is a collection of proof of the training, coaching, guidance and mentoring inputs provided to the Targeted Enterprise and is similar to a log book used by technical students completing experiential training. It is a living document which records the development progress of the Targeted Enterprise and will need to be updated continually throughout the duration of the contract. It remains the property of the Targeted Enterprise who must take it to their next contract.

The Portfolio of Evidence should include the following documentation:

- (i) the development path designed for each Targeted Enterprise;
- (ii) the training courses completed by the Targeted Enterprise;
- (iii) the hours of guidance, coaching and mentoring received for each activity listed in the development plan;
- (iv) a list of outcomes achieved at each level for each activity;
- (v) six-monthly progress reports on the development provided (inputs) versus the actual progress made (output) by the Targeted Enterprise; and
- (vi) a list of competencies.

F9.8 Training Requirements

Only qualified trainers employed by training agencies that are accredited by the relevant Sector Education and Training Authorities (SETA), or other institutions recognised by the Department of Labour shall deliver any training. "Accredited training" refers to both the trainers as well as to the training material. Certificates affirming the successful participation in the various courses shall be presented to each attendant.

The Contractor shall facilitate in the delivery of training by instructing and motivating the hired labour and relevant Targeted Enterprises regarding attendance and participation. All training shall take place within normal working hours, or as agreed with the trainees.

F9.9 Development training

The Contractor will arrange training to support the development of the Targeted Enterprise. This training must be provided by training providers accredited with the relevant SETA pertaining to the course material being presented. The training will take place at hours agreed with the trainees, possibly on a part time basis after hours.

The following training courses are recommended to support the development programme detailed in the contract document:

- (i) NQF Level 2: Construction Contractor Business owner and administration officer;
- (ii) Tender training NQF Level 3 Business owner / Technical expert;
- (iii) Computer literacy training Business owner and admin officer Microsoft Windows, email, Microsoft Word and Microsoft Excel;
- (iv) General bookkeeping relevant to construction Business owner and admin officer;
- (v) Tendering NQF Level 4 and 5 Business owner / Technical expert; and
- (vi) Construction supervision (Roadworks) NQF Level 4 Business owner / Technical expert.

F9.10 Safety Training

The Targeted Enterprise's safety representative is to be fully trained in all aspects of safety and his duties in this regard. The owner of the Targeted Enterprise is to be trained on his responsibilities regarding safety regulations.

F9.11 Construction skills training

The focus of training provided on the contract should be to support the development of the Targeted Enterprise subcontractor. Construction skills training will only be approved by the Employer's Agent when appropriate.

The Targeted Enterprise, their workforce and hired labour that are selected will be entitled to receive structured training that will improve on-task skills necessary for the execution and successful completion of the works. The Contractor, in conjunction with the Employer's Agent, shall monitor the progress of the hired labour and each Targeted Enterprise closely and shall identify those who, in their collective opinion, will benefit from structured construction skills training as may be provided for in the contract, and where required by the Employer's Agent shall make recommendations in this regard. The final list of candidates shall be decided between the Contractor and the Employer's Agent, and those selected shall receive formal construction skills training in a programmed and progressive manner throughout the duration of the contract.

The training programme shall offer complete courses that could comprise some or all of the following modules:

- (i) Use and maintenance of hand tools;
- (ii) Operation of equipment;
- (iii) Manufacture and installation of minor precast concrete units;
- (iv) Erect, dismantle and maintain formwork;
- (v) Basic concrete skills;
- (vi) Excavation, backfill and compaction;
- (vii) Bricklaying; and
- (viii) Erosion protection using stone pitching, gabions or renos.

F9.12 Training venue facility

The training venue facility to be provided by the Contractor is described in clause F5.6 of Part F. This facility shall be used to deliver all training, irrespective of whether it is delivered in terms of Part E or Part F of the Particular Specifications.

F10. MEASUREMENT AND PAYMENT

Note:

In order to avoid duplication of training facilities, the training facility required for the training described in this

Part F: Small Contractor Development, shall be measured and paid for in terms of the pay items provided for training in Part E: Expanded Public Works Programme.

| Item | Unit |
|--------|--|
| F10.01 | Procurement of Targeted Enterprises: |
| (a) | Management and execution of Targeted Enterprise procurement process: |
| (i) | Procurement process for the appointment of CIDB contractor grading designation 1 Targeted Enterprise subcontractor (100 copies of the tender document required for each individual tender)number (No) |
| (ii) | Procurement process for the appointment of CIDB contractor grading designation 2 Targeted Enterprise subcontractor (80 copies of the tender document required for each individual tender)number (No) |
| (iii) | Procurement process for the appointment of CIDB contractor grading designation 3 Targeted Enterprise subcontractor (60 copies of the tender document required for each individual tender)number (No) |
| (iv) | Procurement process for the appointment of CIDB contractor grading designation 4 Targeted Enterprise subcontractor (50 copies of the tender document required for each individual tender)number (No) |
| (v) | Procurement process for the appointment of CIDB contractor grading designation 5 Targeted Enterprise subcontractor (40 copies of the tender document required for each individual tender)number (No) |
| (vi) | Procurement process for the appointment of CIDB contractor grading designation 6 Targeted Enterprise subcontractor (40 copies of the tender document required for each individual tender)number (No) |

The unit of measurement shall be the number of individual subcontract agreements concluded with Targeted Enterprise subcontractors according to the CIDB contractor grading designation for all classes of construction works, in accordance with the procurement process described in this Part F.

Each tendered rate shall be in full compensation for the management and execution of the Targeted Enterprise procurement process in the relevant CIDB contractor grading designation scheduled, including for the compilation, printing, binding and issue of the tender documents for each tender, for the advertising of each tender, for the provision of the venue and the conducting of each compulsory briefing session for tenderers, for the conducting of each tender opening process, for the adjudication of the tenders received for each tender, for the preparation of each tender adjudication report and the review thereof in conjunction with the Employer and Employer's Agent, for the award of each tender and for the conclusion of the subcontract agreement with each successful Targeted Enterprise subcontractor tenderer.

Item

F10.02 Construction Works for Targeted Enterprise subcontractors:

|) | | (a) Payments associated with the construction Works carried out by Targeted Enterprise subcontractors | (8 |
|----|---------------------------|--|----|
|) | percentage (% | (b) Handling costs and profit in respect of subitem F10.02(a). | (t |
|) | provisional sum (Prov sum | (c) Supply of materials and small construction equipment to assist Targeted Enterprise subcontractors | (0 |
|) | percentage (% | (d) Handling costs and profit in respect of subitem G10.02(c). | (0 |
| L_ | an o a th | (a) Monogone at of the Toynoted Enternaise subcontractors | 1. |

(e) Management of the Targeted Enterprise subcontractorsmonth

Expenditure under subitems F10.02(a) and (c) shall be in accordance with clause 6.6 of the General Conditions of Contract 2015.

The provisional sum for subitem F10.02(a) is provided to cover the total cost of the construction Works carried out by the Targeted Enterprises subcontractors based on proof of payment made by the Contractor, as certified by the Employer's Agent, in separate payments for each Targeted Enterprise subcontractor in accordance with Part F of the Particular Specifications.

The tendered percentage for subitem F10.02(b) is the percentage of the amount actually spent under subitem G10.02(a), and shall include full compensation for the handling costs of the Contractor and the profit in connection with the construction Works carried out by the Targeted Enterprise subcontractors.

The provisional sum for subitem F10.02(c) is provided to cover the total cost of the materials and small construction equipment supplied by the Contractor to assist the Targeted Enterprise subcontractors based on proof of payment made by the Contractor, as certified by the Employer's Agent, in separate payments for each Targeted Enterprise subcontractor in accordance with Part F of the Particular Specifications.

The tendered percentage for subitem F10.02(d) is the percentage of the amount actually spent under subitem F10.02(c), and shall include full compensation for the handling costs of the Contractor and the profit in connection with the supply of materials and small construction equipment by the Contractor to assist the Targeted Enterprise subcontractors.

The unit of measure for subitem F10.02(e) is month or part thereof that the service is required. Payment shall only be made for the period one or more appointed Targeted Enterprise subcontractors are on site in the execution of the works. The tendered rate shall include full compensation for the conclusion of all the subcontract agreements and the management of all Targeted Enterprise subcontractors, including for the provision of the necessary management support, coaching, guidance and mentoring to the Targeted Enterprise subcontractors.

| ltem | U | nit |
|--------|---|-----|
| F10.03 | Training of Targeted Enterprise subcontractors: | |
| (a) | Generic skills: | |
| (i) | Training costs provisional sum (Prov su | m) |
| (ii) | Handling costs and profit in respect of subitem F10.03(a)(i) percentage (| %) |
| (b) | Entrepreneurial skills: | |
| (i) | Training costs provisional sum (Prov su | m) |
| (ii) | Handling costs and profit in respect of subitem F10.03(b)(i) percentage (| %) |
| | | |

- (c) Construction skills:
 (i) Training costs provisional sum (Prov sum)
 (ii) Handling costs and profit in respect of subitem F10.03(c)(i) percentage (%)
 (d) Transportation and accommodation costs of selected learners only, while receiving off-site training:
- (i) Transportation and accommodation costs provisional sum (Prov sum)
- (ii) Handling costs and profit in respect of subitem F10.03(d)(i) percentage (%)

Expenditure under subitems F10.03(a)(i), (b)(i), (c)(i) and (d)(i) shall be in accordance with clause 6.6 of the General Conditions of Contract 2015.

The provisional sum for each of subitems F10.03(a)(i), (b)(i) and (c)(i) is provided to cover the total costs of the required training in generic skills, entrepreneurial skills and construction skills respectively, including for the procurement of the services of the accredited trainers and their delivery of the training courses to the learners employed by Targeted Enterprise subcontractors, the provision of all training materials including all stationery and study materials, and the wages of the learners for the duration of the courses. The payment of wages to learners in terms of subitems F10.03(a)(i), (b)(i) and (c)(i) will only be made to those learners who attend and successfully complete each course of the approved training programme. Payment shall not be made to learners who, once selected, do not attend or only partially complete structured training courses.

The Contractor's own personnel shall be permitted to attend the training courses provided for the learners employed by the Targeted Enterprise subcontractors only to the extent that the venue and its facilities can efficiently and comfortably accommodate the additional number of learners. All additional costs relating to such attendance by the Contractor's own personnel shall be carried by the Contractor and shall not be considered for payment in terms of item F10.03, including for any additional costs related to the accredited trainers and their delivery of the training courses, the provision of additional training materials, and the wages of the learners from the Contractor's own personnel for the duration of the courses.

The tendered percentage for each of subitems F10.03(a)(ii), (b)(ii) and (c)(ii) is the percentage of the amount actually spent under each of subitems F10.03(a)(i), (b)(i) and (c)(i) respectively, and shall include full compensation for the handling costs of the Contractor, and the profit in connection with the provision of the training in generic skills, entrepreneurial skills and construction skills respectively, including for the costs of record keeping and reporting with respect to the training received by each learner, and the costs of the compilation of the portfolio of evidence with respect to each Targeted Enterprise subcontractor.

The provisional sum for subitem F10.03(d)(i) is provided to cover all costs related to the transportation and accommodation costs of selected learners only, while receiving off-site training, where such learners have been specifically selected in conjunction with the Employer's Agent to receive such off-site training and where such training cannot be delivered using the training venue facility provided by the Contractor.

The tendered percentage for subitem F10.03(d)(ii) is the percentage of the amount actually spent under subitem F10.03(d)(i), and shall include full compensation for the handling costs of the Contractor, and the profit in connection with the transportation and accommodation costs of selected learners only, while receiving off-site training.

BILL OF QUANTITIES PART F: SMALL CONTRACTOR DEVELOPMENT

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|----------|---|----------|----------|--|
| C1.2 CPG | GENERAL REQUIREMENTS AND PAYMENT | | | |
| C1.2.2 | Programming and Reporting | | | |
| C1.2.2.1 | Submission of a Scheme 1 Programme | Lump Sum | 1 | |
| C1.2.2.2 | Reviewing and updating a Scheme 1 Programme | month | 18 | |
| C1.2.2.6 | Preparation and submission of all information and reports specified in the Contract Documentation | month | 18 | |
| C1.2.5 | Safety | | | |
| C1.2.5.1 | Health and safety plan | Lump Sum | 1 | |
| C1.2.5.2 | Implementation of health and safety plan | month | 18 | |
| C1.2 CPG | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|----------|---|----------|----------|------|
| C1.3 CPG | CONTRACTOR'S SITE ESTABLISHMENT AND GENERAL OBLIGATIONS | | | |
| C1.3.1 | The Contractor's general obligations | | | |
| C1.3.1.1 | Fixed obligations | Lump Sum | 1 | |
| C1.3.1.3 | Time-related obligations | month | 18 | |
| | | | | |
| C1.3 CPG | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|----------|--|----------------|----------|--|
| C1.6 | CLEARING AND GRUBBING | | | |
| C1.6.1 | Clearing | | | |
| C1.6.1.1 | Clearing with machines and some hand labour where necessary | ha | 2 | |
| C1.6.1.2 | Clearing with hand labour only when labour enhanced work is specified | ha | 3 | |
| C1.6.2 | Grubbing | | | |
| C1.6.2.1 | Grubbing with machines and some hand labour where necessary | ha | 1 | |
| C1.6.2.2 | Grubbing with hand labour only when labour enhanced work is specified or it is not practical to use a machine | ha | 3 | |
| C1.6.3 | Removal and grubbing of large trees and tree stumps: | | | |
| C1.6.3.1 | Girth equal to or exceeding 1,0 m up to and including 2,0 m | No | 5 | |
| C1.6.3.2 | Girth exceeding 2,0 m up to and including 3,0 m | No | 5 | |
| C1.6.7 | Re-clearing of previously cleared areas | ha | 2 | |
| C1.6.9 | Conservation of topsoil | | | |
| C1.6.9.1 | Stockpilling topsoil | m³ | 2300 | |
| C1.6.9.2 | Windrowing topsoil | m ³ | 2300 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| C1.6 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|----------|--|----------------|----------|--|
| C3.1 | DRAINS | | | |
| C3.1.1 | Excavation for open drains: | | | |
| C3.1.1.1 | Excavating all material situated within the following depth ranges below the surface level using conventional methods : | | | |
| (a) | 0m to 1.5m | m ³ | 4 000 | |
| (b) | Exceeding 1.5m and up to 3.0m | m ³ | 10 | |
| C3.1.1.2 | Extra over sub-item C3.1.1.1 for excavation in hard and boulder material , irrespective of depth | m ³ | 566 | |
| C3.1.1.3 | Extra over sub-item C3.1.1.1 for excavation in stabilised existing road layers, irrespective of depth | m ³ | 20 | |
| C3.1.1.4 | Excavating soft material situated Om to 1.5m below the surface level using labour enhanced construction methods | m ³ | 3 000 | |
| C3.1.1.5 | Excavating intermediate material situated 0m to 1.5m below the surface level using labour enhanced construction methods | m ³ | 500 | |
| C3.1.2 | Clearing, shaping and disposal of accumulated sediment in existing unlined open drains | | | |
| C3.1.2.1 | Using conventional methods | m ³ | 30 | |
| C3.1.4 | Excavation and disposal of material for subsoil drainage systems | | | |
| C3.1.4.1 | Excavating in all material situated within the following depth ranges below the surface : | | | |
| (a) | 0m to 1.5m | m ³ | 5 | |
| (b) | Exceeding 1.5m and up to 3.0m | m ³ | 9 | |
| (c) | Etc, in increments of 1.5m | m ³ | 10 | |
| C3.1 | TOTAL CARRIED FORWARD | | 1 | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|----------|---|----------------|----------|--|
| | TOTAL BROUGHT FORWARD | | | |
| C3.1.4.2 | Excavating soft material situated within 0m to 1.5m below the surface level using labour enhanced construction methods | m³ | 85 | |
| C3.1.4.3 | Excavating intermediate material situated within 0m to 1.5m below the surface level using labour enhanced construction methods | m³ | 15 | |
| C3.1.4.4 | Extra over sub-item C3.1.4.1 for excavation in hard and boulder material, irrespective of depth | m ³ | 9 | |
| C3.1.4.5 | Extra over sub-item C3.1.4.1 for excavation through stabilised existing road layers | m ³ | 20 | |
| C3.1.5 | Impermeable backfilling to subsoil drainage system | | | |
| C3.1.5.1 | Un-stabilised natural gravel obtained from approved sources on the site | m ³ | 85 | |
| C3.1.5.2 | G5 material obtained from commercial sources | m ³ | 10 | |
| C3.1.7 | Natural permeable material in subsoil drainage system (approved crushed stone): | | | |
| C3.1.7.2 | Crushed stone obtained from commercial sources (Coarse Grade - 19mm) | m ³ | 20 | |
| C3.1.8 | Natural permeable material in subsoil drainage system (approved natural sand) | | | |
| C3.1.8.2 | Natural sand from commercial sources (Coarse) | m ³ | 84 | |
| C3.1.9 | Pipes in subsoil drainage systems | | | |
| C3.1.9.1 | U-PVC pipes and fittings , normal duty, complete with coupling (110mm and perforated or slotted) | m | 110 | |
| C3.1 | TOTAL CARRIED FORWARD | | <u> </u> | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-----------|--|----------------|----------|--|
| | TOTAL BROUGHT FORWARD | | 1 | |
| C3.1.10 | Polymer film sheeting or similar approved material, for lining subsoil drainage systems: | | | |
| C3.1.10.1 | 0.15 mm thick | m² | 130 | |
| C3.1.11. | Geotextile (non-woven, grade 2) | m² | 143 | |
| C3.1.13 | Concrete outlet structures, manhole boxes, junction boxes and cleaning eyes for subsoil drainage systems: | | | |
| C3.1.13.1 | Outlet structures | | | |
| | (a) In situ outlet structures for side drains, class 20/19 concrete, complete as shown on drawing no. SD 0603/A (detail SD 0603/1) | No | 94 | |
| C3.1.13.4 | Cleaning eyes (Rodding Eye, complete as shown in drawing no. SD 0501/A) | No | 15 | |
| C3.1.14 | Caps for subsoil drain pipe : | | | |
| C3.1.14.1 | Concrete caps | No | 5 | |
| C3.1.15 | Repairing or replacing existing drainage systems | Prov sum | 20 000 | |
| C3.1.16 | Loading and hauling of material in excess of 1.0km | m³-km | 63 245 | |
| C3.1.17 | Backfilling existing eroded side drains | m ³ | 50 | |
| C3.1.18 | Backfilling of drains with selected material compacted to 93 % of MDD prior to construction of concrete lining and/or stone pitched lining | m ³ | 20 | |
| C3.1.23 | Subsoil drain outlet marker (type or drawing specified) | No | 10 | |
| | | | | |
| C3.1 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| C3.2 CULVERTS C3.2.1 Excavation for culvert structures: Excavating in all material situated within the following depth ranges below the surface level: Om to 1.5m Om to 1.5m Excavating soft material 0 m to 3.0m Excavating soft material 0 m to 1,5 m below the surface level using about results of 1.5m Excavating soft material 0 m to 1,5 m below the surface level using about results of instructed by hand under Clause A3.2.7.2d): Extra over sub-item C3.2.1.1 for excavation in stabilised existing road layers, irrespective of depth C3.2.1.5 Extra over sub-item C3.2.1.1 for excavation in stabilised existing road layers, irrespective of depth C3.2.2.1 Using the excavated material m³ 10 C3.2.2.2 Using the excavated material m³ 1305 C3.2.2.3 Concrete pipe culverts: | ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|---|----------|---|----------------|----------|--|
| C3.2.1.1Excavating in all material situated within the following depth ranges below the surface level:(a)0m to 1.5mm³2 610(b)Exceeding 1.5m and up to 3.0mm³1 830(c)Etc, in increments of 1.5mm³200C3.2.1.2Excavating soft material 0 m to 1,5 m below the surface level using labour enhanced construction methods, or instructed by hand under Clause A3.2.7.20):m³500C3.2.1.4Extra over sub-item C3.2.1.1 for excavation in hard or boulder material, irrespective of depthm³392C3.2.1.5Extra over sub-item C3.2.1.1 for excavation in stabilised existing road layers, irrespective of depthm³10C3.2.2.1Using the excavated materialm³1305C3.2.2.2Using imported selected material: (a)m³1305(a)From commercial sources (G6)m³550(b)From sources on site (G6)m³1305 | C3.2 | CULVERTS | | | |
| C3.2.1.1within the following depth ranges below the surface level:(a)Om to 1.5mm³2 610(b)Exceeding 1.5m and up to 3.0mm³1 830(c)Etc, in increments of 1.5mm³200Excavating soft material 0 m to 1,5 m below the surface level using labour enhanced construction methods, or instructed by hand under Clause A3.2.7.2d):m³500C3.2.1.4Extra over sub-item C3.2.1.1 for excavation in hard or boulder material, irrespective of depthm³392C3.2.1.5Extra over sub-item C3.2.1.1 for excavation in stabilised existing road layers, irrespective of depthm³10C3.2.2.1Using the excavated materialm³1305C3.2.2.2Using imported selected material: (a)m³550(b)From commercial sources (G6)m³550 | C3.2.1 | Excavation for culvert structures: | | | |
| (b)Exceeding 1.5m and up to 3.0mm³1 830(c)Etc, in increments of 1.5mm³200Excavating soft material 0 m to 1,5 m below the surface level using labour enhanced construction methods, or instructed by hand under Clause A3.2.7.20):m³200C3.2.1.2Extra over sub-item C3.2.1.1 for excavation in hard or boulder material, irrespective of depthm³392C3.2.1.5Extra over sub-item C3.2.1.1 for excavation in stabilised existing road layers, irrespective of depthm³10C3.2.2.1Backfilling: using the excavated materialm³1305C3.2.2.2Using the excavated materialm³550(a)From commercial sources (G6)m³550(b)From sources on site (G6)m³1305 | C3.2.1.1 | within the following depth ranges | | | |
| (c)Etc, in increments of 1.5mm³200Excavating soft material 0 m to 1,5 m below the surface level using labour enhanced construction methods, or instructed by hand under Clause A3.2.7.2d):m³500C3.2.1.4Extra over sub-item C3.2.1.1 for excavation in hard or boulder material, irrespective of depthm³392C3.2.1.5Extra over sub-item C3.2.1.1 for excavation in stabilised existing road layers, irrespective of depthm³10C3.2.2Backfilling:m³10C3.2.2.1Using the excavated materialm³1 305(a)From commercial sources (G6)m³550(b)From sources on site (G6)m³1 305 | (a) | 0m to 1.5m | m ³ | 2 610 | |
| C3.2.1.2Excavating soft material 0 m to 1,5 m below the surface level using labour enhanced construction methods, or instructed by hand under Clause A3.2.7.2d):m³C3.2.1.4Extra over sub-item C3.2.1.1 for excavation in hard or boulder material, irrespective of depthm³392C3.2.1.5Extra over sub-item C3.2.1.1 for excavation in hard or boulder material, irrespective of depthm³392C3.2.1.5Extra over sub-item C3.2.1.1 for excavation in stabilised existing road layers, irrespective of depthm³10C3.2.2Backfilling:10C3.2.2Using the excavated materialm³1 305C3.2.2.2Using imported selected material:1 305(a)From commercial sources (G6)m³550(b)From sources on site (G6)m³1 305 | (b) | Exceeding 1.5m and up to 3.0m | m ³ | 1 830 | |
| C3.2.1.2m below the surface level using labour enhanced construction methods, or instructed by hand under Clause A3.2.7.2d):m³500C3.2.1.4Extra over sub-item C3.2.1.1 for excavation in hard or boulder material, irrespective of depthm³392C3.2.1.5Extra over sub-item C3.2.1.1 for excavation in stabilised existing road layers, irrespective of depthm³10C3.2.2Backfilling:m³10C3.2.2.1Using the excavated materialm³1 305C3.2.2.2Using imported selected material:m³550(a)From commercial sources (G6)m³550(b)From sources on site (G6)m³1305 | (c) | Etc, in increments of 1.5m | m ³ | 200 | |
| C3.2.1.4excavation in hard or boulder material, irrespective of depthm³392C3.2.1.5Extra over sub-item C3.2.1.1 for excavation in stabilised existing road layers, irrespective of depthm³10C3.2.2Backfilling:1010C3.2.2.1Using the excavated materialm³1 305C3.2.2.2Using imported selected material:1010(a)From commercial sources (G6)m³550(b)From sources on site (G6)m³1305 | C3.2.1.2 | m below the surface level using labour enhanced construction methods, or instructed by hand | m ³ | 500 | |
| C3.2.1.5excavation in stabilised existing road layers, irrespective of depthm³10C3.2.2Backfilling: | C3.2.1.4 | excavation in hard or boulder | m ³ | 392 | |
| C3.2.2.1Using the excavated materialm³1 305C3.2.2.2Using imported selected material: | C3.2.1.5 | excavation in stabilised existing | m ³ | 10 | |
| C3.2.2.2Using imported selected material:(a)From commercial sources (G6)m³(b)From sources on site (G6)m³1305 | C3.2.2 | Backfilling: | | | |
| (a)From commercial sources (G6)m³550(b)From sources on site (G6)m³1305 | C3.2.2.1 | Using the excavated material | m ³ | 1 305 | |
| (b) From sources on site (G6) m^3 1305 | C3.2.2.2 | Using imported selected material: | | | |
| | (a) | From commercial sources (G6) | m ³ | 550 | |
| C3.2.3 Concrete pipe culverts: | (b) | From sources on site (G6) | m ³ | 1305 | |
| | C3.2.3 | Concrete pipe culverts: | | | |
| C3.2.3.3 On Class C bedding Class 100D | C3.2.3.3 | On Class C bedding Class 100D | | | |
| 1) 450 mm Diameter m 340 | | 1) 450 mm Diameter | m | 340 | |
| 2) 600 mm Diameter m 695 | | 2) 600 mm Diameter | m | 695 | |
| 3) 900 mm Diameter m 20 | | 3) 900 mm Diameter | m | 20 | |
| C3.2 TOTAL CARRIED FORWARD | C3.2 | TOTAL CARRIED FORWARD | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-----------|--|----------------|----------|--|
| | TOTAL BROUGHT FORWARD | | I | |
| C3.2.3.5 | Provision of skew ends of pipe culvert (Class 100D) | | | |
| | 1) 450 mm Diameter | No | 4 | |
| | 2) 600 mm Diameter | No | 10 | |
| | 3) 900 mm Diameter | No | 2 | |
| C3.2.6 | Extra over items C3.2.3, C3.2.4 and C3.2.5 for constructing inclined culverts | m | 15 | |
| C3.2.7 | Cast in situ concrete and formwork: | | | |
| C3.2.7.5 | In inlet and outlet structures including kerbs, chutes and downpipes, skewed ends, catchpits, manholes, thrust and anchor blocks, excluding formwork but including Class U2 surfacing finish (class of concrete indicated) | m ³ | 35 | |
| C3.2.7.6 | Formwork of concrete under items C3.2.7.3 to 5 above (Class of finish indicated) | m² | 40 | |
| C3.2.10 | Reinforcement: | | | |
| C3.2.10.1 | Mild steel bars | t | 0.1 | |
| C3.2.10.2 | High-tensile steel bars | t | 0.2 | |
| C3.2.10.3 | Welded steel fabric | kg | 620 | |
| C3.2.13 | Removing and re-laying existing culverts: | | | |
| C3.2.13.1 | Removing and stacking existing culverts for re-use | | | |
| | (a) Class 100D: | | | |
| | (i) 450 mm diameter | m | 105 | |
| | (ii) 600 mm diameter | m | 53 | |
| | (ii) 900 mm diameter | m | 53 | |
| C3.2 | TOTAL CARRIED FORWARD | | <u> </u> | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-----------|--|------|----------|--|
| | TOTAL BROUGHT FORWARD | | - | |
| C3.2.13.3 | Re-laying existing culverts from stacking (size and type of bedding indicated) | | | |
| | (a) Class 100D: | | | |
| | (i) 450 mm diameter | m | 40 | |
| | (ii) 600 mm diameter | m | 30 | |
| | (ii) 900 mm diameter | m | 30 | |
| C3.2.16 | Brickwork (Engineering bricks): | | | |
| C3.2.16.1 | 115 mm thick | m² | 15 | |
| C3.2.16.2 | 230 mm thick | m² | 367 | |
| C3.2.16.3 | 345 mm thick | m² | 20 | |
| C3.2.17 | Plaster | m² | 131 | |
| C3.2.18 | Benching | m² | 16 | |
| C3.2.19 | Accessories: | | | |
| C3.2.19.1 | Manhole frames (Frame and Grid as per SD 0602/B) | No | 9 | |
| C3.2.24 | Compaction of bedding for inlets, outlets, manholes and catchpits: | | | |
| C3.2.24.1 | Preparation and compaction of in situ bedding material to 90 % of MDD (150mm Deep) | m³ | 15 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| C3.2 | TOTAL CARRIED FORWARD TO SUMMARY | | 1 | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|----------|---|------|----------|------|
| C3.3 | CONCRETE KERBING AND CHANNELLING, ASPHALT BERMS, CHUTES, DOWNPIPES, AS WELL AS CONCRETE, STONE PITCHED AND GABION LININGS FOR OPEN DRAINS | | | |
| C3.3.1 | Concrete kerbing: | | | |
| C3.3.1.1 | Prefabricated kerbing | | | |
| (a) | SABS 927 figure 6, as shown on drawing no. SD 0701/A | m | 305 | |
| C3.3.2 | Concrete kerbing-channeling combination: | | | |
| C3.3.2.1 | Prefabricated kerbing-channeling | | | |
| (a) | 500 mm wide kerb and channel using prefabricated battered kerb, radius greater than 20 m, SABS 927 figure 6, with cast in situ class 15/19 concrete channel, as shown on drawing no. SD 0701/A | m | 325 | |
| C3.3.3 | Extra over items C3.3.1 and C3.3.2 for concrete kerbing or concrete kerbing and channeling on curves | | | |
| C3.3.3.1 | On curves of radii more than or equal to 5,0 m but less than 20 m | m | 50 | |
| C3.3.3.2 | On curves with radii more than or equal to 1,0 m but less than 5,0 m | m | 10 | |
| C3.3.4 | Extra over item C3.3.2 for drop kerbs at pedestrian crossings and driveways | m | 1000 | |
| C3.3.8 | Linings for open drains: | | | |
| C3.3.8.1 | Cast in situ concrete lining | | | |
| | (a) Cast in situ class 20/19 concrete lining in open drains: | | | |
| | (i) V-drains (as shown on drawing no. SD 0601/C) SD 0601/C) | m³ | 2005 | |
| | (ii) 1.8m wide footway | m³ | 70 | |

| C3.3 | TOTAL CARRIED FORWARD | | | |
|-----------|--|------|----------|--|
| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
| | TOTAL BROUGHT FORWARD | | 1 | |
| C3.3.8.2 | Class U2 surface finish to cast in situ concrete | | | |
| | (i) V-drains | m² | 16010 | |
| | (ii) 1.8m wide footway | m² | 456 | |
| C3.3.8.3 | Stone pitched lining (200 mm thickness) | | | |
| (a) | Grouted stone pitching (V - Drain) | m² | 165 | |
| (b) | Grouted stone pitching on a concrete bed (Class 25/13 Concrete, V-Drain) | M² | 165 | |
| C3.3.9 | Formwork to cast in situ concrete lining for open drains (Class F2 surface finish): | | | |
| C3.3.9.2 | To sides with formwork on both internal and external faces (each face measured) | m² | 1250 | |
| C3.3.9.3 | To ends of slabs | m² | 490 | |
| C3.3.10 | Sealed joints in concrete and stone pitched linings of open drains (sealed with a closed cell expanded polyethylene joint filler over the full panel depth, as per Note 3 on drawing no. SD 0601/C) | | | |
| | (a) Construction joints | m | 2 496 | |
| | (b) Expansion joints | m | 1 248 | |
| C3.3.11 | Concrete screed or backfill below chutes (50mm thick class 15/13 MPa Concrete) | m³ | 150 | |
| C3.3.12 | Reinforcement: | | | |
| C3.3.12.3 | Welded steel fabric | kg | 63 240 | |
| C3.3.13 | Polymer film sheeting (0.15mm thick) for concrete-lined open drains | m² | 130 | |
| | | | | |

| C3.3 | TOTAL CARRIED FORWARD | | | |
|-----------|--|------|----------|--|
| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
| | TOTAL BROUGHT FORWARD | | | |
| C3.3.15 | Energy dissipaters in outlet structures | | | |
| C3.3.15.1 | Precast concrete blocks in outlet structures | No | 20 | |
| C3.3.15.2 | Stones set in outlet structures | m² | 80 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| C3.3 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-----------|--|----------------|----------|--|
| C11.1 | PITCHING, STONEWORK, CAST IN SITU CONCRETE FOR PROTECTION AGAINST EROSION | | | |
| C11.1.1 | Foundation trenches for stone masonry walls | | | |
| C11.1.1.1 | Excavating foundation trenches in soft material using labour enhanced construction methods 0 m to 1,0 m depth | m³ | 20 | |
| C11.1.1.2 | Excavating foundation trenches in intermediate material using labour enhanced construction methods 0 m to 1,0 m depth | m³ | 15 | |
| C11.1.2 | Stone pitching | | | |
| C11.1.2.1 | Plain stone pitching | | | |
| (a) | Method 1 | m² | 165 | |
| C11.1.2.3 | Grouted stone pitching on a concrete bed | m² | 165 | |
| C11.1.6 | Concrete edge beams (class of concrete indicated) | M ³ | 20 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| C11.1 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-----------|---|------|----------|--|
| C11.2 | NON-STRUCTURAL GABIONS | | | |
| C11.2.1 | Foundation trench excavation: | | | |
| C11.2.1.1 | Excavating all material situated within the following depth ranges below the surface level | | | |
| (a) | 0 m to 1,5 m | m³ | 100 | |
| (b) | Exceeding 1,5 m and up to 3,0 m | m³ | 100 | |
| (c) | Etc, in increments of 1,5 m | m³ | 50 | |
| C11.2.1.2 | Extra over sub-item C11.2.1.1 for excavation in hard material, irrespective of depth | m³ | 200 | |
| C11.2.1.3 | Excavating soft material within 1,5 m below the surface level using labour enhanced construction methods: | m³ | 500 | |
| C11.2.1.4 | Excavating intermediate material within 1,5 m below the surface level using labour enhanced construction methods: | m³ | 300 | |
| C11.2.2 | Surface preparation for bedding the gabion boxes and mattresses | m² | 1 178 | |
| C11.2.3 | Gabion boxes and mattresses: | | | |
| C11.2.3.1 | Galvanized gabion boxes (dimensions of box) | | | |
| | (i) 2,0m long x 1,0m wide x 1,0m deep (mesh size 80mm x 100mm, with 2,7mm OD frame wire & 2,2mm OD mesh wire) Galvanized gabion mattresses | m³ | 2 355 | |
| C11.2.3.3 | (dimensions of mattress) | | | |
| | (i) 6,0m long x 2,0m wide x 0,3m deep (mesh size 80mm x 100mm, with 2,5mm OD frame wire and 2,2m OD mesh wire, diaphragm spacing 1,0m) | m³ | 428 | |
| C11.2.4 | Geotextile (Nonwoven continious filament needle punched geotextile grade A4) | m² | 6175 | |
| C11.2 | TOTAL CARRIED FORWARD | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|---------------------|---|----------------|----------|--|
| | TOTAL BROUGHT FORWARD | | | |
| C11.2/ C13.1.8.1 | Backfill to excavations utilising labour: | | | |
| | Material from excavation | m ³ | 353 | |
| C11.2/ C13.1.14 | Foundation fill consisting of: | | | |
| | Mass concrete (class 15/35) | m ³ | 20 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| C11.2 | TOTAL CARRIED FORWARD TO SUMMARY | | <u> </u> | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-----------|--|------|----------|--|
| C11.4 | ROAD RESTRAINT SYSTEMS | | | |
| C11.4.1 | Erecting of guardrails at 3,81 m spacing | | | |
| C11.4.1.1 | Complete galvanized system compliant to SANS 1350: | | | |
| (a) | On timber posts (Drawing SD 1101/B) | m | 1 420 | |
| (d) | Extra over C11.4.1.1(a) and C11.4.1.1(b) for excavating holes of posts using labour enhanced methods (soft and intermediate) | m | 1 420 | |
| C11.4.1.2 | Terminal sections for 3,81 guardrails comprising of: | | | |
| (a) | End wings to SANS 1350 | No | 10 | |
| (d) | End treatments where single guardrail sections are specified (As per drawing SD 1102/A) | No | 15 | |
| (e) | End treatments where double guardrail sections are specified (As per drawing SD 1102/A) | No | 15 | |
| (g) | Extra over C11.4.1.2(d) and C11.4.1.2(e) for excavating holes for posts using labour enhanced methods (soft and intermediate) | No | 30 | |
| C11.4.4 | Extra over for horizontally curved guard rails | | | |
| C11.4.4.1 | Extra over C11.4.1 and C11.4.11 for horizontally curved guard rails factory bent to a radius of less than 45 m | m | 25 | |
| C11.4.4.2 | Extra over C11.4.2.1(a) for horizontally curved guard rails factory bent to a radius of less than 45 m | m | 25 | |
| C11.4.5 | Additional guardrail posts for 3,81 m systems: | | | |
| C11.4.5.1 | Timber | No | 75 | |
| C11.4 | TOTAL CARRIED FORWARD | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-----------|--|------|----------|--|
| | TOTAL BROUGHT FORWARD | | | |
| C11.4.6 | Reflective plates | | | |
| C11.4.6.1 | Steel plates | No | 190 | |
| C11.4.7 | Removing existing guardrails: | m | 25 | |
| C11.4.14 | Nailing of gang nail plates on top of timber guardrail posts | No | 75 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| C11.4 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-----------|---|------|----------|--|
| C11.5 | FENCING | | | |
| C11.5.1 | Supply and erect new fencing material for new fences and for supplementing material in existing fences which are being repaired or removed: | | | |
| C11.5.1.1 | Zinc-coated barbed wire (SABS 675) - High-tensile-grade, single- strand 3,15mm x 2,50mm oval- shaped wire - Galvanised, Class A | km | 95 | |
| C11.5.1.2 | Zinc-coated smooth wire - 4,0mm dia,mild steel straining wire, Grade C galvanised | km | 15 | |
| C11.5.1.7 | Standards 2,0m x 2,5 kg/m mild steel y section | No | 250 | |
| C11.5.1.8 | Droppers 1,4m x 0,56 kg/m mild steel ridge back section | No | 1 030 | |
| C11.5.1.9 | Straining posts, stays and anchors: | | | |
| (a) | Vertical | | | |
| (i) | Steel straining posts (Notched 2100 x 125mm galvanized & anchored in concrete) | No | 70 | |
| (c) | Horizontal | | | |
| (i) | Steel stays and anchors (100mm diameter and wall thickness 3mm) | No | 55 | |
| C11.5.4 | Dismantling existing fences and gates: | | | |
| C11.5.4.1 | Fences: | | | |
| (a) | Stock-proof fences | km | 25 | |
| C11.5.9 | Repairing existing fences (Stock Proof) | km | 10 | |
| | | | | |
| C11.5 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|------------|---|------|----------|--|
| C11.7 | ROAD MARKINGS AND ROAD STUDS | | | |
| C11.7.2 | Retro-reflective road marking: | | | |
| C11.7.2.1 | White lines broken or unbroken (Retro-reflective road-marking paint) | | | |
| | (i) 100 mm wide | km | 8 | |
| | (ii) 200 mm wide | km | 1 | |
| C11.7.2.2 | Yellow lines broken or unbroken (Retro-reflective road-marking paint) | | | |
| | (i) 100 mm wide | km | 16 | |
| C11.7.2.3 | Red lines broken or unbroken (Retro- reflective road-marking paint) | | | |
| | (i) 100 mm wide | km | 2 | |
| C11.7.2.11 | Labour enhanced hand painted white lettering and symbols (Retro-reflective road-marking paint) | m² | 150 | |
| C11.7.2.12 | Labour enhanced hand painted yellow lettering and symbols (Retro-reflective road-marking paint) | m² | 50 | |
| C11.7.2.13 | Labour enhanced hand painted transverse lines, painted island and arrestor bed markings (any colour) (Retro-reflective road-marking paint) | m² | 500 | |
| C11.7.5 | Variations in rate of application: | | | |
| C11.7.5.1 | White paint | Ι | 150 | |
| C11.7.5.2 | Yellow paint | I | 150 | |
| C11.7.5.3 | Red paint | Ι | 150 | |
| C11.7.5.4 | Retro-reflective beads | kg | 300 | |
| | | | | |
| | | | | |
| | | | | |
| C44 7 | | | | |
| C11.7 | TOTAL CARRIED FORWARD | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|------------|---|------|----------|--|
| | TOTAL BROUGHT FORWARD | | | |
| C11.7.7 | Road studs | | | |
| C11.7.7.2 | Permanent road studs compliant to SANS 1463 | | | |
| | (a) 100 mm x 100 mm x 20 mm high, plastic stickon type with 43-bead glass reflectors (bidirectional type, any colour) | No | 833 | |
| C11.7.7.3 | Temporary road studs compliant to SANS 1442 or 1463 (type/classification & colours stated) | No | 210 | |
| C11.7.8 | Setting out and premarking the lines (excluding traffic island markings, lettering and symbols) | km | 23 | |
| C11.7.9 | Re-establishing the painting unit during the defects notification period and at other instances on instruction of the Engineer | No | 1 | |
| C11.7.10 | Removal of existing, temporary or final road markings by: | | | |
| C11.7.10.1 | Sandblasting | m² | 10 | |
| C11.7.10.3 | Overpainting as temporary measure | m² | 10 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| C11.7 | TOTAL CARRIED FORWARD | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-----------|--|------|----------|--|
| C11.8 | LANDSCAPING AND PLANTING PLANTS | | | |
| C11.8.1 | Trimming: | | | |
| C11.8.1.1 | Machine trimming | m² | 3 000 | |
| C11.8.1.2 | Hand trimming | m² | 5 000 | |
| C11.8.3.3 | Topsoiling within the road reserve where the following materials are used: | | | |
| (a) | Topsoil obtained from within the road reserve or borrow areas | m³ | 1 000 | |
| (b) | Topsoil obtained from commercial sources by the Contractor | M³ | 2 000 | |
| C11.8.4 | Grassing | | | |
| C11.8.4.2 | Sodding by using the following types of sods: | | | |
| (b) | Veld sods | m² | 500 | |
| C11.8.4.3 | Hydroseeding: | | | |
| (c) | Hydroseeding | ha | 3 | |
| C11.8.5 | Watering the grass when established by topsoiling only | kł | 100 | |
| C11.8.6 | Watering the already planted grass, trees and shrubs during the growing season | k{ | 100 | |
| C11.8.7 | Mowing the grass | ha | 88 | |
| C11.8.9 | Trees and shrubs: | | | |
| C11.8.9.1 | Providing trees and shrubs | | | |
| (a) | Trees (indigenous - 50kg) | No | 10 | |
| C11.8.9.2 | Planting and establishing: | | | |
| (a) | Trees, all types and sizes | No | 10 | |
| C11.8.11 | Weeding all grass-seeded areas and the grass when established by topsoiling only | ha | 5 | |
| C11.8 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-----------|--|------|----------|--|
| C11.9 | FINISHING THE ROAD AND ROAD RESERVE AND TREATING OLD ROADS | | | |
| C11.9.1 | Finishing the road and road reserve: | | | |
| C11.9.1.2 | Single carriageway road | km | 6.66 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| C11.9 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-------------|---|----------------|----------|------|
| | PART 1: STC 4189 - 3/2.0 x 2.25m BOX CULVERT | | | |
| 1/C13.1 | FOUNDATIONS | | | |
| 1/C13.1.3 | Excavation: | | | |
| 1/C13.1.3.1 | Excavating soft material situated within the following successive depth ranges: | | | |
| (a) | 0 m up to 1,5 m | m ³ | 20 | |
| (b) | > 1,5 m and < 3,0 m | m ³ | 24 | |
| (c) | Etc. in increments of 1,5 m | m ³ | 8 | |
| 1/C13.1.3.2 | Extra over subitem C13.1.3.1 for excavation in hard material irrespective of depth | m ³ | 40 | |
| 1/C13.1.3.3 | Extra over subitem C13.1.3.1 for additional excavation required by the Engineer after excavation is complete | m ³ | 5 | |
| 1/C13.1.4 | Excavation by labour enhanced methods: | | | |
| 1/C13.1.4.1 | Excavate in soft material situated within the following successive depth ranges: | | | |
| (a) | 0 m up to 1,5 m | m ³ | 240 | |
| 1/C13.1.4.2 | Extra over item C13.1.3.1(a) for excavation in intermediate material | m ³ | 20 | |
| 1/C13.1.4.3 | Extra over item C13.1.3.1(a) for additional excavation required by the Engineer after excavation is complete | m ³ | 40 | |
| 1/C13.1.8 | Backfill to excavations utilising labour: | | | |
| 1/C13.1.8.1 | Material from excavation | m ³ | 96 | |
| 1/C13.1.8.2 | Imported material (G7) | m³ | 246 | |
| 1/C13.1 | TOTAL CARRIED FORWARD | | | |
| 1/013.1 | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|--------------|--|--------------------|----------|--|
| | TOTAL BROUGHT FORWARD | | L | |
| 1/C13.1.9 | Fill within a restricted area (extra over item C5.2.2) | m ³ | 20 | |
| 1/C13.1.10 | Haul in excess of 1,0 km on excavated material and on material imported for backfill, foundation fill and fill for caissons | m ³ -km | 1800 | |
| 1/C13.1.12 | Overbreak in excavation in hard material: | m² | 15 | |
| 1/C13.1.14 | Foundation fill consisting of: | | | |
| 1/C13.1.14.1 | Rock fill | m ³ | 10 | |
| 1/C13.1.14.4 | Mass concrete (15/35) | m ³ | 10 | |
| 1/C13.1.14.5 | Concrete blinding (75mm Thick and Class 15/19) | m ³ | 21 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 1/C13.1 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-----------|---|------|----------|--|
| | PART 1: STC 4189 - 3/2.0 x 2.25m BOX CULVERT | | | |
| 1/C13.2 | FALSEWORK, FORMWORK AND CONCRETE FINISH | | | |
| 1/C13.2.2 | Vertical formwork to provide : | | | |
| | (a) Class F1 surface finish to: | | | |
| | (i) Floor slabs and cut-off walls | m² | 116 | |
| | (ii) Culvert walls | m² | 68 | |
| | (iii) Wingwalls | m² | 92 | |
| | (iv) Movement joints | m² | 7 | |
| | (v) Deck slab and headwalls | m² | 27 | |
| | (b) Class F2 surface finish to: | | | |
| | (i) Culvert walls | m² | 204 | |
| | (ii) Deck slab and wingwalls | m² | 107 | |
| 1/C13.2.3 | Horizontal formwork to provide | | | |
| | (a) Class F2 surface finish to: | | | |
| | (i) Deck slab | m² | 105 | |
| 1/C13.2.4 | Inclined formwork to provide | | | |
| | (a) Class F2 surface finish to: | | | |
| | (i) Underside of deck slab | m² | 91 | |
| | (ii) Culvert floor | m² | 25 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 1/C13.2 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-------------|---|------|----------|--|
| | PART 1: STC 4189 - 3/2.0 x 2.25m BOX CULVERT | | | |
| 1/C13.3 | STEEL REINFORCEMENT | | | |
| 1/C13.3.1 | Reinforcement for: | | | |
| 1/C13.3.1.1 | (1) Roof Slab | | | |
| | (b) High yield stress steel bars | t | 14 | |
| | (2) Floor Slab | | | |
| | (b) High yield stress steel bars | t | 16 | |
| | (3) Wingwalls | | | |
| | (b) High yield stress steel bars | t | 4 | |
| | (4) Culvert Walls | | | |
| | (b) High yield stress steel bars | t | 19 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 1/C13.3 | TOTAL CARRIED FORWARD TO SUMMARY | | 1 | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-------------|---|----------------|----------|--|
| | PART 1: STC 4189 - 3/2.0 x 2.25m BOX CULVERT | | | |
| 1/C13.4 | CONCRETE | | | |
| 1/C13.4.1 | Cast in situ concrete | | | |
| 1/C13.4.1.1 | Strength concrete (class 30/19): | | | |
| | (a) Roof Slab | m ³ | 28 | |
| | (b) Floor Slab | m ³ | 66 | |
| | (c) Wingwalls | m ³ | 21 | |
| | (d) Culvert Walls | m ³ | 41 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 1/C13.4 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-------------|--|------|----------|--|
| | PART 1: STC 4189 - 3/2.0 x 2.25m BOX CULVERT | | | |
| 1/C13.7 | JOINTS | | | |
| 1/C13.7.2 | Filled joints: | | | |
| 1/C13.7.2.1 | 25mm bituminous impregnated softboard | m² | 7 | |
| 1/C13.7.4 | Sealing joints with: | | | |
| 1/C13.7.4.1 | (a) Sikaflex PRO-3Wf or similar approved sealant (as shown on drawings): | m | 24 | |
| 1/C13.7.4.2 | (b) 300mm x 1.6mm galvanised mild steel strip (as shown on the drawings) | m | 24 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 1/C13.7 | TOTAL CARRIED FORWARD | | 1 | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|--------------|---|----------------|----------|--|
| | PART 1: STC 4189 - 3/2.0 x 2.25m BOX CULVERT | | | |
| 1/C13.8 | ANCILLARY STRUCTURAL ELEMENTS | | | |
| 1/C13.8.7 | Numbers for structures: (refer to drawings) | | | |
| 1/C13.8.7.2 | Painted numbers | No | 2 | |
| 1/C13.8.7.3 | Numbers formed in concrete | No | 2 | |
| 1/C13.8.8 | Cast in situ no-fines concrete (Class NF 19) | m ³ | 10 | |
| 1/C13.8.10 | Drainage pipes and weep holes: | | | |
| 1/C13.8.10.1 | Drainage pipes: | | | |
| (a) | M65 Netlon Pipes | m | 37 | |
| 1/C13.8.10.2 | Weep holes: | | | |
| (a) | Non Ferrous 50mm dia. | m | 21 | |
| 1/C13.8.12 | Synthetic-fibre filter fabric (Geotextile Grade A4) | m² | 23 | |
| 1/C13.8.14 | Crushed stone in drainage strips (20mm) | m ³ | 2 | |
| 1/C13.8.15 | Drainage strips (Netlon DN1 325mm wide) | m | 180 | |
| 1/C13.8.16 | Perforated drainage pipes: | | | |
| 1/C13.8.16.1 | Size (110mm diameter) and perforated pipe wrapped in synthetic – filter fabric as specified (Geotextile Grade A4.) | m | 50 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 1/C13.8 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-------------|---|----------------|----------|--|
| | PART 2: STC 3389 - 1/3.0 x 2.m BOX CULVERT | | | |
| 2/C13.1 | FOUNDATIONS | | | |
| 2/C13.1.3 | Excavation: | | | |
| 2/C13.1.3.1 | Excavating soft material situated within the following successive depth ranges: | | | |
| (a) | 0 m up to 1,5 m | m ³ | 20 | |
| (b) | > 1,5 m and < 3,0 m | m ³ | 65 | |
| (c) | Etc. in increments of 1,5 m | m ³ | 8 | |
| 2/C13.1.3.2 | Extra over subitem C13.1.3.1 for excavation in hard material irrespective of depth | m ³ | 30 | |
| 2/C13.1.3.3 | Extra over subitem C13.1.3.1 for additional excavation required by the Engineer after excavation is complete | m ³ | 5 | |
| 2/C13.1.4 | Excavation by labour enhanced methods: | | | |
| 2/C13.1.4.1 | Excavate in soft material situated within the following successive depth ranges: | | | |
| (a) | 0 m up to 1,5 m | m ³ | 645 | |
| 2/C13.1.4.2 | Extra over item C13.1.3.1(a) for excavation in intermediate material | m ³ | 65 | |
| 2/C13.1.4.3 | Extra over item C13.1.3.1(a) for additional excavation required by the Engineer after excavation is complete | m ³ | 40 | |
| 2/C13.1.8 | Backfill to excavations utilising labour: | | | |
| 2/C13.1.8.1 | Material from excavation | m ³ | 258 | |
| 2/C13.1.8.2 | Imported material (G7) | m ³ | 169 | |
| 2/C13.1 | TOTAL CARRIED FORWARD | | | |
| 2/013.1 | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|--------------|--|--------------------|----------|--|
| | TOTAL BROUGHT FORWARD | L | | |
| 2/C13.1.9 | Fill within a restricted area (extra over item C5.2.2) | m ³ | 20 | |
| 2/C13.1.10 | Haul in excess of 1,0 km on excavated material and on material imported for backfill, foundation fill and fill for caissons | m ³ -km | 700 | |
| 2/C13.1.12 | Overbreak in excavation in hard material: | m² | 15 | |
| 2/C13.1.14 | Foundation fill consisting of: | | | |
| 2/C13.1.14.1 | Rock fill | m ³ | 10 | |
| 2/C13.1.14.4 | Mass concrete (15/35) | m ³ | 10 | |
| 2/C13.1.14.5 | Concrete blinding (75mm Thick and Class 15/19) | m ³ | 9 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 2/C13.1 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-----------|---|------|----------|------|
| | PART 2: STC 3389 - 1/3.0 x 2.m BOX CULVERT | | | |
| 2/C13.2 | FALSEWORK, FORMWORK AND CONCRETE FINISH | | | |
| 2/C13.2.2 | Vertical formwork to provide : | | | |
| | (a) Class F1 surface finish to: | | | |
| | (i) Floor slabs and cut-off walls | m² | 80 | |
| | (ii) Culvert walls | m² | 94 | |
| | (iii) Wingwalls | m² | 53 | |
| | (iv) Movement joints | m² | 10 | |
| | (v) Deck slab and headwalls | m² | 32 | |
| | (b) Class F2 surface finish to: | | | |
| | (i) Culvert walls | m² | 94 | |
| | (ii) Deck slab and wingwalls | m² | 61 | |
| 2/C13.2.3 | Horizontal formwork to provide | | | |
| | (a) Class F2 surface finish to: | | | |
| | (i) Deck slab | m² | 69 | |
| 2/C13.2.4 | Inclined formwork to provide | | | |
| | (a) Class F2 surface finish to: | | | |
| | (i) Underside of deck slab | m² | 71 | |
| | (ii) Culvert floor | m² | 10 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 2/C13.2 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-------------|---|------|----------|--|
| | PART 2: STC 3389 - 1/3.0 x 2.m BOX CULVERT | | | |
| 2/C13.3 | STEEL REINFORCEMENT | | | |
| 2/C13.3.1 | Reinforcement for: | | | |
| 2/C13.3.1.1 | (1) Roof Slab | | | |
| | (b) High yield stress steel bars | t | 6 | |
| | (2) Floor Slab | | | |
| | (b) High yield stress steel bars | t | 7 | |
| | (3) Wingwalls | | | |
| | (b) High yield stress steel bars | t | 1 | |
| | (4) Culvert Walls | | | |
| | (b) High yield stress steel bars | t | 9 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 2/C13.3 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-------------|---|----------------|----------|------|
| | PART 2: STC 3389 - 1/3.0 x 2.m BOX CULVERT | | | |
| 2/C13.4 | CONCRETE | | | |
| 2/C13.4.1 | Cast in situ concrete | | | |
| 2/C13.4.1.1 | Strength concrete (class 30/19): | | | |
| | (a) Roof Slab | m ³ | 36 | |
| | (b) Floor Slab | m ³ | 53 | |
| | (c) Wingwalls | m ³ | 13 | |
| | (d) Culvert Walls | m ³ | 38 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 2/C13.4 | TOTAL CARRIED FORWARD TO SUMMARY | | 1 | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-------------|--|------|----------|--|
| | PART 2: STC 3389 - 1/3.0 x 2.m BOX CULVERT | | | |
| 2/C13.7 | JOINTS | | | |
| 2/C13.7.2 | Filled joints: | | | |
| 2/C13.7.2.1 | 25mm bituminous impregnated softboard | m² | 3 | |
| 2/C13.7.4 | Sealing joints with: | | | |
| 2/C13.7.4.1 | (a) Sikaflex PRO-3Wf or similar approved sealant (as shown on drawings): | m | 32 | |
| 2/C13.7.4.2 | (b) 300mm x 1.6mm galvanised mild steel strip (as shown on the drawings) | m | 32 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 2/C13.7 | TOTAL CARRIED FORWARD | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|--------------|---|----------------|----------|--|
| | PART 2: STC 3389 - 1/3.0 x 2.m BOX CULVERT | | | |
| 2/C13.8 | ANCILLARY STRUCTURAL ELEMENTS | | | |
| 2/C13.8.7 | Numbers for structures: (refer to drawings) | | | |
| 2/C13.8.7.2 | Painted numbers | No | 2 | |
| 2/C13.8.7.3 | Numbers formed in concrete | No | 2 | |
| 2/C13.8.8 | Cast in situ no-fines concrete (Class NF 19) | m ³ | 10 | |
| 2/C13.8.10 | Drainage pipes and weep holes: | | | |
| 2/C13.8.10.1 | Drainage pipes: | | | |
| (a) | M65 Netlon Pipes | m | 57 | |
| 2/C13.8.10.2 | Weep holes: | | | |
| (a) | Non Ferrous 50mm dia. | m | 32 | |
| 2/C13.8.12 | Synthetic-fibre filter fabric (Geotextile Grade A4) | m² | 36 | |
| 2/C13.8.14 | Crushed stone in drainage strips (20mm) | m³ | 2 | |
| 2/C13.8.15 | Drainage strips (Netlon DN1 325mm wide) | m | 125 | |
| 2/C13.8.16 | Perforated drainage pipes: | | | |
| 2/C13.8.16.1 | Size (110mm diameter) and perforated pipe wrapped in synthetic – filter fabric as specified (Geotextile Grade A4.) | m | 50 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 2/C13.8 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | | |
|-------------|---|----------------|------|--|
| | PART 3: STC 4191 - 1/1.8 x 1.8m BOX CULVERT | | | |
| 3/C13.1 | FOUNDATIONS | | | |
| 3/C13.1.3 | Excavation: | | | |
| 3/C13.1.3.1 | Excavating soft material situated within the following successive depth ranges: | | | |
| (a) | 0 m up to 1,5 m | m ³ | 20 | |
| (b) | > 1,5 m and < 3,0 m | m ³ | 16 | |
| (c) | Etc. in increments of 1,5 m | m ³ | 8 | |
| 3/C13.1.3.2 | Extra over subitem C13.1.3.1 for excavation in hard material irrespective of depth | m ³ | 10 | |
| 3/C13.1.3.3 | Extra over subitem C13.1.3.1 for additional excavation required by the Engineer after excavation is complete | m ³ | 5 | |
| 3/C13.1.4 | Excavation by labour enhanced methods: | | | |
| 3/C13.1.4.1 | Excavate in soft material situated within the following successive depth ranges: | | | |
| (a) | 0 m up to 1,5 m | m ³ | 155 | |
| 3/C13.1.4.2 | Extra over item C13.1.3.1(a) for excavation in intermediate material | m ³ | 20 | |
| 3/C13.1.4.3 | Extra over item C13.1.3.1(a) for additional excavation required by the Engineer after excavation is complete | m ³ | 10 | |
| 3/C13.1.8 | Backfill to excavations utilising labour: | | | |
| 3/C13.1.8.1 | Material from excavation | m ³ | 62 | |
| 3/C13.1.8.2 | Imported material (G7) | m ³ | 81 | |
| | | | | |
| 2/C13.1 | TOTAL CARRIED FORWARD | | | |

| ITEM NO | DESCRIPTION | | | | |
|--------------|--|--------------------|----------|--|--|
| | TOTAL BROUGHT FORWARD | | | | |
| 3/C13.1.9 | Fill within a restricted area (extra over item C5.2.2) | m ³ | 20 | | |
| 3/C13.1.10 | Haul in excess of 1,0 km on excavated material and on material imported for backfill, foundation fill and fill for caissons | m ³ -km | 500 | | |
| 3/C13.1.12 | Overbreak in excavation in hard material: | m² | 15 | | |
| 3/C13.1.14 | Foundation fill consisting of: | | | | |
| 3/C13.1.14.1 | Rock fill | m ³ | 10 | | |
| 3/C13.1.14.4 | Mass concrete (15/35) | m ³ | 10 | | |
| 3/C13.1.14.5 | Concrete blinding (75mm Thick and Class 15/19) | m ³ | 7 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| 3/C13.1 | TOTAL CARRIED FORWARD TO SUMMARY | L | <u> </u> | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-----------|--|------|----------|--|
| | PART 3: STC 4191 - 1/1.8 x 1.8m BOX CULVERT | | | |
| 3/C13.2 | FALSEWORK, FORMWORK AND CONCRETE FINISH | | | |
| 3/C13.2.2 | Vertical formwork to provide : | | | |
| | (a) Class F1 surface finish to: | | | |
| | (i) Floor slabs and cut-off walls | m² | 58 | |
| | (ii) Culvert walls | m² | 56 | |
| | (iii) Wingwalls | m² | 48 | |
| | (iv) Movement joints | m² | 3 | |
| | (v) Deck slab and headwalls | m² | 16 | |
| | (b) Class F2 surface finish to: | | | |
| | (i) Culvert walls | m² | 56 | |
| | (ii) Deck slab and wingwalls | m² | 53 | |
| 3/C13.2.3 | Horizontal formwork to provide | | | |
| | (a) Class F2 surface finish to: | | | |
| | (i) Deck slab | m² | 27 | |
| 3/C13.2.4 | Inclined formwork to provide | | | |
| | (a) Class F2 surface finish to: | | | |
| | (i) Underside of deck slab | m² | 28 | |
| | (ii) Culvert floor | m² | 15 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 3/C13.2 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-------------|--|------|----------|--|
| | PART 3: STC 4191 - 1/1.8 x 1.8m BOX CULVERT | | | |
| 3/C13.3 | STEEL REINFORCEMENT | | | |
| 3/C13.3.1 | Reinforcement for: | | | |
| 3/C13.3.1.1 | (1) Roof Slab | | | |
| | (b) High yield stress steel bars | t | 2 | |
| | (2) Floor Slab | | | |
| | (b) High yield stress steel bars | t | 3 | |
| | (3) Wingwalls | | | |
| | (b) High yield stress steel bars | t | 1 | |
| | (4) Culvert Walls | | | |
| | (b) High yield stress steel bars | t | 3 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 3/C13.3 | TOTAL CARRIED FORWARD TO SUMMARY | 1 | 1 | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-------------|--|----------------|----------|------|
| | PART 3: STC 4191 - 1/1.8 x 1.8m BOX CULVERT | | | |
| 3/C13.4 | CONCRETE | | | |
| 3/C13.4.1 | Cast in situ concrete | | | |
| 3/C13.4.1.1 | Strength concrete (class 30/19): | | | |
| | (a) Roof Slab | m ³ | 9 | |
| | (b) Floor Slab | m ³ | 20 | |
| | (c) Wingwalls | m ³ | 11 | |
| | (d) Culvert Walls | m ³ | 14 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 3/C13.4 | TOTAL CARRIED FORWARD TO SUMMARY | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|-------------|--|----------------|----------|------|
| | PART 3: STC 4191 - 1/1.8 x 1.8m BOX CULVERT | | | |
| 3/C13.7 | JOINTS | | | |
| 3/C13.7.2 | Filled joints: | | | |
| 3/C13.7.2.1 | 25mm bituminous impregnated softboard | m ² | 3 | |
| 3/C13.7.4 | Sealing joints with: | | | |
| 3/C13.7.4.1 | (a) Sikaflex PRO-3Wf or similar approved sealant (as shown on drawings): | m | 23 | |
| 3/C13.7.4.2 | (b) 300mm x 1.6mm galvanised mild steel strip (as shown on the drawings) | m | 23 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 3/C13.7 | TOTAL CARRIED FORWARD | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | |
|--------------|---|----------------|----------|--|
| | PART 3: STC 4191 - 1/1.8 x 1.8m BOX CULVERT | | | |
| 3/C13.8 | ANCILLARY STRUCTURAL ELEMENTS | | | |
| 3/C13.8.7 | Numbers for structures: (refer to drawings) | | | |
| 3/C13.8.7.2 | Painted numbers | No | 2 | |
| 3/C13.8.7.3 | Numbers formed in concrete | No | 2 | |
| 3/C13.8.8 | Cast in situ no-fines concrete (Class NF 19) | m ³ | 10 | |
| 3/C13.8.10 | Drainage pipes and weep holes: | | | |
| 3/C13.8.10.1 | Drainage pipes: | | | |
| (a) | M65 Netlon Pipes | m | 37 | |
| 3/C13.8.10.2 | Weep holes: | | | |
| (a) | Non Ferrous 50mm dia. | m | 21 | |
| 3/C13.8.12 | Synthetic-fibre filter fabric (Geotextile Grade A4) | m² | 23 | |
| 3/C13.8.14 | Crushed stone in drainage strips (20mm) | m ³ | 2 | |
| 3/C13.8.15 | Drainage strips (Netlon DN1 325mm wide) | m | 67 | |
| 3/C13.8.16 | Perforated drainage pipes: | | | |
| 3/C13.8.16.1 | Size (110mm diameter) and perforated pipe wrapped in synthetic – filter fabric as specified (Geotextile Grade A4.) | m | 50 | |
| | | | | |
| | | | | |
| | | | | |
| 3/C13.8 | TOTAL CARRIED FORWARD TO SUMMARY | | l | |

PART C4: SITE INFORMATION

TABLE OF CONTENTS

Page

| C4.1 | LOCALITY PLAN | C225 |
|------|---|------|
| C4.2 | EXAMPLE OF CONTRACT SIGNBOARD DETAILS | C226 |
| C4.3 | EXISTING SERVICES REPORT | C227 |
| C4.4 | CONDITIONS ON SITE: MATERIALS INFORMATION | C228 |
| C4.5 | TRAFFIC INFORMATION | C233 |

C4.1 LOCALITY PLAN

Main Road P8/3 is located in KZN436 within DC 43, where the start of the project is 4.5 km west of Creighton and traverses toward Riverside. Main Road P8/3 can be seen indicated in blue in **Figure C4.1**



Figure C4.1 – Locality Plan of Main Road P8/3

The approximate limits of construction can be seen in Table C4.1.


Table C4.1 – Approximate project limit of construction co-ordinates

| Km | Latitude | Longitude |
|------------------|----------------------|---------------|
| <u>Km 17.560</u> | <u>30° 2'4.16"S</u> | 29°47'37.04"E |
| Km 24.221 | <u>30° 3'19.90"S</u> | 29°44'20.91"E |

C4.2 EXAMPLE OF CONTRACT SIGNBOARD DETAILS

C4.2.2 CONTRACT SIGNBOARD FOR USE WHEN THE NYS PROGRAMME IS REQUIRED:

<u>Note:</u> The "S'hamba Sonke" logo, as indicated below, shall appear on the signboard for Provincial Road Maintenance Grant (PRMG) contracts only. In all other cases it shall be omitted.



C4.3 EXISTING SERVICES REPORT

1. C4.3.1. LOCATION OF SERVICES

The following services are scheduled for relocation under this contract:

It is also expected that unknown buried domestic services crossings requiring relocation or protection may be encountered along the route as the work proceeds. The Contractor shall therefore make every effort to establish the location of any such unknown services in a particular area prior to excavations commencing in that area. Such efforts shall include the Contractor conducting a thorough visual surface inspection for services which have not been shown on the drawings but which may be affected by the construction activities in that area, and any such services shall be brought to the attention of the Employer's Agent immediately. Exploratory hand excavation trenching work shall be carried out where necessary to establish the exact position of buried services.

The Contractor shall take note of the requirements of Chapter 2 of the standard specifications with regard to services.

C4.3.2. LIAISON WITH SERVICE OWNERS

Immediately after the site has been handed over to the Contractor and prior to the commencement of any construction work on the site, the Contractor shall arrange a meeting with the relevant authorities to establish the exact location of the various services affected (if any), to plan the necessary services relocations (if required) and to obtain contact details for the service owners' technical and emergency staff.

Where services relocations are required, the Contractor shall arrange regular planning meetings with the service owners until such time as the services have been relocated and commissioned and the existing services uplifted and removed.

C4.3.3. PROTECTION OF EXISTING SERVICES

Prior to the commencement of any construction work on the site, the Contractor shall establish markers at 50 m centres (or closer where necessary), clearly delineating the routes traversed by the services within the road reserve as confirmed by the service owners.

Excavation operations shall commence only after the existing services within or in the near vicinity of the excavations have been suitably protected against damage.

The Contractor shall take particular care when carrying out blasting, pneumatic or mechanical breaking, and general excavation operations in the vicinity of the services, and subcontractors, foremen and plant operators shall be fully briefed on precautionary measures to be taken before excavation commences in these areas.

C4.3.4. RELOCATION OF SERVICES

Should any services need to be relocated, the Contractor shall be required to assist the service owner with programming, organising and carrying out the relocation work, in order to minimise any delays in the construction.

C4.3.5. PAYMENT FOR THE SERVICE RELOCATION WORK

A provisional sum has been provided under Chapter 2.1 of the schedule of quantities to cover the costs of any protection, relocation, realignment, removal or replacement of services that may arise.

C4.4 CONDITIONS ON SITE: MATERIALS INFORMATION

CONTENTS

| C4.4.1 | DISCLAIMER | C229 |
|--------|-----------------------------|------|
| C4.4.2 | GENERAL DESCRIPTION OF ROAD | C229 |
| C4.4.3 | BORROW PIT INVESTIGATION | C231 |
| C4.4.4 | MATERIALS FOR CONSTRUCTION | C231 |

C4.4.1 DISCLAIMER

The information in this document records the results of investigations done and various tests carried out on materials encountered in the existing road. The results are given in good faith and there is no warranty that the results are entirely representative of all the materials that may be encountered, the intention being to give an indication of the materials likely to be encountered.

No responsibility for any consequence arising from variation between the actual material properties and those indicated in this document will be accepted.

The specification and contract drawings shall always overrule this part of the contract documents.

C4.4.2 GENERAL DESCRIPTION OF ROAD

Road P8/3 traverses hilly to mountainous terrain of rural area of KwaZulu-Natal between Creighton in the north east and Riverside in the south west. The total length of road P8/3 is approximately 20.0km.

The portion of the existing gravel road to be upgraded has a nominal width of 8.5 metres and the overall length is approximately 6.6 km.

The contract commences at km 17.560 at the intersection of Hlabeni and continues to km 24.221, which is the intersection of Kwashusha. There are numerous existing culverts crossing the road as well as an existing bridge that crosses the Mzimkhulu River and km 19.680.

Geology:

The road is underlined by Dolorite of the Beaufort Group formation of the Karoo Supergroup.

SGS Matrolab carried out a geotechnical investigation during March 2019. The investigation comprised the following:

- Ten (10) test pits on the road
- Stabilization design
- Testing of borrow pits
- Thirty (30) Dynamic Penetration Tests (DCP)

Samples of the layers were taken to determine the grading, Atterberg limits, CBR values and COLTO classification. The location of the test pits can be seen in **Figure C4.4.2.** The test pit results and DCP results are summarised in **Table 4.4.2A** and **Table 4.4.2B**



Figure C4.4.2 – Location of Test Pits

TABLE 4.4.2A: TEST PITS SUMMARISED RESULTS

| | | | LABORATORY TEST RESULTS | | | | | | | |
|------------|-------|------------|------------------------------|----|----|------|------|-----------|-------|----------------|
| TEST PIT | LAYER | DEPTH (MM) | DESCRIPTION | LL | PI | LS | GM | CBR | SWELL | CLASSIFICATION |
| 1 | 1 | 0-630 | CLAYEY SANDY GRAVEL | 30 | 14 | 7.0 | 2.46 | 16 @ 98% | 0.06 | G7 |
| | 1 | 0-150 | CLAYEY SANDY GRAVEL | 26 | 10 | 5.0 | 2.35 | | | NONE |
| 2 | 2 | 150-300 | CLAYEY SANDY GRAVEL | 33 | 15 | 7.0 | 1.80 | 20 @ 98% | 0.23 | G9 |
| 3 | 1 | 0-330 | CLAYEY SANDY GRAVEL | 34 | 14 | 7.5 | 1.76 | 5.9 @ 98% | 0.26 | NONE |
| 4 | 1 | 0-500 | CLAYEY SANDY GRAVEL | 38 | 14 | 7.0 | 2.26 | 4.0 @ 98% | 0.16 | NONE |
| | 1 | 0-210 | CLAYEY SANDY GRAVEL | 27 | 10 | 5.0 | 2.21 | 8.8 @ 98% | 0.14 | NONE |
| 5 | 2 | 210-400 | CLAYEY SANDY GRAVEL | 47 | 16 | 8.0 | 1.70 | 13 @ 97% | 0.49 | NONE |
| 6 | 1 | 0-270 | GRAVELY CLAYEY SAND | 40 | 18 | 9.0 | 1.33 | 3.1 @ 98% | 0.15 | NONE |
| 7 | 1 | 0-150 | GRAVELY CLAYEY SAND | 36 | 16 | 8.0 | 0.41 | 6.6 @ 98% | 0.17 | NONE |
| 7 | 2 | 150-400 | GRAVELY CLAYEY SAND | 26 | 12 | 6.0 | 0.94 | 18 @ 97% | 0.39 | NONE |
| | 1 | 0-200 | SANDY CLAYEY GRAVEL | 50 | 18 | 9.0 | 2.23 | 12@ 98% | 0.17 | NONE |
| 8 | 2 | 200-500 | SANDY CLAYEY GRAVEL | 48 | 20 | 10.0 | 1.76 | 16@ 97% | 0.42 | NONE |
| | 1 | 0-200 | CLAYEY SANDY GRAVEL | 35 | 12 | 6.0 | 2.21 | 21 @ 98% | 0.12 | G8 |
| 9 | 2 | 200-500 | CLAYEY SANDY GRAVEL | 30 | 14 | 7.0 | 2.13 | 11 @ 97% | 0.19 | NONE |
| | 3 | 500-900 | RESIDUAL CLAYEY SANDY GRAVEL | 36 | 16 | 8.0 | 1.37 | 11 @ 95% | 0.27 | NONE |
| 10 | 1 | 50-300 | GRAVELY CLAYEY SAND | 34 | 14 | 7.0 | 1.35 | 13 @ 98% | 0.12 | NONE |
| BORROW PIT | 1 | 0-400 | LIGHT BROWN | 34 | 16 | 8.0 | 2.60 | 12 @ 98% | 0.06 | NONE |

Most of the existing material did not obtain a classification as the material is to fine.

| POSITION | CBR @ 0.8M |
|------------------------|------------|
| BETWEEN TP 1 AND TP 2 | 33 |
| TP 2 | 13 |
| BETWEEN TP 2 AND TP 3 | 43 |
| TP 3 | 21 |
| BETWEEN TP 3 AND TP 4 | 28 |
| TP 4 | 50 |
| TP 5 | 43 |
| TP 6 | 29 |
| BETWEEN TP 6 AND TP 7 | 11 |
| BETWEEN TP 7 AND TP 8 | 18 |
| TP 8 | 12 |
| BETWEEN TP 8 AND TP 9 | 13 |
| TP 9 | 13 |
| BETWEEN TP 9 AND TP 10 | 39 |
| TP 10 | 170 |

TABLE 4.4.2B: DCP TEST RESULTS SUMMARISED

C4.4.3 BORROW PIT INVESTIGATION

An existing borrow pit is located approximately 5 km away from km 23.5. The testing of the borrow pit formed part of the geotechnical investigation done by SGS Matrolab. The borrow pit consist of G10 material which can be used as fill material. The existing borrow pit material is not acceptable for layer works. Layer works will have to be imported from commercial sources.

Alternative sources can be investigated by the appointed contractor.

The appointed contractor is required to submit all test results to the engineer for approval before any material is delivered to site.

C4.4.4 MATERIAL FOR CONSTRUCTION

C4.4.4.1 Selected subgrade and subbase layers

The material for the selected subgrade and subbase layers will be from commercial sources.

Alternative sources can be investigated by the appointed contractor.

The appointed contractor is required to submit all test results to the engineer for approval before any material is delivered to site.

C4.4.4.2 Crushed stone base

The G2 required for the construction of the crushed stone base shall be obtained from commercial sources.

There are two possible commercial sources for material, namely Ixopo Quarry and Midmar Crushers. The nearest commercial source Ixopo Quarry, located in Ixopo, is approximately 46 kilometres from the site and can supply material up to G2 material quality. Midmar Crushers, located outside Howick, is approximately 130 kilometres from the site and can supply material up to G2 material quality.

Alternative sources can be investigated by the appointed contractor.

The appointed contractor is required to submit all test results to the engineer for approval before any material is delivered to site.

C4.4.4.3 Concrete and surface seal aggregate, gabion stone and stone for erosion protection works

The appointed contractor is required to submit all test results to the engineer for approval before any material is delivered to site.

C4.4.4.4 Natural sand

The Contractor will have to make his own arrangements for the procurement of suitable sand for concrete, drainage and other construction purposes from commercial sources.

The appointed contractor is required to submit all test results to the engineer for approval before any material is delivered to site.

C4.4.4.5 Water

No specific source of water for construction purposes is identified. The Contractor will have to make his own arrangements in this regard. Water may be available from local rivers and streams, but the Contractor will have to make suitable arrangements for access as required as well as for the necessary testing to prove its suitability.

C4.5 TRAFFIC INFORMATION

C4.5.1 PROPOSED LAYERWORKS

The traffic counts obtained from the previous Traffic Study done by ILISO Consulting are summarised in **Table 5.1**.

Table 5.1 – Measure Traffic Counts

| MEASURED DAILY TRAFFIC (ADT) | | |
|------------------------------|-------------------------|--------------------------|
| YEAR | TOTAL VEHICLES (ADT) | HEAVY VEHICLES (ADTT) |
| 2012 | 133 | 37 |

A growth rate of 4% has been allowed for to the end of construction which is assumed 2022 after which the growth rate has been increased to 6% to allow for the additional traffic that is assumed to be generated due to the upgrade of the gravel road to blacktop. It is also assumed that the villages will generate more trips due to the upgraded road.

An average of 2.7 E80 axles per heavy vehicle has been used for the determination of the design traffic. Based on 137 E80's per day and a design life of 15 years, the total design E80's for the section of road is 1.4 million (ES 3).




Figure C4.5 – Figure showing location of traffic surveys.

The current traffic volumes over 7 days were obtained by means of loops at the 2 locations shown in **Figure C4.5**.

Just north of the P602 / R617 intersection the average daily traffic is some 323 vehicles/day, 17% of this

traffic being heavy vehicles whilst the corresponding figure on Provincial Road P602 just south of the P8/3 / P602 intersection is 265 vehicles/day, with 28% of this traffic being heavy vehicles.

C4.5.2 PROPOSED LAYERWORKS

The TRH4 was utilised as the basis for the proposed pavement layers. Utilising the traffic class of ES3 and the road category of C the TRH4 pavement layers consist of the following:

- 150mm G2
- 200mm C4
- 150mm G7
- 150mm G9
- 150mm G10

The above pavement layers were analysed using the Rubicon Mechanistic Pavement Design Software which takes into account the increased tyre pressures of 750kPa that was introduced after the TRH4 has been published. The TRH4 is based on tyre pressures of 520kPa. This indicated that the layerworks only had the structural capacity for 1 million E80's which is considerably lower than the required 1.4 million E80's. As such it the G7 subgrade was replaced with a G6 material which yielded a design capacity of 2 million axles.

It can be concluded that the pavement with the substitution of the G7 with G6 material will have sufficient structural capacity for the required E80's. It must also be said that no additional G9 layer will be required with the substitution

Based on this analysis, the layerworks will be as follows:

- 150mm G2
- 200mm C4
- 150mm G6

This can also be seen in Figure C4.5.3

ANNEXURE A: GUIDELINES FOR CONSTRUCTION AND MAINTENANCE PROJECTS DURING COVID-19 LOCKDOWN



transport

Department: Transport **Province of KwaZulu-Natal**

PROJECT SITE OCCUPATIONAL HEALTH AND SAFETY

GUIDELINES FOR CONSTRUCTION AND MAINTENANCE PROJECTS DURING COVID-19 LOCKDOWN

Revision 1/1 July 2020

Contents

| 1 | INTRODUCTION | C238 |
|------|--|------|
| 1.1 | BACKGROUND | C238 |
| 1.2 | PURPOSE | C239 |
| 1.3 | OBJECTIVES | C239 |
| 2 | RISK ASSESSMENT | C239 |
| 2.1 | BACK TO BASICS | |
| 2.2 | IMPLEMENTATION OF CONTROL MEASURES | C240 |
| 3 | SITE OPERATING PROCEDURES | C241 |
| 3.1 | SELF-ISOLATION | |
| 3.2 | IF SOMEONE FALLS ILL | |
| 3.3 | TRAVEL TO SITE | |
| 3.4 | SITE ACCESS POINTS | |
| 3.5 | HAND WASHING | |
| 3.6 | TOILET FACILITIES | |
| 3.7 | CANTEENS AND EATING ARRANGEMENTS | |
| 3.8 | CHANGING FACILITIES, SHOWERS AND DRYING ROOMS | |
| 3.9 | AVOIDING CLOSE WORKING | |
| 3.10 | GENERAL PRINCIPLES | |
| 3.11 | SITE MEETINGS | |
| 3.12 | CLEANING | |
| 4 | CONSTRUCTION PROTOCOLS | |
| 4.1 | PHYSICAL DISTANCING AND HYGIENE PROTOCOL | |
| 4.2 | SITE TRANSPORTATION PROTOCOL | |
| 4.3 | CLEANING PROTOCOL | |
| 4.4 | SCREENING AND MONITORING PROTOCOL | |
| | ONYMS | |
| KEY | TERMS & DEFINITIONS | C252 |
| | ENDIX A: SAFE PRACTICES ON SITE | |
| | ENDIX B: SUSPECTED OR CONFIRMED CASE OF COVID-19 | |
| | ENDIX C: COVID-19 DAILY SYMPTOM MONITORING TOOL | |
| APPE | ENDIX D: COVID-19 BASELINE RISK ASSESSMENT | C256 |

Content of Figures

| Figure 1: COVID-19 Alert Levels | C238 |
|--|------|
| Figure 2: Risk exposures | C239 |
| Figure 3: Infection control strategies | C240 |
| Figure 4: Symptoms of COVID-19 | C241 |

1 INTRODUCTION

Coronavirus Disease 2019 (COVID-19) is a respiratory disease caused by the SARS-CoV-2 virus. In order to reduce the impact of COVID-19 on businesses, workers, customers and the public, the Kwazulu-Natal Department of Transport (KZNDOT), within the parameters of the COVID-19 regulatory framework, want to ensure that all those businesses, workers, customers and public it's interacting with are in compliance to the requirements as stipulated to ensure a safe work-environment for all.

On 23 April 2020, President Cyril Ramaphosa addressed the nation and announced that the country would resume economic activity in a phased approach from 1 May 2020. The lockdown levels depicted by Figure 1 below, will be lifted in phases, level 5 the highest and level 1 being the lowest as depicted below:

| ALERT | ALERT | ALERT | ALERT | ALERT |
|---|---|---|--|---|
| LEVEL | LEVEL | LEVEL | LEVEL | LEVEL |
| 5 | 4 | 3 | 2 | 1 |
| Drastic measures to contain the spread of the virus and save lives. | Extreme precautions to limit community transmission and outbreaks, while allowing some activity to resume. | Restrictions on many activities, including at workplaces and socially, to address a high risk of transmission. | Physical distancing and restrictions on leisure and social activities to prevent a resurgence of the virus. | Most normal activity can resume, with precautions and health guidelines followed at all times. Population prepared for an increase in alert levels if necessary. |

Figure 1: COVID-19 Alert Levels

1.1 BACKGROUND

Occupational Health and Safety are a fundamental segment of the construction industry. Safety must be embedded in all processes, implementing a top down approach, enabling the adoption of a safe and healthy working culture by all. Individual businesses or workplaces must have COVID-19 risk assessments and prevention and mitigation plans in place, and must conduct worker education on COVID-19 and protection measures:

- Identification and protection of vulnerable employees
- Safe transport of employees
- Screening of employees on entering the workplace
- Prevention of viral spread in the workplace
- Hand sanitisers and face masks
- Cleaning of surfaces and shared equipment
- Good ventilation
- Shift arrangements and canteen controls
- Managing sick employees

In addition to the above, monitoring systems must be in place to ensure compliance with safety protocols and to identify infections among employees.

1.2 PURPOSE

This document sets out the key principles and minimum requirements of the KZNDOT that define responsible, healthy and safe operations for road construction related operations working under COVID-19 Lockdown. The present state of the lockdown is geared toward the revival of economic activities and to allow employees involved in permitted services to resume work under certain conditions. This COVID-19 guidance has been developed on the basis of traditional infection prevention and occupational hygiene practices.

1.3 OBJECTIVES

The aims of this document are to:

- Keep workers and the wider public healthy and safe by preventing the spread of COVID-19.
- Apply relevant guidance from the Department of Health, Department of Employment and Labour and other Government Authorities to the construction environment.
- Encourage a safe and respectful work environment and good communication between all stakeholders.
- Sit alongside existing health and safety controls to ensure workers are safe on site.

Contractors and their employees should use this guidance to help identify risk levels on construction sites and to identify any appropriate control measures to be implemented. Additional guidance may be needed as the conditions of the COVID-19 outbreak change and as new information about the virus, its transmission and impact become available. It focuses on, as well as considerations for, the need for contractors to implement engineering, administrative and work practice controls and personal protective equipment (PPE).

Frequency Risk factors HOST Nisk occupation Risk occupation Reservoirs ENVIRONMENT Controls Different workers have different risk exposures

RISK ASSESSMENT

The legislation governing workplaces in relation to COVID -19 is the Occupational Health and Safety Act, Act 85 of 1993, as amended, and with the Hazardous Biological Agents Regulations and the Construction Regulation 2014. Section 8(1) of the Occupational Health and Safety Act, Act 85 of 1993, as amended, requires the employer to provide and maintain a working environment that is, to the extent possible reasonably practicable, as amended. Specifically, Section 8(2)(b) requires steps that may be reasonably practicable to eliminate or mitigate any hazard or potential hazard prior to the use of personal protective equipment (PPE).

2.1 BACK TO BASICS

Risk Assessment should be done to determine the **RISK** of **EXPOSURE** and to communicate this to the **WORKERS**.

2

Figure 2: Risk Exposures

2.2 IMPLEMENTATION OF CONTROL MEASURES

Before the implementation of control measures, current risk assessments need to be reviewed and updated, taking into account the new hazards posed by exposure to COVID-19 in the workplace. This is in accordance with Section 8 (2) (d) of the OHS Act.

With COVID-19, it may not be possible to eliminate the hazard, the most effective protection measures are engineering controls, administrative controls, safe work practices (a type of administrative control), and Personal Protection Equipment.

Measures for protecting workers from exposure to, and infection with, SARS-CoV-2, the virus that causes Coronavirus Disease 2019 (COVID-19), depend on the type of work being performed and exposure risk, including potential for interaction with people with suspected or confirmed COVID-19 and contamination of the work environment.

Contractors should adapt infection control strategies based on a thorough hazard assessment, using appropriate combinations of engineering and administrative controls, safe work practices, and personal protective equipment (PPE) to prevent worker exposures.




Figure 3: Infection Control Strategies

In preventing occupational exposure to COVID-19 also require Contractors to train workers on elements of infection prevention, including PPE. This would assist Contractors to identify:

- Exposure Levels
- "High Contact" Activities, and
- Vulnerable Workers and Special Measures

Contractors are expected to undertake and champion the principles of constantly focussing on eliminating or reducing the risk of COVID-19 transmission to an acceptable level, engaging meaningfully with their workforce, and making worker health a key priority. A Baseline Risk Assessment is included under Appendix D: COVID-19 Baseline Risk Assessment.

3 SITE OPERATING PROCEDURES

KZNDOT Construction sites operating during the Covid-19 pandemic need to ensure that they protect their workforce and minimise the risk of infection spread. In line with government guidelines on social distancing, this guideline is intended to implement effective steps at all KZNDOT construction sites of any size. These are extraordinary situations, and the KZNDOT intends to abide to the latest COVID-19 advice from national government.

3.1 SELF-ISOLATION

Anyone who meets one of the following criteria should not come to site:

- Has a high temperature or a new persistent cough;
- Is a vulnerable person (by virtue of their age, underlying health condition, clinical condition or pregnancy); or
- Is living with someone in self-isolation or with a vulnerable person.

3.2 IF SOMEONE FALLS ILL

If a worker develops a high temperature or a persistent cough while at work, they should:

- Return home immediately;
- Avoid touching anything; and
- Cough or sneeze into a tissue and put it in a bin, or if they do not have tissues, cough and sneeze into the crook or into the bent elbow.




Figure 4: Symptoms of COVID-19

They must self-isolate and not return to work until their period of self-isolation has been completed and his or her negative status has been confirmed.

3.3 TRAVEL TO SITE

Wherever possible workers should travel to site alone using their own transport, and construction sites need to consider:

- Parking arrangements for additional cars, taxis, buses, etc;
- Other means of transport to avoid public transport e.g. cycling;
- They must ensure disinfecting the alternative transport before and after use; and Public Transport Regulations in respect of COVID-19 are adhered to;

- Providing hand cleaning facilities at entrances and exits. This should be soap, water and paper towels (and not fabric towels) wherever possible or hand sanitiser if water is not available; and
- How someone detected vulnerable after screening, taken ill and would get transported home.

3.4 SITE ACCESS POINTS

- Stop all non-essential visitors
- People, be it workers or visitors, without relevant face masks should not be allowed to enter construction sites; and workers should wear face masks at all times.
- Introduce staggered start and finish times to reduce congestion and contact at all times
- Monitor site access points to enable social distancing you may need to change the number of access points, either increase to reduce congestion or decrease to enable monitoring
- Remove or disable entry systems that require skin contact e.g. fingerprint scanners
- Require all workers to wash or clean their hands before entering or leaving the site or as frequent as possible
- Allow plenty of space (two metres) between people waiting to enter site
- Regularly clean common contact surfaces in Site Office, Access Control and delivery areas e.g. scanners, turnstiles, screens, telephone handsets, desks, particularly during peak flow times
- Reduce the number of people in attendance at site inductions and consider holding them outdoors wherever possible
- Drivers should remain in their vehicles if the load will allow it and must wash or clean their hands before unloading goods and materials.

3.5 HAND WASHING

- Provide additional hand washing facilities to the usual welfare facilities on a large spread out site or significant numbers of personnel on site
- Ensure soap, fresh water and paper towels is always readily available and kept topped up
- Provide hand sanitiser where hand washing facilities are unavailable
- Regularly clean the hand washing facilities and check soap and sanitiser levels
- Provide suitable and enough rubbish bins for hand paper towels with regular removal and disposal.
- Sites will need extra supplies of soap, hand sanitiser and paper towels and these should be securely stored.

3.6 TOILET FACILITIES

- Restrict the number of people using toilet facilities at any one time e.g. use a welfare attendant
- Wash hands before and after using the facilities
- Enhance the cleaning regimes for toilet facilities particularly door handles, locks and the toilet flush handles or buttons
- Portable toilets should be avoided wherever possible, but where in use these should be cleaned and emptied more frequently
- Provide suitable and sufficient rubbish bins for hand towels with regular removal and disposal.

3.7 CANTEENS AND EATING ARRANGEMENTS

Whilst there is a requirement for construction sites to provide a means of heating food and making hot drinks, these are exceptional circumstances and where it is not possible to introduce a means of keeping equipment clean between use, kettles, microwaves etc. must be removed from use.

The workforce should also be required to stay on site once they have entered it and not use local shops.

- Dedicated eating areas should be identified on site to reduce food waste and contamination
- Break times should always be staggered to reduce congestion and contact
- Hand cleaning facilities or hand sanitiser should be available at the entrance of any room where people eat and should be used by workers when entering and leaving the area
- The workforce should be asked to bring pre-prepared meals and refillable drinking bottles from home
- Workers should sit 2 metres apart from each other whilst eating and avoid all contact
- Where catering is provided on site, it should provide pre-prepared and wrapped food only
- Crockery, eating utensils, cups etc. should not be used
- Drinking water should be provided with enhanced cleaning measures of the tap mechanism introduced
- Tables should be cleaned between each use
- All rubbish should be put straight in the bin and not left for someone else to clear up
- All areas used for eating must be thoroughly cleaned at the end of each break and shift, including chairs, door handles, vending machines and payment devices.

3.8 CHANGING FACILITIES, SHOWERS AND DRYING ROOMS

- Always introduce staggered start and finish times to reduce congestion and contact
- Introduce enhanced cleaning of all facilities throughout the day and at the end of each day
- Consider increasing the number or size of facilities available on site if possible
- Based on the size of each facility, determine how many people can use it at any one time to maintain a distance of 1 ½ metres
- Provide suitable and enough rubbish bins in these areas with regular removal and disposal.

3.9 AVOIDING CLOSE WORKING

There will be situations where it is not possible or safe for workers to distance themselves from each other by 1.5 metres.

3.10 GENERAL PRINCIPLES

- Non-essential physical work that requires close contact between workers should not be carried out
- Work requiring skin to skin contact should not be carried out
- Plan all other work to minimise contact between workers
- Re-usable PPE should be thoroughly cleaned after use and not shared between workers
- Single use PPE should be disposed of so that it cannot be reused
- Stairs should be used in preference to lifts or hoists
- Where lifts or hoists must be used:
 - \circ $\;$ Always lower their capacity to reduce congestion and contact $\;$
 - o Regularly clean touchpoints, doors, buttons etc.
- Increase ventilation in enclosed spaces
- Regularly clean the inside of vehicle cabs and between use by different operators.

3.11 SITE MEETINGS

- Only absolutely necessary meeting participants should attend
- Attendees should be two metres apart from each other
- Rooms should be well ventilated / windows opened to allow fresh air circulation
- Consider holding meetings in open areas where possible.

3.12 SITE MEETINGS

Enhanced cleaning procedures should be in place across the site, particularly in communal areas and at touch points including:

- Taps and washing facilities
- Toilet flush and seats
- Door handles and push plates
- Handrails on staircases and corridors
- Lift and hoist controls
- Machinery and equipment controls
- Food preparation and eating surfaces
- Telephone equipment
- Keyboards, photocopiers and other office equipment

Rubbish collection and storage points should be increased and emptied regularly throughout and at the end of each day.

4 CONSTRUCTION PROTOCOLS

The core principle behind this "Construction Protocols" is to protect the health and safety of all workers required to perform duties during the COVID-19 crisis, including related health and safety impacts on operations related to operating under a COVID-19 environment, as well as protecting the wider KwaZulu-Natal population from transmission and spread of the virus.

| Before arriving on Site | | Each Contractor must have a plan detailing the steps they will take to mitigate risks, including those presented by COVID-19. The details of the plan must be communicated to workers before they start work. Before any activity is recommenced the Contractor must ensure that all hazards have been reviewed and appropriately controlled before work activity is commenced after lockdown. Where possible, conduct a remote induction before arrival on site, this can be done via video conferencing or by phone. If an in-person induction is required, the Physical Distancing and Hygiene Protocol must be followed. All workers shall undergo a screening process to ensure they are fit for duty by confirming their health status. Contractors must understand how workers will travel to and from site and will communicate the Site Transportation Protocol to all. Ensure all workers understand when additional PPE may be required due |
|-------------------------------|------------|--|
| | Site Entry | face masks or gloves please follow these processes. Only relevant personnel to the workplace are to access the site. All office employees supporting a project will work remotely, where possible. A daily register of workers entering and leaving site must be completed along with a health declaration. Use your existing sign in register or the example Sign-in register. Signage reminding workers of the COVID-19 Physical Distancing and Hygiene Protocol will be posted at the site entrance and in common areas where appropriate. |

| Site Operations | All work is to be undertaken in such a way as to reduce any possible contact between workers and to promote physical distancing wherever possible, as per the Physical Distancing and Hygiene Protocol. All visitors to the site, such as necessary delivery workers, will be restricted to one person wherever possible. These workers must follow the Site Transportation Protocol. All offices and jobsites must implement cleaning measures as per the Cleaning Protocol. All tools, equipment, plant and vehicles must be used in alignment with the Cleaning Protocol. Toolbox talks should be held with physical distancing in place as per the Physical Distancing and Hygiene Protocol. Additional sanitary measures are to be implemented on site to prevent the spread of COVID-19 e.g. hand washing stations, provision of additional hand sanitizer, provision of disinfectant wiping products, as per the Physical Distancing and Hygiene Protocol. Smokers must follow the Physical Distancing and Hygiene Protocol. A COVID-19 Response plan must be available and accessible on site. |
|--------------------|---|
| Leaving Site | Workers must use the sign-in register to sign out. When returning home, workers will need to follow the necessary hygiene measures. Each site must be cleaned and sanitised at the end of the working day or end of each shift, as per the Cleaning Protocol. All waste and disposable PPE must be removed from site and securely disposed of as per the Cleaning Protocol. Workers must follow the Site Transportation Protocol. |

4.1 PHYSICAL DISTANCING AND HYGIENE PROTOCOL

Physical distancing, also known as "social distancing", is about keeping a safe distance from others. For physical distancing, at least one and ½ metre's separation is required at work, and two metres in uncontrolled environments, like in public. This aligns with World Health Organisation advice. We expect one and ½ metre's separation between people at work as the minimum and greater separation where it is reasonably practicable to do so. This is important to help protect us from COVID-19, which spreads via droplets from coughing and sneezing.

| General Working Arrangements | Keep team sizes as small as possible. Keep a record of who is in each team every day as it is required to assist contact tracing. Site teams are encouraged to put forward split/alternating shifts to avoid extensive intermingling to reduce potential of exposure. Work site is always to be segregated into zones (or by other methods) as much as possible to keep different teams/trades physically separated. Where possible, a one-way system in high-traffic areas, such as lifts, stairwells and scaffolds (Where Applicable). Where practical, all office employees supporting a project, work remotely. When using a vehicle, the Cleaning Protocol needs to be followed. |
|------------------------------------|---|
| | When using a vehicle, the Cleaning Protocol needs to be followed. When using a vehicle, limit this to one/two person per vehicle if possible. |

| External Interfaces | One member of the crew nominated to receive supplies etc. Keep the engagement with the other person as brief as possible and maintain a two-metre physical distance. Ask for paperwork to be emailed rather than handed over as much as possible. If unavoidable, then either wear gloves when handling the item or wash hands before and after handling said items. |
|---------------------------|--|
| Site Entry | Limit visitors to site wherever possible. Introduce staggered start and finish times where possible to reduce congestion and contact. Monitor site access points to enable physical distancing – you may need to change the number of access points, increase to reduce congestion or decrease to enable monitoring. Where entry systems that require skin contact, the Cleaning Guide must be followed. Require all workers to wash or clean their hands before entering and leaving the site. Allow plenty of space 1½ metres between people waiting to enter site. Regularly clean common contact surfaces in reception, office, access control and delivery areas e.g. scanners, turnstiles, screens, telephone handsets, desks, particularly during peak flow times. Where possible, conduct a remote induction before arrival on site, this can be done via video conferencing or by phone. If an in-person induction is required, reduce the number of people and hold them outdoors wherever possible. Delivery drivers should remain in their vehicles if the load will allow it and must wash or clean their hands before unloading goods and materials. Any sign in registers should be recorded by one person where possible – |
| | do not pass material around the group and minimise contact with any screens. |
| Site Meetings | Only absolutely necessary meeting participants should attend. Attendees should be two metres apart from each other Rooms should be well ventilated / windows opened to allow fresh air circulation. Hold meetings in open areas where possible. Meetings are to be held through teleconferencing or videoconferencing where possible. |
| Avoiding Close Working | Risk assessments and method statements must be updated to include COVID-19 control measures. At least 1½ metre's separation is required at work. KZNDOT expect 1½ metre separation between people at work as the minimum and greater separation where it is reasonably practicable to do so. If it is not possible or safe for workers to distance themselves by one metre for a work activity, the works should not be carried out. Re-usable PPE should be thoroughly cleaned after use and not shared between workers. Single use PPE should be disposed of so that it cannot be reused. Stairs should be used in preference to lifts or hoists. Where lifts or hoists must be used: Lower their capacity to reduce congestion. Regularly clean touchpoints, doors, buttons etc. Increase ventilation in enclosed spaces |

| Toilet Facilities | Physical distancing rules apply to the use of shared facilities, including toilets. Wash hands before and after using the facilities. Enhance the cleaning regimes for toilet facilities particularly door handles, locks, toilet flush and sanitary bins. Provide suitable and sufficient rubbish bins for hand towels with regular removal and disposal. |
|--|--|
| Eating Measures | If you need to leave site for any reason, follow site entry procedures on return. Dedicated eating areas should be identified on site to reduce food waste and contamination. Break times should be staggered to reduce congestion and contact at all times. Hand cleaning facilities or hand sanitiser should be available at the entrance of any room where people eat and should be used by workers when entering and leaving the area. The workforce should be asked to bring pre-prepared meals and refillable drinking bottles from home. Workers should sit 2 metres apart from each other whilst eating and avoid all contact. Where catering is provided on site, it should provide pre-prepared and wrapped food only. Shared crockery, eating utensils, cups etc. should not be used. Tables should be put straight in the bin and not left for someone else to clear up. All areas used for eating must be thoroughly cleaned at the end of each break and shift, including chairs, door handles. Limit access and use of water fountains. Consider numbers on site for site facilities as physical distancing may require additional space/facilities. |
| Changing Facilities, Showers and Drying Rooms | Introduce staggered start and finish times to reduce congestion and contact at all times. Introduce enhanced cleaning of all facilities throughout the day and at the end of each day. Consider increasing the number or size of facilities available on site if possible. Based on the size of each facility, determine how many people can use it at any one time to maintain a distance of one metre. Provide suitable and sufficient rubbish bins in these areas with regular removal and disposal. |
| General Hygiene | Each worker must sanitise their hands with hand sanitiser or soap and running water before entry onto site, use warm water if available. Set up a specific place near the entry of the site for handwashing and/ or sanitising. Any personal items brought to site by workers must be segregated (kept separate from other workers items). Individual PPE for workers must be kept separate from other workers PPE and cleaned correctly as per the Cleaning Protocol. All eating and drinking utensils to be cleaned by the user. Have paper towels accessible to dry. |
| Smoking | Smokers/vapers must use designated area or do so off-site and butts are to be placed in the designated receptacle. Hands must be washed before and after smoking. Stand so that smoke or vapor produced is not going into another person's breathing zone. |

| Hand Washing | Provide additional hand washing facilities to the usual welfare facilities on large, spread out sites or significant numbers of personnel on site. Ensure soap and fresh water is readily available and kept topped up at all times. |
|--------------|---|
| | Provide hand sanitiser where hand washing facilities are unavailable. Regularly clean the hand washing facilities and check soap and sanitiser levels. Sites will need extra supplies of soap, hand sanitiser and paper towels and these should be securely stored. |

4.2 SITE TRANSPORTATION PROTOCOL

Employers are required to have an understanding of how workers will travel to and from site.

| Workers travel to site | for the second s | Workers are to travel to the site one person per vehicle where possible. |
|---|--|---|
| | + | Log is to be kept recording who has arrived on site, how they travelled and who they travelled with for contact tracing purposes. |
| | | Workers must travel home in the same vehicle as they arrived in. |
| | 5 | Handwashing protocols to be observed before entering site. |
| Any travel | *** | Allowing for spaces between passengers. |
| managed by the employer should ensure that | 5 | Hygienic washing of hands before and after the journey. |
| adequate steps can be achieved for this transport | | Follow Vehicle Cleaning Procedures as per the Cleaning Protocols. |
| which includes: | | Restricting equipment and baggage to trailers and or separate parts of the vehicle. |
| | †Ø | Deliveries to site should be delivered by one person only where possible. |
| Deliveries to site | 5 | Handwashing protocols to be observed once arrived at site. |
| | \neg | Sign-in register must be completed for persons delivering goods to site. |
| | 1 ··· • | 1,5 m physical distancing rules to be applied at all times. |

4.3 CLEANING PROTOCOL

Construction Sites operating under Coronavirus COVID-19 Lockdown need to ensure they are protecting their workforce and minimising the risk of spread of infection.

Key Cleaning Tips All construction sites (offices and jobsites included) should implement additional cleaning measures of common areas to help minimise the spread of COVID-19. Consider your work environment and what is frequently used and touched by workers, customers and others. The virus can be spread from person to person or by touching unclean equipment or surfaces. To stop the spread, focus efforts on cleaning areas where the virus is more likely to spread, such as the kitchen and toilet.

- Schedule regular cleaning.
- Use a suitable cleaning product.
- Use disposable cloths, if available.
- Always wear disposable gloves when cleaning. When finished, place used gloves in a rubbish bin.
- Wear disposable gloves while handling soiled items.
- Wash hands immediately after removing gloves or after handling these items.

Physical distancing should also be practiced when cleaning offices and jobsites. Refer to the **Physical Distancing and Hygiene Protocol** for more information.

every day with antiseptic wipes or disinfectant, including bleach solutions.

| Disinfecting Cleaning Aids | Cleaning aids, such as cloths or mops, must be germ-free or they'll spread germs to other surfaces. To help prevent the spread of germs: Use disposable cloths or paper towels when possible. Reusable cloths should be disinfected or washed after each use. Wash brushes in a dishwasher regularly or clean with detergent and warm water after each use. Use two buckets for mopping - one for detergent and the other for rinsing. Mops and buckets should be cleaned and dried after each use. |
|-------------------------------|--|
| Site Cleaning | Before leaving the jobsite at the end of the working day or end of each shift, wipe down any tables/surfaces with soapy water or cleaning agents where possible. All workers must be checked out of site and record kept daily. |
| | Common touch points may include: |
| | All waste and disposable PPE must be securely disposed of. All door handles, railings and personal workstation areas are wiped down with a disinfectant, such as disinfectant wipes. Individuals are responsible for cleaning their workstation area with disinfectant wipes. Clean all 'high-touch' surfaces such as desks, counters, tabletops, doorknobs, bathroom fixtures, toilets, light switches, phones, and keyboards |

| Cleaning Bathrooms, Toilets and Showers | Clean toilets with a separate set of cleaning equipment (disposable cleaning cloths, mops, etc). Clean sinks frequently if they're used regularly. If your jobsite has a shower: Clean shower trays frequently, if used regularly. If a shower has not been used for a while, let it run with hot water before using it. Keep tiles and grout in good condition. Clean shower curtains frequently. Common toilet touch points may include: Keep the U-bend and toilet bowl clean by flushing after each use. Limescale should be regularly removed using a descaling product. |
|--|--|
| Cleaning Tools and Equipment | Clean tools and equipment before and after each day's work with a disinfectant, concentrating on points of contact such as handles. Wash your hands after handling tools and equipment to prevent the spread of germs. If possible, don't share tools on-site. If sharing cannot be prevented, take precautions and follow the hand washing guide before and after each use. |
| Cleaning Vehicles | Have dedicated drivers when using vehicles to avoid the spread of germs. Don't share vehicles if possible, if you need to use a shared vehicle then wipe down the common touched areas of the vehicle after each use (steering wheel, handbrake, gear stick, dashboard, handles, etc) and wash hands before and after using the vehicle. Wipe down the inside and common touched areas of the vehicle before and after each day. Have one person per vehicle where possible. If you are required to have more than one person then keep as much distance between people as possible, open the windows to keep air circulating and passengers to face towards the window to reduce the spread of germs. If you need to have multiple people in a vehicle, then where possible, split teams into groups and stay in those groups when you travel together. |
| Cleaning PPE | Work clothes to be placed in washing machines and clean reusable PPE. Read and follow directions on the labels of laundry or clothing and detergent. In general, wash and dry laundry and clothing with the warmest temperatures recommended on the label. When handling soiled laundry wash your hands afterwards. All clothes and towels should be washed with a laundry product to prevent germs from spreading. Don't leave laundry in the washing machine – any remaining germs can multiply rapidly. |
| Specialist Clean | If a worker is unwell and removed from site, a specialist clean will be completed in the area/ areas identified where the worker was working and has accessed. These areas are to be isolated until a specialist clean has taken place. All equipment and vehicles used must be cleaned down and disinfected, concentrating on points of contact such as handles, steering wheels etc. |

4.4 SCREENING AND MONITORING PROTOCOL

Construction Sites operating under Coronavirus COVID-19 Lockdown need to ensure they are protecting their workforce and minimising the risk of spread of infection. Screening is a method to assess the possibility of employees and visitors who may have symptoms or have been infected with COVID-19. Rigid screening of employees must take place every day before they enter the workplace. This will be the most effective way to control the spread of the virus within the workplace.

| spread 0 | The virus within the workplace. |
|--|--|
| | Employees should be screened for COVID-19 related symptoms and report such symptoms to a designated person and / or occupational health practitioner prior to entry into the workplace or work area in order for a decision to be made as to the staff member's continued attendance at work. |
| During Screening | At the start of a workday/shift and prior to ending the workday/shift, designated persons and / or occupational health practitioner must check with employees whether they have experienced sudden onset of any of the following symptoms: cough, shortness of breath or fever/chills(or ≥ 38°C measured temperature if this is available at the worksite), in the past 24 hours as outlined in <i>Daily Symptom Monitoring Tool</i>. If an employee reports any of the above-mentioned symptoms, they should immediately be provided with a FFP1 surgical mask and referred to the designed of the surgical mask and referred to the surgical mask an |
| | designated staff at the workplace so that arrangements can be made for COVID-19 testing at the closest testing centre. If employee report any additional symptoms as outlined in the symptom monitoring sheet, s/he should be provided with a surgical mask and referred to the occupational health clinic, family practitioner or primary care clinic for further clinical evaluation and requirement for COVID-19 testing if indicated. On receiving their results, the employee and/or health professional supporting the employee should notify their workplace so that the employee is managed accordingly. The workplace should proactively take steps to obtain this information to avoid any delays in reporting. |
| After isolation or quarantine period | Undergo medical evaluation to confirm that they are fit to work Wearing of surgical masks at all times while at work for a period of 21 days from the initial test Implement social distancing measures as appropriate (in the case of health workers avoiding contact with severely immunocompromised patients) Adherence to hand hygiene, respiratory hygiene, and cough etiquette Continued self-monitoring for symptoms, and seek medical re-evaluation if respiratory symptoms recur or worsen |

"Appendix C: COVID-19 Daily Symptom Monitoring Tool" is a monitoring Tool to track construction workers on a daily basis for two weeks.

ACRONYMS

| PPE | Personal Protective Equipment |
|------|---|
| WHO | World Health Organization |
| NICD | National Institute of Communicable Diseases |
| RR | Residual Risk |
| OHSA | Occupational Health and Safety Act, 1993 (Act No. 85 of 1993) |

KEY TERMS & DEFINITIONS

| Contractor | Is defined as a person or company that arranges to supply materials or workers for building or for moving goods. |
|------------------------------------|---|
| Extremely Vulnerable Persons | Defined as someone who is solid organ transplant recipients; people with specific cancers: people with cancer who are undergoing active chemotherapy or radical radiotherapy for lung cancer; people with cancers of the blood or bone marrow such as leukaemia, lymphoma or myeloma who are at any stage of treatment; people having immunotherapy or other continuing antibody treatments for cancer; people having other targeted cancer treatments which can affect the immune system, such as protein kinase inhibitors or PARP inhibitors; people who have had bone marrow or stem cell transplants in the last 6 months, or who are still taking immunosuppressive drugs; People with severe respiratory conditions including all cystic fibrosis, severe asthma and severe COPD; People with rare diseases and inborn errors of metabolism that significantly increase the risk of infections (such as SCID, homozygous sickle cell); People on immunosuppression therapies sufficient to significantly increase risk of infection; Women who are pregnant with significant heart disease, congenital or acquired.) |
| Physical Distancing | Physical distancing, also known as "social distancing", is about keeping a safe distance from others. |
| Safe Work Practices | Safe work practices are types of administrative controls that include procedures for safe and proper work used to reduce the duration, frequency, or intensity of exposure to a hazard. |
| Screening | Screening is a way for health workers to find out if you may have COVID-19 or not. The health worker will ask you questions and scan your forehead to take your temperature. |
| Workplace | Workplace means any premises or place where a person performs work. |

APPENDIX A: SAFE PRACTICES ON SITE

| | Using Face M | asks on Site | |
|-------------|------------------------|---|--|
| 5 | Wash Hands First | Always make sure you wash your hands thoroughly before and after touching a mask. | |
| | Masks | There are many kinds of masks, depending on the task. | |
| (@) | The Right Side | There is a metal clip at the top of the mask. | |
| And. | Placement | Place the metal clip across the top of your nose. | |
| R Ch | Attach the Mask | Attach the mask by pulling the elastic bands over your ears. | |
| | Stretch Down | Stretch the mask down, so that it covers your chin. | |
| Ch | Adjust | Bend the metal clip around your nose so that it sits securely. | |
| BCR | Taking off the Mask | Pull the elastic bands away from your ears. | |
| ₹ S A | Disposal | Always place the used mask in a closed rubbish bin for secure disposal. | |

Using Face Masks on Site

Any time you are completing a manual task Use your usual work safety gloves

lf you are cleaning any surfaces Use disposable gloves for this and throw them in the bin when you finish cleaning



Avoid touching your face while wearing gloves

Remove your gloves and then wash your hands prior to eating, drinking or smoking/vaping



Practice good hand hygiene and good cough and sneeze etiquette while wearing gloves

APPENDIX B: SUSPECTED OR CONFIRMED CASE OF COVID-19

| If the suspe at work | ected or confi | rmed case of COVID-19 is | | ected or co ork when d | onfirmed case of COVID-19 iagnosed |
|-------------------------|----------------|---|-----|---------------------------|---|
| (@) | Isolate | Isolate the person from others and provide a disposable surgical mask, if available, for the person to wear. | K. | Inform | Call (<mark>Insert No</mark>). Follow the advice of health officials. |
| | Inform | Call (<mark>Insert No</mark>). Follow the advice of health officials. | ŤŤŤ | Identify | Identify who at the workplace had close contact with the infected person in the 24 hours before that infected person started showing symptoms. Send those people home to isolate. Allow employees to raise concerns. Clean the area where the |
| - | Transport | Ensure the person has transport to their home or to a medical facility | Es. | Clean | person was working and all places they have been. This may mean evacuating those areas. Use PPE when cleaning. |
| Es. | Clean | Clean the area where the person was working and all places they have been. This may mean evacuating those areas. Use PPE when cleaning. | | | Review risk management |
| † † † | Identify | Identify who at the workplace had close contact with the infected person in the 24 hours before that infected person started showing symptoms. Send those people home to isolate. Allow employees to raise concerns. | | Review | controls relating to COVID-19 and review whether work may need to change. Keep employees up to date on what is happening. |
| Es. | Clean | Clean the area where the person was working and all places they have been. This may mean evacuating those areas. Use PPE when cleaning. | | | |
| | Review | Review risk management controls relating to COVID-19 and review whether work may need to change. Keep employees up to date on what is happening. | | | |

APPENDIX C: COVID-19 DAILY SYMPTOM MONITORING TOOL

| | transport Department: Transport Province of KwaZulu-N | latal | cov | VID-19 DAILY SYN | ΙΡΤΟΜ Μ | IONITORING TO | OOL | | |
|---------------------------|---|------------------------|-----------------------|----------------------------|----------------------------|---------------------------|--------------------------|--------------------------------|---------------|
| Details of Worker | <u>r</u> | | | | Details of Pe | rson completing this form | Date completing form | g DD/MM/YYYY | |
| Identifier | Date of contact | DD/MM/YYYY | Place last contact | | Surname | | Name | | |
| Surname | | Name | - | | Role | | Facility name | | |
| Date of birth | DD/MM/YYYY | Age (Y) | Sex | M_F_ | Email address | | Telephone num | ber | |
| Healthcare worker | Y N If yes, fa | acility name | | | Next of kin deta | ails | | | |
| Contact number(s) | | Email | | | Next of Kin nan surname | ne and | Next of Kin co number | ntact | |
| Physical address | | | | | | | | | |
| House number | | Street | - | | Suburb | | Town | | |
| District | | Province | | | Patient traced | YONO | | | |
| Details of confirm | ned COVID-19 case (Comp | plete only if Applicab | le | | | | | | |
| Contact type ¹ | Close Casual | Relationship | - | | Name | Surname | | Date of Birth DD/MM/YYYY | |
| nstructions for | completion: Instruc | tions for comple | etion: Mar | k "Y" if symptom present a | nd "N" if not. If | any symptoms are prese | nt collect, conta | act (Insert No) immediately ar | nd make |
| mmediate arra | ngements for the col | llection of a com | bined nase | opharyngeal and orophary | ngeal swab. Ref | er to COVID-19 Quick Gu | ide on the NICD | website for additional detail | ls. Days post |
| exposure to cas | e. | | | | | | | | |

| xposure to cuse. | | | | | | | | | | | | | | |
|------------------------|------|---------|---------|---------|---------|---|---------|---|------|---------|---------|---------|---------|---------|
| DAY | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 |
| Date (DD/MM) | | | | | | | | | | | | | | |
| Measured body temp | | | | | | | | | | | | | | |
| Chills | | | □ Y □ N | | | | □ Y □ N | | | □ Y □ N | | □ Y □ N | □ Y □ N | □ Y □ N |
| Cough | □Y□N | | | | | | | | | □ Y □ N | | | □ Y □ N | □ Y □ N |
| Sore throat | □Y□N | | | | □ Y □ N | | □ Y □ N | | | □ Y □ N | | | □ Y □ N | □Y□N |
| Shortness of breath | □Y□N | □ Y □ N | □ Y □ N | □ Y □ N | □ Y □ N | | □ Y □ N | | □Y□N | □Y□N | □ Y □ N | □ Y □ N | □Y □ N | □Y□N |
| Myalgia/body pains | | | □ Y □ N | | □ Y □ N | | □ Y □ N | | | □ Y □ N | | □ Y □ N | □ Y □ N | □ Y □ N |
| Diarrhoea ³ | □Y□N | | □ Y □ N | □ Y □ N | □ Y □ N | | □ Y □ N | | | □ Y □ N | □ Y □ N | □ Y □ N | □ Y □ N | □Y□N |

¹ Close contact: A person having had face-to-face contact (<2 metres) or was in a closed environment with a COVID-19 case; this includes, amongst others, all persons living in the same household as a COVID-19 case and, people working closely in the same environment as a case. A healthcare worker or other person providing direct care for a COVID-19 case, while not wearing recommended personal protective equipment or PPE (e.g., gowns, gloves, NIOSH-certified disposable N95 respirator, eye protection). A contact in an aircraft sitting within two seats (in any direction) of the COVID-19 case, travel companions or persons providing care, and crew members serving in the section of the aircraft where the index case was seated. Casual contact: Anyone not meeting the definition for a close contact but with possible exposure. ² Chose from: Spouse, Aunt, Child, Class mate, Colleague, Cousin, Father, Friend, Grandfather, Grandmother, Healthcare worker taking care of, Mother, Nephew, Niece, Other relative, Uncle. 3 Diarrhoea defined as three or more loose stools in a 24-hour period.

APPENDIX D: COVID-19 BASELINE RISK ASSESSMENT

| | | | | | | | | | Likel | hood | | |
|--|---|---|------|---|---|---|--|--|-------|-------|------------|----------------|
| | | | | | | | Very Unlikely | Unlikely | Pos | sible | Likely | Very Likely |
| | | | | | | Negligible | 1 | 2 | | 3 | 4 | 5 |
| | | | | | ₹ | Minor | 2 | 4 | | 6 | 8 | 10 |
| | | | | | Severity | Moderate | 3 | 6 | | 9 | 12 | 15 |
| | | | | | Se | Major | 4 | 8 | | 12 | 16 | 20 |
| | | | | | | Extreme | 5 | 10 | | 15 | 20 | 25 |
| Hazard | L | S | Risk | Control Measures | | | | | | RR | | |
| Exposure from others due to: 1. Living with someone with a confirmed case of COVID-19. 2. Have come into close contact (within 2 metres for 15 minutes or more) with a confirmed case of COVID-19. 3. Being advised by a public health authority that contact with a diagnosed case has occurred. | | | | To follow government action of self following circumstances: for media supplies; for exercise once per day deemed 'key workers' Any existing individual risk assessme expectant mothers) to be reviewed Maintain contact with line manager follow company policy / guidance. Travel is only required for essentia public transport and to implement clearance from persons and not to the immediate family) To continue following ongoing governtian Stay at home and only attend host surgery and phone (Insert No) if furth Company to ensure extremely vulner following their specific medical advice Always follow good hygiene measure Avoid all visitors to your home unless Do not take any antibiotics as they do | al re r; and ments nent l trav t so ravel imen pital er ad cable e issu s they pack | eason; to shop d for essential a (disability, you and Human R rel; reduce the cial distancing in groups of m t guidance in an emergen vice is required persons are sh ed to them no la are providing a ages to be left o | o for nece works inclu ung person esources (I amount of where po nore than 2 cy. Do not ielding then ater than 29 medical re on the doors | essary food uding those as or new / HR) and to time using possible (2m unless it is attend GP mselves and p/3/2020 quirement | | | Individual | Workers |

| | | | | |] | | | | Like | elih | bod | | |
|--|---|---|------|--|---|--|---|---|------|------|-----|-----------|----------------|
| | | | | | | | Very Unlikely | Unlikely | P | ossi | ble | Likely | Very Likely |
| | | | | | | Negligible | 1 | 2 | | 3 | | 4 | 5 |
| | | | | | ₹ | Minor | 2 | 4 | | 6 | | 8 | 10 |
| | | | | | Severity | Moderate | 3 | 6 | | 9 | | 12 | 15 |
| | | | | | Se | Major | 4 | 8 | | 12 | | 16 | 20 |
| | | | | | | Extreme | 5 | 10 | | 15 | | 20 | 25 |
| Hazard | L | S | Risk | Control Measures | | | | | L | S | RR | | |
| Suspected case whilst working on site General travel including foreign travel | | | | If a worker develops a high temperature should: 1. Return home immediately 2. Avoid touching anything 3. Cough or sneeze into a tissue and p cough and sneeze into the crook of t 4. They must then follow the guidance their period of self-isolation has beer 1. Do not travel unless you cannot we implement teleconferencing for meet 2. Where an individual has recently visit isolate themselves until further notice continue to apply) 3. Please continue to follow any further 4. Where an occupational health (OH) seek additional advice or concerns the second provide their use of publice use private single occupancy where | out it i heir e on se ork fr ings ited th e fron natio servic roug trans possi | in a bin, or if the elf-isolation and pleted. om home or de nese countries, in the governme inal government is provider has h this service sport. Where trade | ey do not ha not return t eemed a ke they should nt (lockdow t advice pro- been appoir avel is esser | ave tissues, o work until ey worker – self / home n measures vided nted, please | | | | Individua | workers |
| Access / egress to site | | | | Where possible, please consider and implied 1. Stop all non-essential visitors Introduce staggered start and finish all times Monitor site access points to enable the number of access points, either to enable monitoring Remove or disable entry systems scanners Require all workers to wash or clean site | time socia incre that | s to reduce cor I distancing – y ase to reduce o require skin o | ngestion and ou may nee congestion o contact e.g. | d to change or decrease fingerprint | | | | Individua | workers |

| | | | | | 1 | | | | Lik | eliho | ood | | |
|--|---|---|------|---|---|---|---|--|-----|--------|------|------------|----------------|
| | | | | | | | Very Unlikely | Unlikely | Р | ossi | ible | Likely | Very Likely |
| | | | | | | Negligible | 1 | 2 | | 3 | | 4 | 5 |
| | | | | | ₹ | Minor | 2 | 4 | | 6 9 | | 8 | 10 |
| | | | | | veri | Moderate | 3 | 6 | | | | 12 | 15 |
| | | | | Minor 2 4 Moderate 3 6 Major 4 8 | | | | | | 12 | 2 | 16 | 20 |
| | | | | | | Extreme | 5 | 10 | | 15 | ; | 20 | 25 |
| Hazard | L | S | Risk | Control Measures | | | | | L | S | RR | Persons | at Risk |
| Inclement weather – cold temperature allows disease to | | | | Allow plenty of space (two metres) b Regularly clean common contact s and delivery areas e.g. scanners, desks, particularly during peak flow t Reduce the number of people in a holding them outdoors wherever pos Drivers should remain in their vehicl clean their hands before unloading g All persons to dress appropriately for Welfare facilities provided to shelter Maintain good hygiene measures at | urface, turr imes attence sible les if loods r the from | es in reception, nstiles, screens, dance at site in the load will allo and materials. weather the elements | office, acc telephone ductions ar | cess control e handsets, nd consider | | | | Individual | workers |
| survive | | | | Appropriate respiratory protective ed last resort however face fit test (I effectiveness. It is advised to speal matters and supplies should be r documented that supplies have beer | quipm FFT) k to y eserv | nent (RPE) masl must be comp your H&S comp red for medical | leted to er etent perso | nsure mask on on these | | | | | |
| Poor hygiene | | | | Wash your hands thoroughly and reseconds. Use alcohol-based hand and hand washing technique to be a and hand washing technique to be a Avoid touching your face/eyes/nose/cough or sneeze with a tissue then th Provide additional hand washing facespread out site or significant number Regularly clean the hand washing faces and disposal. Sites will need extra supplies of stress should be securely stored. | saniti dopte mout hrow ilities s of p cilitie sh bir | ser if soap and ed as directed h with unwashed it in the bin. to the usual we personnel on site s and check soa as for hand towe | water is n hands and lfare facilitie p and sanit ls with regu | ot available d cover your es if a large iser levels ılar removal | | | | Individual | workers |

| | | | | | 7 | | | | Lik | eliho | ood | | |
|--|---|---|------|--|--|---|---|--|-----|-------|-----|------------|----------------|
| | | | | | | | Very Unlikely | Unlikely | P | ossi | ble | Likely | Very Likely |
| | | | | | | Negligible | 1 | 2 | | 3 | | 4 | 5 |
| | | | | | iť | Minor | 2 | 4 | | 6 | | 8 | 10 |
| | | | | | Severity | Moderate | 3 | 6 | | 9 | | 12 | 15 |
| | | | | | s | Major | 4 | 8 | | 12 | | 16 | 20 |
| | _ | | | | | Extreme | 5 | 10 | | 15 | | 20 | 25 |
| Hazard | L | S | Risk | Control Measures7. Restrict the number of people usin | | | | | L | S | RR | Persons | at Risk |
| | | | | welfare attendant. Wash hands be the cleaning regimes for toilet facili toilet flush. Portable toilets should be use these should be cleaned and en | ties p be av nptied | articularly door oided wherever more frequently | handles, lo possible, b y. | cks and the out where in | | | | | |
| Canteen - exposure from large numbers of persons | | | | The workforce should also be require and not use local shops. Dedicated eating areas should be contamination Break times should be staggered to Hand cleaning facilities or hand sar any room where people eat and she leaving the area The workforce should be asked to drinking bottles from home Workers should sit 2 metres apart contact Where catering is provided on site, food only - Payments should be ta and Crockery, eating utensils, cups of mechanism introduced Tables should be cleaned between ea 10. All rubbish should be put straight in up All areas used for eating must be th and shift, including chairs, door devices. | identii reduc hitiser ould b to bri from it sho ken b ken b ketc. sl with e each u the bi horou | fied on site to r se congestion ar should be avail be used by work ng pre-prepared each other whil uld provide pre- by contactless of nould not be use nhanced cleanir use n and not left for ghly cleaned at | educe food ad contact a able at the kers when e d meals a st eating a prepared a card where ed ng measure r someone the end of | I waste and at all times entrance of entering and and refillable and avoid all and wrapped ver possible es of the tap else to clear each break | | | | Individual | Workers |

| | | | | | 1 | | | | | Likelihood | | | | |
|--|--------------|---|------|--|------------|----------|------------------|----------|----------|------------|------|--------|----------------|--|
| | | | | | | | Very Unlikely | Unlikely | Possible | | ible | Likely | Very Likely | |
| | | | | ity | Negligible | 1 | 2 | 3 | | | 4 | 5 | | |
| | | | | | Minor | 2 | 4 | 6 | | | 8 | 10 | | |
| | | | | | Severity | Moderate | 3 | 6 | 9 | | | 12 | 15 | |
| | | | | | Se | Major | 4 | 8 | 12 | | 2 | 16 | 20 | |
| | Extreme 5 10 | | | | | | | 10 | 15 | | 5 | 20 | 25 | |
| Hazard | L | S | Risk | Control Measures L S RR Persons at Risk | | | | | | | | | | |
| Use of Changing facilities, showers and drying rooms | | | | Introduce staggered start and finish times to reduce congestion and contact at all times Introduce enhanced cleaning of all facilities throughout the day and at the end of each day Consider increasing the number or size of facilities available on site if possible Based on the size of each facility, determine how many people can use it at any one time to maintain a distance of two metres Provide suitable and sufficient rubbish bins in these areas with regular removal and disposal. | | | | | | | | | | |