



KWAZULU-NATAL PROVINCE

TRANSPORT
REPUBLIC OF SOUTH AFRICA

DIRECTORATE:

Financial Services

Private Bag X9043, PIETERMARITZBURG, 3200

Inkosi Mhlabunzima Maphumulo House, 172 Burger Street, Pietermaritzburg, 3201

Tel: 033 355 8600 Fax: 033 355 8737

ADDENDUM NO. 01:

CONTRACT NO. ZNB01850/00000/00/HOD/INF/23/T

THE REHABILITATION OF MAIN ROAD P40 (KM 0.000 TO KM 1.800) IN THE AMAJUBA DISTRICT UNDER LADYSMITH REGION

Date Issued: 25/10/2023

This Addendum No. 01 comprises a total of **NINE (09) PAGES**, including this page.

The addendum serves to amend pages C36, C38, C40, C45, C48, C162 and C166 of the bill of quantities. Please amend the bill of quantities by replacing C36, C38, C40, C45, C48, C162 and C166 with C36A & C36B, C38A, C40A, C45A, C48A, C162A and C166A respectively.

The amendments required to the tender document are as follows:

Amendment No.	Amendment Required
1	Delete the Page C36 and replace with the new C36A & C36B.
2	Delete the Page C38 and replace with the new C38A.
3	Delete the Page C40 and replace with the new C40A.
4	Delete the Page C45 and replace with the new C45A.
5	Delete the Page C48 and replace with the new C48A.
6	Delete the Page C162 and replace with the new C162A.
7	Delete the Page C166 and replace with the new C166A.

Non-acknowledgment of this addendum will lead to disqualification.

The acknowledgment of this addendum must only be submitted with the bid document.

Should you have any queries with regards to the above, please contact Zamokuhle Mlondo or Sandile Nkala.

Yours faithfully

BSC CHAIRPERSON

I/We acknowledge receipt of this Addendum No.01 and have made the required alterations to our tender document.

BIDDER:.....

NAME OF SIGNATORY:.....

DATE:.....

**THE REHAB ON MAIN ROAD P40 (KM 0 TO KM 1.8) in the
Amajuba District under Ladysmith Region
SCHEDULE A: ROADWORKS**

SECTION 5.4

ITEM	DESCRIPTION	UNIT	QTY	RAT E	AMOUNT R : c
C5.4	STABILISATION				
C5.4.2	Chemical stabilisation				
C5.4.5	Cementitious stabilisation agents for pavement layers				
C5.4.5.1	Addition of cementitious stabilisation agents for pavement layers				
(a)	Cement (Base Layer) Ordinary Portland cement (2.50%)	T	300		
C5.4.7	Bituminous stabilisation of pavement layers				
C5.4.8.3	Foamed Bitumen (70/100pen 5% nominal)	L	140 000		
C5.4.14	Trial section for a chemically stabilised layer	m3	250		
Total Carried Forward To Summary (Page C40A)					

**THE REHAB ON MAIN ROAD P40 (KM 0.00 TO KM 1.80)
IN THE AMAJUBA DISTRICT UNDER LADYSMITH REGION
SCHEDULE A: ROADWORKS**

SECTION C5.5

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R : c
C5.5	RECONSTRUCTION OF PAVEMENT LAYERS				
C5.5.4	Sampling of in-situ material for mix design procedure	No	4		
C5.5.8	Pre-pulverising material in the existing pavement				
C5.5.8.1	Asphalt wearing course (120mm)	m3	1555		
C5.5.8.4	Stabilised gravel layer (specify nominal depth)	m3	4200		
C5.5.18.3	Foam stabilised base layer compacted to 102% of MDD:				
(d)	Using pre-pulverised material (as per item C5.5.8) compacted to 200 mm thick	m3	2590		
C5.5.21	Finishing the stabilised layer				
C5.5.21.1	Slush trial section with:				
(a)	Water	m2	13000		
(b)	Diluted emulsion	m2	13000		
Total Carried Forward To Summary (Page C40A)					

**THE REHAB ON MAIN ROAD P40 (KM 0.00 TO KM 1.80)
IN THE AMAJUBA DISTRICT UNDER LADYSMITH REGION
SCHEDULE A: ROADWORKS**

SECTION C9.1

ITEM	DESCRIPTION	UNIT	QTY	RAT E	AMOUNT R : c
C9.1	ASPHALT LAYERS				
C9.1.2	ASPHALT LAYERS				
C9.1.2.1	Construction of trial sections	m2	2000		
C9.1.3	Application of bond coat				
C9.1.3.2	Applied in restricted areas using a portable pressure sprayer	ℓ	825		
C9.1.4.2	Rehabilitation				
(a)	Continuously graded asphalt base 60mm thickness (26.5mm maximum aggregate size using 50/70 penetration grade bitumen (Incl. haulage)	t	2000		
C9.1.5	Asphalt layers (40mm and placed with paver)				
C9.1.5.1	Asphalt surfacing				
C9.1.5.1	New construction				
(a)	Stone skeletal mix - continuously graded as defined (40mm, 50/70 pen grade bitumen, design class 1/level 1 and hand/paper placing technique)	t	1500		
C9.1.13	Coring of asphalt layers				
C9.1.13.1	100 mm diameter	No	60		
Total Carried Forward To Summary (Page C40A)					



**PROVINCE OF KWAZULU-NATAL
DEPARTMENT OF TRANSPORT**

CONTRACT NO. ZNB01850/00000/00/HOD/INF/23/T: THE REHABILITATION ON MAIN ROAD P40 (KM 0.00 TO KM 1.80) IN THE AMAJUBA DISTRICT UNDER LADYSMITH REGION

SCHEDULE A: ROADWORKS

SUMMARY OF SECTIONS

CHAPTER	DESCRIPTION	FROM PAGE	AMOUNT
C1.2	GENERAL REQUIREMENTS AND PAYMENT	C29	R
C1.3	CONTRACTOR'S SITE ESTABLISHMENT AND GENERAL OBLIGATIONS	C31	R
C1.4	FACILITIES FOR THE ENGINEER	C32	R
C1.6	CLEARING AND GRUBBING	C34	R
C2.1	GENERAL REQUIREMENTS AND TRENCHING FOR SERVICES	C35	R
C5.4	STABILISATION	C36A	R
C5.5	RECONSTRUCTION OF PAVEMENT LAYERS	C36B	R
C8.1	PRIME COAT	C37	R
C9.1	ASPHALT LAYERS	C38A	R
C20.1	TESTING MATERIALS AND JUDGEMENT OF WORKMANSHIP	C39	R
	TOTAL CARRIED FORWARD TO TENDER SUMMARY (48)		R



KWAZULU-NATAL PROVINCE

TRANSPORT
REPUBLIC OF SOUTH AFRICA

THE REHAB ON MAIN ROAD P40 (KM 0.00 TO KM 1.80)
SCHEDULE F: CONTRACTOR PARTICIPATION GOALS

SECTION F1000

ITEM	DESCRIPTION	UNIT	LI	QTY	RATE	AMOUNT R: c
	Brought Forward					
F10.02	(vi) Procurement process for the totality of all tenders concluded for the appointment of CIDB contractor grading designation 6CE PE Targeted Enterprise subcontractors (1 x individual tenders prescribed, 40 copies of the tender document required for each individual tender) Construction Works for Targeted Enterprises	No		0.00		
	(a) Payments associated with the construction Works carried out by Targeted Enterprise subcontractors appointed in terms of Part F	PC Sum		1.00		5 243 626.29
	(b) Handling costs and profit in respect of subitem F10.02(a) above	%		5 243 626.29		
	(c) Supply of materials and small plant to assist Targeted Enterprise subcontractors appointed in terms of Part F	PC Sum		1.00		1 747 875.43
	(d) Handling costs and profit in respect of subitem F10.02(c) above	%		1 747 875.43		
F10.03	Contractors management fee for managing emerging contractors under CPG	Lump-Sum		1.00		
	Training of learners employed by Targeted Enterprise subcontractors:					
	(a) Generic Skills:					
	(i) Training Costs	PC Sum		1.00		800 000.00
	(ii) Handling Cost and profit in respect of subitem F10.03 (a)(i).	%		800 000.00		
	(b) Entrepreneurial skills					
	(i) Training Costs	PC Sum		1.00		600 000.00
	(ii) Handling Cost and profit in respect of subitem F10.03 (b) (i).	%		600 000.00		
Carried Forward						



**PROVINCE OF KWAZULU-NATAL
DEPARTMENT OF TRANSPORT**

CONTRACT NO. ZNB01850/00000/00/HOD/INF/23/T ZNT: REHABILITATION OF P40(KM 0.00 TO KM 1.80) IN THE AMAJUBA DISTRICT UNDER LADYSMITH REGION `

TENDER SUMMARY

DESCRIPTION	AMOUNT
Totals of Bill of Quantities brought forward:	
Schedule A: Roadworks (b/f from page C40A)	R
Schedule E: Expanded Public Works Programme (b/f from page C43)	R
Schedule F: Small Contractor Development (b/f from page C47)	R
SUBTOTAL 1	R
Add: Contingencies (10% of SUBTOTAL 1)	R
SUBTOTAL 2	R
Add: Contract Price Adjustment - CPA (8% of SUBTOTAL 2)	R
SUBTOTAL 3	R
Add: VAT (15% of SUBTOTAL 3)	R
TOTAL CARRIED FORWARD TO FORM OF OFFER C1.1.1	R

Signed on behalf of the Tenderer: (Signature)

Date:

Tenderer's Name: (Company Name)

**PROVINCE OF KWAZULU-NATAL
DEPARTMENT OF TRANSPORT****CONTRACT NO. ZNB01850/00000/00/HOD/INF/23/T: THE REHABILITATION ON MAIN ROAD P40 (KM 0 TO KM 1.8)****SCHEDULE F: SMALL CONTRACT DEVELOPMENT: CPG: F1000****SUMMARY OF SECTIONS**

CHAPTE R	DESCRIPTION	FROM PAGE	AMOUNT
C1.3	CONTRACTOR'S SITE ESTABLISHMENT AND GENERAL OBLIGATIONS	C152	R
C1.5	ACCOMMODATION OF TRAFFIC	C153	R
C1.7	LOADING AND HAULING	C154	R
C3.1	DRAINS	C155	R
C3.2	CULVERTS	C156	R
C3.3	CONCRETE KERBING AND CHANNELING, ASPHALT BERMS, CHUTES, DOWNPIPES, AS WELL AS CONCRETE, STONE PITCHED AND GABION LININGS FOR OPEN DRAINS	C157	R
C4.2	CUT MATERIALS	C159	R
C5.1	ROADBED	C160	R
C5.2	FILL	C161	R
C5.3	ROAD PAVEMENT LAYERS	C162A	R
C11.1	PITCHING, STONEMWORK, CAST IN SITU CONCRETE FOR PROTECTION AGAINST EROSION	C163	R
C11.6	ROAD SIGNS	C164	R
C11.7	ROAD MARKINGS AND ROAD STUDS	C165	R