



KWAZULU-NATAL PROVINCE

TRANSPORT
REPUBLIC OF SOUTH AFRICA

DIRECTORATE:

Private Bag X9043, PIETERMARITZBURG, 3200

Inkosi Mhlabunzima Maphumulo House, 172 Burger Street, Pietermaritzburg, 3201

Tel: 033 355 8600 Fax: 033 355 8737

Date: 12 January 2024

ADDENDUM NO. 1:

CONTRACT No. ZNB01615/00000/00/HOD/INF/22/T

THE CONSTRUCTION OF EARTHWORKS, LAYERWORKS, DRAINAGE AND SURFACING OF DISTRICT ROAD (D77) FROM KM 0.00 - KM 5.00 IN THE LADYSMITH REGION

This Addendum No. 1 comprises a total of **TWO PAGES**, including this page. The addendum serves to revise The Contract Section, Project Specification 1.5.2 on page C115 read "The Contractor is not required to carry out any demolition work to existing structures". The revised Contract section is included in this Addendum with the corrected specification which reads "The Contractor is required to carry out demolition work to existing structures".

The amendments required to the tender document are as follows:

Amendment No.	Amendment Required
1	On page C115: Project Specification 1.5.2 Demolition work "The Contractor is required to carry out demolition work to existing structures"

Non-acknowledgement of this addendum will lead to disqualification.

The acknowledgement of this addendum must only be submitted with the bid document.

Should you have any queries with regards to the above, please contact Shaun Tischendorf or Sandile Nkala.

Yours faithfully

.....
BSC: Chairperson

**PROVINCE OF KWAZULU-NATAL
DEPARTMENT OF TRANSPORT**

CONTRACT No. ZNB01615/00000/00/HOD/INF/22/T

**THE CONSTRUCTION OF EARTHWORKS, LAYERWORKS, DRAINAGE AND SURFACING OF
DISTRICT ROAD (D77) FROM KM 0.00 - KM 5.00 IN THE LADYSMITH REGION**

I / We acknowledge receipt of this Addendum No.1 and have made the required alterations to our tender documents.

BIDDER.....

NAME OF SIGNATORY.....

DATE.....

1.4 Extent of the Works

The Works to be carried out include the following main activities:

- (a) Establishment on site and clearing and grubbing.
- (b) Provision of traffic accommodation facilities.
- (c) Survey requirements.
- (d) Construction of all pavement layer to the top of the G2 base, including priming to protect the G2 layer.
- (e) Road prism drainage.
- (f) Construction of erosion protection measures (gabions, stone pitching, etc.)
- (g) Installation of guardrails.
- (h) Construction of culverts
- (i) Finishing and cleaning up of the road and road reserve.
- (j) Continuous quality control over materials and workmanship, and compliance with the Particular Specifications regarding environmental management and occupational health and safety, during all the above construction activities.
- (k) Removal of all site establishment facilities and constructional plant on completion of the Works.
- (l) Making good of any defects during the Defects Liability Period

1.5 Detailed description of the Works

The following description is a broad outline of the works and does not limit the work to be executed by the Contractor in terms of the contract. The description of some of the major items indicated in this section are indicative, not absolute, and are provided to define in general terms the overall scope of the project.

The Employer requires the Contractor to establish the necessary machinery, equipment, methodology and personnel to carry out the construction of D77, inclusive of, but not necessarily limited to the main activities mentioned in Section 1.4.

The approximate quantities of each type of work to be carried out in accordance with the contract documents are listed in the Schedule of Quantities on the following tables.

The site shall not only comprise the proclaimed road reserve but shall be extended in the broader sense to take account of all areas occupied by the Contractor, be it deliberate or unintentional, in the execution of the contract. The site includes all the land within the proclaimed limits of the road reserve along the extent of the works, borrow pits and quarry sites, stockpile areas, locations set aside for construction and supervision accommodation and any other location required for the execution of the Works.

Incidental intrusion into private or tribal property outside the road reserve shall not be permitted without the owner's written authority. Any such agreement reached with a private or tribal landowner (occupier) shall include the proviso that any material or equipment on that site shall remain the exclusive property of the Employer in terms of the contract.

1.5.1 Access to the Site

Refer to the locality plan contained in section C4: Site Information.

Access to the Site to be obtained from P160, Mizpah Road or P16 exiting Greytown

Throughout the duration of this contract, Main Road D77 shall be shared with other contractors engaged by the KwaZulu-Natal Department of Transport on this D77 project whose construction activities may affect access from time to time. The Contractor shall therefore be required to liaise on an ongoing basis with these other contractors with respect to access related matters throughout the duration of the contract.

1.5.2 Demolition work

The Contractor is required to carry out demolition work to existing structures.